1

מדינת ישראל

משרד ראש הממשלה

ארכיון המדינה

מושל מחוז השומרון - ממשלת א"י
נפת טולכרם

Water Supply - TulKarm
3rd Jacket
T/24/17
9/8/1946 - 21/6/1939

מס' תיק 4900/1


תיק מס' T/24/17

מכיל מס'

מחלקה

מדינת ישראל
גנזך המדינה

מ
ארץ ישראל
ממשלת המנדט



מזהה פיזי: מ - 4900/1
כתובת: 02-108-11-11-07
03/12/2003

~~1-5-6~~
~~1-6-6~~

~~T/25/20~~
T/24/17

WATER SUPPLY - TULKARM.

Closed See III Jacket

NO.T/24/17-162. 162

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

9th August, 1946.

Chairman,
Municipal Commission,
Tulkarm.

Sir,

I have the honour to refer to your letter No.81/5-A dated 7.8.46, and to our conversation of yesterday on this subject and shall be grateful if you will contact the British Commercial Agent first, as indicated in para 2 of Asst. Liaison Officer's letter No.H/1 of 29.7.46 which has been forwarded to you under my covering letter No. T/24/17-160 of 4.8.46.

161
158
160


I am, Sir,
Your obedient servant.

Assistant District Commissioner,
Tulkarm.

ARA/AT.

161

الرجاء ان تذكروا عند الاجابة
رقم 81/5-A



بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

طولكرم في 7th Aug. 1946.

Assistant District Commissioner
Tulkarm

Subject : Tulkarm Municipal Water Supply

Sir,

I have the honour to refer to Ag/Assistant Liaison Officer, Samaria District. letter No. H/1 dated 29.7.46 and draw your kind attention to the followings: 158

2. An agreement was signed between the Municipality and Mr. Burger, Mech. Engineer, Tel-Aviv. to import a plant to the Municipal Water Supply after been recommended by the Director of Public Works Department to carry on an agreement to the effect in accordance with his letter No. 5/5/7 dated 30th March 1946, from which I quote a paragraph in my previous letter.

3. Negotiations lasted a long time for the a/m plant, and now the plant has been already ordered from U.S.A. ; and the first instalment of its price has been covered. The plant is expected to be here in two months time Moreover if we are going to contact newly British Agents and Suppliers and negotiate with the competent authorities ,at least ayear will elapse till we reach an agreement.

4. Owing to extraordinary circumstances and ex post facto, thereupon please be kind enough to approve and approach the C. of Heavy Industries to issue an import licence. Obviously we shall keep in view in future to obtain our requirements and supply in the sterling area.

c.c. Lt for the Chairman to contact the British Commercial Agent first as per (159) AB 8/8

Yours faithfully

H. Jadjaan

Chairman, Municipal Commission
Tulkarm

on 162

NO. T/24/17-160.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

August, 1946.

Chairman,
Municipal Commission,
Tulkarm.

Subject:- Tulkarm Municipal Water Supply

Sir,

I have the honour to refer to your letter No. 81/5-1 dated 8.7.1946, and enclose herewith for necessary action, a copy of letter No. H/1 dated 29.7.46 from Ag/Assistant Liaison Officer, Samaria together with the relative forms.

I have the honour to be,
Sir,
Your obedient servant.

Assistant District Commissioner,
Tulkarm.

ARA/AT.

H/1. GOVERNMENT OF PALESTINE. 159

DISTRICT CONTROLLER'S OFFICES,
SAMARIA DISTRICT, NABLUS.
P.O.B. 34.
29 July, 1946.

Assistant District Commissioner,
~~Jenin.~~ Tulkarm

157

I have the honour to refer to your letter No.T/24/17-157 dated 9th July 1946 and regret to inform you that the Controller of Heavy Industries has been unable to issue an Import Licence for a deep well turbine pump on the U.S.A., as such pumps can be obtained in the sterling area.

The applicant should contact the British Commercial Agent, 11 Princess Mary Avenue, Jerusalem who can give him the names and addresses of firms able to supply.

An application should then be submitted to the Controller of Heavy Industries, through this office, on the attached forms, giving full particulars as required.


A Baker
Ag/ASSISTANT LIAISON OFFICER
SAMARIA DISTRICT.

ACB/RH.

Please see folios 144 to 155 it seems another delay. [initials] 2.8.46

c.c. Copy with these forms to the Chairman Municipal Council, Tulkarm.
[initials] 2/8
160

الرجاء ان تذكروا عند الاجابة
رقم 81/5-A



بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

158

طولكرم في 1st August 1946

Assistant District Commissioner
TULKARM

Subject : Water Supply
Ref: My letter No. 81/5-A dated 8/7/46

156

I have learnt from Mr.M. Burger Mec.Engineer with whom we have signed a contract for importing a pump and a motor for the Tulkarm water supply scheme, that he received information from the Controller of Heavy Industries to the effect that the import licence for the said motor and pump was rejected on the grounds that it is not essential.

I need not emphasize thar the motor and pump are indispensable for our water supply scheme for the correspondence which took place in the last 14 months bear enough evidence of its essentiality. I herby quote a paragraph from a letter by the Director of P.W.D. No. 557 dated 17/6/46 .

"The purchase of new plant appears justified having regard to : a- bad deterioration of the existing plant . b- wide fluctuations of water level which can not safely be dealt with by a horizontal pump . c- Lack of stand- by plant for a public supply"

I shall be most glad if you will kindly give this matter your special consideration and to approach the C of H. I. with the view of reconsidering his decision. Please explain to him that Tulkarm town is competely under threat of remaining without water at any moment as there exists only one worn out pump,and there is no other source for water except the only well which is now in use now by the Municipality.

Finally I hope you will kindly employ your good offices in convincing him to issue an import licence for the required plant.

Yours faithfully

H. Tawasi

Chairman, Municipal Commission
Tulkarm

160

NO. T/24/17-157.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE 157
TULKARM.

9 July, 1946.

Asst. Liaison Officer,
Nablus.

Subject:- Supply of Pump for Tulkarm Municipal Well.

The District Commissioner, Samaria, having approved the purchase of a Pomona Pump for the Tulkarm Municipal Water Supply the Chairman, Municipal Commission of Tulkarm has submitted the attached application for an Import Permit.

As the matter is one of extreme urgency I appeal that you give it your immediate support.

Taken by Mr Somerville. 5.9.47

Assistant District Commissioner,
Tulkarm.

Copy to: District Commissioner, Samaria
ref. his No. 515 dated 28.6.46. 153

157

JS/AT

[illegible]

[illegible]

[illegible]

9

[illegible]

[illegible]

[illegible]

[illegible]

The District Commissioner, [illegible], having approved the [illegible] for the [illegible] [illegible] [illegible] [illegible]

[illegible] I trust that you [illegible]

Assistant District Commissioner,
[illegible]


[illegible]
[illegible]

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٨١/٥-١

طولكرم في ٨/٧/١٩٤٦



سعادة مساعد حاكم اللواء في طولكرم المحترم

الموضوع :- الطحن في طولكرم

الاشارة :- كتابكم رقم طك/٤/١٧ تاريخ ٥/٧/١٩٤٦

انه عملاً بنصيحتكم قد اتصلت فوراً بالخواجه م. بورجر وعقدت معه الاتفاقية لتوريد طاحونة وموتور (اليومنا) لبلدية البلدة ودفعت له القسط الاول من قيمته وفقاً لقرار مجلس بلدية طولكرم رقم ٢٤ بتاريخ ٦/٧/١٩٤٦. وكما هو ملحوظ ان اسعار الطاحونات قد ارتفعت عند جميع الشركات والوكلاء بمعدل ٢٠ في المئة اما الخواجه بورجر فقد بقيت اسعاره حتى الآن على ما كانت عليه.

اقدم لسعادتكم طلبات رخصة الاستيراد راجياً تقديمها لمراقب الصناعات التقنين مع توصيتكم بسرعة اصدار الرخصة نظراً لحاجة مدينة طولكرم الملحة للموتور والطاحونة. وتفضلوا بقبول فائق الاحترام

[illegible]
رئيس لجنة بلدية طولكرم

مكتب مساعد حاكم اللواء بطولكرم   الرقم س/٢٤/٠١٧

٥/٧/١٩٤٦

سعادة رئيس لجنة بلدية طولكرم المحترم.

الموضوع. - الماء في طولكرم.

الاشارة. - كتابكم رقم ٥/٨٧ في ٢٩/٥/٤٦
و ٥/٨١ في ١٧/٦/٠٤٦.

انقل اليكم بطيه صورة جواب سعادة حاكم لواء السامرة
اني قد تأكدت لك محتويات كتابكم المرقم ٥/٨١ - ا المذكور
الى سعادة مدير الاشغال العامة.

انصحكم بسرعة انجاز تركيب المضخة الاضافية فيه.

وتفضلوا بقبول فائق الاحترام.

مساعد حاكم اللواء
بطولكرم

C.C.

(154

Ref 153

Pl. convey para 1 to Ch. O.S.C., Rn by phone with my compliments and the suggestion that he lose no time in implementing it.

[illegible] 4/7

Spoke with C.C. Tolkhana Municipality who in his turn informed the Ch. M.C. in his house.

He asked to send him a copy of page 153 for audit purposes. please

[illegible]
4.7.

to be trouble strictly
— went for an
ordinary police
station was posted
on the main
road but I
was to sketch
[illegible] to

Interviewed by

Action Taken by J. D. [illegible]

153

GOVERNMENT OF PALESTINE.

IN REPLY PLEASE QUOTE
No. 515

2 JULY 1946
KULKARM

DISTRICT COMMISSIONER'S OFFICES,
SAMARIA DISTRICT,
NABLUS.

28 June, 1946

Asst. Dist. Commissioner,
Tulkarm

---

p.148

With reference to your letter No. T/24/17-148 dated the 20th June, 1946, regarding the Tulkarm Municipal Water Supply I am willing to approve straight away the purchase of the new pump provided sufficient money has been included in the Estimates.

p.144

2. In this connection, however, I note that the Chairman has already complained that the water in the present well is impure (vide your letter No. T/24/17-144 dated the 6th June, 1946). I suggest that a consistent policy should be followed.

[signature]
Ag. DISTRICT COMMISSIONER
SAMARIA DISTRICT

NO.T/24/17-152.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

3 July, 1946.

Director of Pulic Works,
Jerusalem.

Subject:- Tulkarm Municipal Water Supply
Ref'nce:- Your No.5/5/7 dated 17.6.46.

The contents of your above were passed on to the Chairman, Municipal Commission of Tulkarm, who replies as follows:

" I have noted the contents of the Director of Public Work's letter. My attention was called to the fourth para which implies that the demand on the existing pump is not more than 400 m3 p.d. supplied by eight hours pumping. The fact is that the pump works sixteen hours p.d., and sometimes in excess of that, to keep up with the demand. I thus consider that the matter has become an exceedingly serious one due to the non-existence of any alternative supply should the machinery break down. In my opinion it is absolutely necessary to remedy the position with the utmost speed.

"2 I do not wish to argue the contents of the Director of Public Work's first paragraph about the yield of the well. I content myself with the short tests made by the Nablus Engineer. In any case it is not possible for us to depend on this well alone whatever the yield thereof for the following reasons:

a) A breakdown in the machinery may occur resulting in the Town being without water.

b) The well is exceedingly deep and the walls thereof are in poor condition as everyone who goes does it calls to our attention.

c) The water of the present well is contaminated and, despite treatment, is consistently adversely reported on by the P.H.D.

d) All experts who have been down the well advise us to bore another on a new site elsewhere in the town.

"3 I am thus wholly in favour of the Director of Public Work's proposal, in his fourth para, to replace the present machinery with a Vertical pump. The old machinery can then be repaired and held in reserve in case anything should befall the new installation, as is stated in the Director of Public Work's fifth para. We shall until such time as the new well is bored apply economy in the distribution of water keeping a safe ratio between the power of the machinery and the consumption. When we have the new well bored we can instal powerful machinery quite capable of fully supplying the town. The old well and its machinery can then either supplement the supply or simply be maintained and held in reserve.

"4 The present water requirements of the Town are estimated at 750 m3 p.d. which, it is believed, will rise to 1500 m3 p.d. in ten years time, the more so if the Municipal Commission encourages near by model vegetable farms to draw water from it.

[illegible].

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.
3 July, [illegible].

Director of Public Works,
Jerusalem.

Subject:- Tulkarm Municipal Water Supply
Reference:- Your No. [illegible]/5/7 dated 17.6.[illegible].

The contents of your above were passed on to the Chairman, Municipal Commission of Tulkarm, who replies as follows:

"I have noted the contents of the Director of Public Works's letter. My attention was called to the figure there which implies that the demand on the existing pump is not more than 400 [illegible] p.d. supplied by eight hours pumping. The fact is that the pump works sixteen hours p.d. and sometimes in excess of that, to keep up with the demand. I thus consider that the matter has become an exceedingly serious one due to the non-existence of any alternative supply should the machinery break down. In my opinion it is absolutely necessary to remedy the position with the utmost speed.

2. I do not wish to argue the contents of the Director of Public Works's first paragraph about the yield of the well. I am in agreement with the short tests made by the [illegible] Engineer. In any case it is not possible for us to depend on this well [illegible] whatever the yield thereof for the following reasons:

a) A breakdown in the machinery may occur, resulting in the town being without water.

b) The well is exceptionally deep and the walls thereof are in poor condition [illegible] to our attention.

c) The water of the present well is contaminated and, despite treatment, is occasionally adversely reported on by the [illegible].

d) All experts who have been down the well advise [illegible] elsewhere in the town.

3. I am [illegible] of the Director of Public Works's proposal, [illegible] the present machinery [illegible]. The old machinery can then be repaired and held in reserve in case anything should befall [illegible] Director of Public Works's first para. [illegible] the new well [illegible] the machinery [illegible] the new well [illegible] supplying the town. The [illegible] the machinery [illegible] supplement the supply or [illegible] and held in reserve.

4. The present water requirements of the town are estimated at [illegible] which, it is estimated, will rise to [illegible] p.d. in ten years time, the [illegible] Commission [illegible] from water [illegible].

" From the above it is clear that the present water, supply even with new machinery, is insufficient either at the moment or in the future. But we are obliged to instal new machinery and content ourselves with the output until we have bored a new well as I have pointed out above.

"5 It so happened that the electric current was cut this morning - 29.6.46 - Before two hours had passed the Municipal Offices were deluged with callers and telephone enquiries and people became panicky. We called for the P.E.C. maintenance men but they could not come because it was their Sabbath and because of the curfew imposed. It was the late afternoon before the pump worked again. This incident gave us a vivid picture of what would take place if a breakdown occurred.

"6 I ask your pardon if I press with all the strength I have for speed in the installation of the new machinery by permission being granted us to contact the approved firm directly and get the matter under way. Much time has been, practically, lost, and, with the coming of the heat and all that such entails, no time remains to be lost. Should it be considered that it is too much for the Municipal Commission of Tulkarm to carry out the above, we are prepared to authorize the P.W.D. to select the machinery it desires and put the matter through with the least possible delay, I am sure the gravity of the situation will be realized and the menace of the breakdown of the supply at any moment grasped. In fact should that occur I do not dare envisage what would be the result. I am profoundly hopeful that the matter will be taken up as one of immediate urgency and put in hand."

I endorse what the Chairman, Municipal Commission of Tulkarm, has said above. The telephone calls I, personally, received during the hectic few hours of the morning of Saturday the 29th June and the reports I received on the temper of the masses on the subject do, in my opinion, call for immediate action. As more than one put it: "With a budget of over LP.33.000 surely the Municipal Commission of Tulkarm can ensure a proper water supply."

Please help them to do so.

Assistant District Commissioner,
Tulkarm.

JS/AT

13 4/7

-2-

From the above it is clear that the present water supply even with new machinery is inadequate either at the moment or in the future. Are we not obliged to install new machinery and content ourselves with the present until we have bored a new well as I have pointed out above.

(b) It so happened that the electric current was cut this morning - 27.6.46 - before the boma had opened [illegible] Medical Officer came [illegible] with [illegible] and telephoned [illegible] about [illegible] people [illegible]. We called for the P.W.D. engineer and [illegible] could not [illegible] because it was [illegible] and [illegible] of the [illegible], it was the [illegible] afternoon before the [illegible] worked again. This incident gave me a vivid picture of what would take place if a breakdown occurred.

(c) I ask your pardon if I press with all the urgency I [illegible] for speed in the installation of the new machinery by [illegible] putting [illegible] to be [illegible] approve [illegible] directly and get the matter under way. Much time has been practically lost [illegible] with the [illegible] of the [illegible] and [illegible] time [illegible] to be lost, should I be [illegible] that it is [illegible] the Municipal Commission [illegible] are prepared to authorise the P.W.D. to select the machinery if desired and put the matter through with the [illegible] possible speed. I am sure the gravity of the situation will be realised and the chances of the total breakdown of the water supply at any [illegible] accepted. [illegible] should [illegible] I [illegible] the [illegible] would be [illegible]. I am profoundly hopeful that the matter will be taken up as one of immediate urgency and put in hand.

I suppose that the Chairman, Municipal Commission of [illegible] has said above. The telephone [illegible] I [illegible] received during the [illegible] the [illegible] of [illegible] and the [illegible] I received of the report of the [illegible] subject [illegible] for immediate action. [illegible] with a [illegible] of [illegible] funds the Municipal Commission of [illegible] can [illegible] a proper [illegible].

[illegible] with [illegible].

Assistant District Commissioner,
[illegible].

151

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٨١/٥ـ١

24/17

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
29 JULY 1946
received at 1345 P.M.

طولكرم في ٢٩/٦/٩٤٦م

سعادة مساعد حاكم اللواء بطولكرم المحترم

الموضوع :- مشروع الماء

الاشارة :- كتابكم رقم ط/٤/١٧ تاريخ ٢٥/٦/٩٤٦م . /150

اطلعت على كتاب سعادة مدير الاشغال المرفق بكتابكم وقد استرعى انتباهي الخاص ما جاء في الفقرة الرابعة منه وهو ان الحد الاقصى للمدة التي يصح فيها تشغيل آلات مشروع الماء هي ٨ ساعات في اليوم . وبما ان الآلات تشتغل في الواقع ١٦ ساعة في اليوم وكثيراً ما تتجاوز هذا الحد لكي تستطيع مجاراة الاستهلاك في الماء ، فاني ارى بان الموضوع اصبح جد خطير بسبب عدم وجود آلات احتياطية لسحب الماء في حالة توقف الآلات الحاضرة عن العمل وصار من الواجب المحتم معالجة الموضوع باقصى ما يمكن من السرعة .

٢ انني لا أود ان اجادل فيما جاء في الفقرة الاولى من كتاب سعادة مدير الاشغال عن قوة الماء في بئر البلدية بل اكتفي بالتجارب القصيرة التي عملت من قبل مهندس نابلسي لانه في أي حال لا يكون الاعتماد على هذا البئر وحده مهما بلغت قوة الماء فيه للاسباب التي بينتها في كتابي رقم ٨١/٥ تاريخ ١/١١/٩٤٥م وفي تقارير اخرى وخلاصتها أن البئر عميقة جداً وجدرانه بالية والنزول اليه خطر . ثم ان مياهه ملوثة بالجراثيم لوقوعه على خط المجاري العمومية . وجميع الخبراء الذين شاهدوا مشروع الماء اشاروا علينا بضرورة حفر بئر ثان في مكان آخر من المدينة . ولذلك فانني اوافق على اقتراح سعادة مدير الاشغال في البند الرابع من كتابه واستبدال الآلات الحاضرة بآلات عمودية نفس قوتها وتصليح الآلات القديمة وحفظها للاحتياط فيما اذا حصل تعطيل في الآلات الجديدة وفقاً لما جاء في البند الخامس من الكتاب المذكور . وانما سنراعي جانب الاقتصاد في توزيع الماء تبعاً لقوة الآلات التي تركب في البئر الحاضر الى حين أن نحفر البئر الجديد ونركب عليه آلات قوية تكفي بحاجة المدينة من الماء ونحتفظ بالبئر القديم وآلاته لنستعملها عندما يطرأ خلل على آلات البئر الجديد .

111

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ....

طولكرم في ....

٣ – يقدر الحد الأعلى لحاجة المدينة في الوقت الحاضر من الماء بنحو ٧٥٠ متراً مكعباً في اليوم ومن المتوقع ان يرتفع هذا الرقم الى ١٥٠٠ متر مكعب خلال عشر سنوات وعلى الأخص اذا شجعت البلدية انشاء مزارع جديدة للخضار في ضواحي المدينة ومدتها بحاجتها من الماء. ويتضح من ذلك أن البئر الحالي والآلات التي ستركب عليه لا تكفي لحاجة المدينة لا في الحاضر ولا في المستقبل. بيد اننا مضطرون كل الاضطرار لتركيب الآلات الجديدة فيه والقناعة بما يجود علينا من ماء للحاجات الرئيسية ريثما يتم المشروع الجديد كما بينت في البند السابق.

٤ – صدف أن قطع التيار الكهربائي عن آلات مشروع الماء هذا الصباح ولم تمض ساعتان حتى نفد الماء من الخزان واضحت المدينة بدون ماء فقامت ضجة الاهالي واشغلوا دائرة البلدية بالسؤالات المباشرة وبواسطة التلفون عن أسباب انقطاع الماء. لقد طلبنا من شركة الكهرباء لاصلاح الخلل ولكننا لا ندري ان كانوا سيحضرون بسبب عطلة السبت ومناسبة فرصة منع التجول هذا اليوم. اننا نستطيع ان ندرك حراجة الموقف فيما لو انقطع الماء لمدة طويلة قياساً عن الاستياء الذي تركه انقطاع الماء لفترات قصيرة.

٥ – استميح العذر اذا طلبت في الختام بكل الحاح سرعة البت في تركيب الآلات الجديدة للبئر وذلك باعطائنا تفويضاً للاتصال بالشركات من جديد اتصالاً مباشراً ومفاوضتها لتركيب آلات عمودية بقوة ٥٠ متراً مكعباً في الساعة والاتفاق مع من نجد شروطه أوفق من غيره لمصلحة البلدية من حيث جودة الآلات والسعر والمدة دون ما حاجة لتكليفهم تقديم العطاءات ثم عرضها على المجلس البلدي ومن بعده الى دائرة الاشغال وترقب صدور موافقتها واضاعة هذا الوقت الطويل دون جدوى لأن النتيجة التي سنصل اليها عن هذه الطريق الملتوية يمكننا أن نصل اليها أيضاً في أقصر وقت. وان حراجة الموقف تبرر لجوءنا الى هذا السبيل، بل انها تحتمه علينا تحتيماً.

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ....

طولكرم في ....

وأما اذا كان ذلك كثير علينا فاننا من جهتنا على استعداد تام لتفويض دائرة الاشغال العامة لتقوم هنا بهذه المهمة وتختار لنا الآلات حسب رأيها وكل ما يهمنا في الأمر أن نتوصل الى تركيب الآلات الجديدة بأقصى سرعة مستطاعة . ولي كل الثقة بانكم تقدرون روعنا من الخطر الجاثم الذي يهددنا بانقطاع الماء في كل لحظة وتشاطروننا قلقنا عن حالة المدينة وسكانها فيما اذا بقيت بدون ماء لمدة لا نستطيع حصرها لا سيما واننا لا ندري ماذا نفعل لمعالجة المشكلة اذا وقعت . وأملي وطيد بانكم ستضمون صوتكم الى صوتي والحاحكم الى الحاحي لعدم اضاعة أي وقت آخر بعمل كل ما هو في حيز الامكان لتركيب الآلات الجديدة في البئر الحاضر باقصر ما يمكن من الوقت . وللمباشرة بمفاوضة الشركات والمراجع المختصة لحفر البئر الثاني . وأرجوه تعالى ان يكون التوفيق حليفنا في هذه المرة وان لا تكون نصيب مساعينا الضياع هباءً منثوراً كما قدر لها ان تكون حتى الآن .

وتفضلوا بقبول فائق الاحترام

[signature]
رئيس لجنة بلدية طولكرم

150

مكتب مساعد حاكم اللواء بطولكرم

الرقم – ط/٢٤/١٧

٢٥/٦/١٩٤٦

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع = – مشروع الماء .

الاشارة . – كتابي رقم ط/٢٤/١٧ تاريخ ٨/٤/٤٦ .

1374

1377

أنقل اليكم بطيه صورة كتاب آخر ورد من سعادة مدير الأشغال في القدس وذلك ردا على كتابي الذى ارسلت اليه معه تفاصيل المعرض .

ألفت نظركم الى كون صاحب التوقيع المستر هولدز لا المستر كروك .


وتفضلوا بقبول الاحترام .

مساعد حاكم اللواء

بطولكرم

٢٦/٦

5/5/7.



PUBLIC WORKS DEPARTMENT
JERUSALEM.

149

17th June, 1946.

Assistant District Commissioner,
Tulkarm.

Subject :- Tulkarm Municipal Water Supply.

Reference:- Your T/24/17-133 of 23.3.46. and my 5/5/7 of 30.3.46.

133
134

Further to para.4 of my letter under reference I have to inform you that the short tests carried out by the District Engineer, Nablus District have shown the existing pumping plant to deliver an average of 47 cubic metres per hour only. No information is available that the well has ever yielded a larger quantity and the tests carried out so far by the District Engineer with the existing plant in the well has produced no evidence to suggest that $80m^3/h$ can be relied upon as a regular yield of this well.

2. I cannot therefore recommend the installation of a pumping plant of the proposed output of 80 cubic metres per hour for which you have obtained tenders, unless it has been ascertained by a proper 72 hours well test towards the end of the dry season that the well will be able to yield this increased quantity, and under which conditions regarding low water level.

3. The estimated cost of such a well test if carried out by a private contractor can be estimated only very roughly since the equipment available is not known. It should, however, be not higher than LP.250.- A P.W.D. test pump to augment the capacity of the existing one to an approximate total of $75\text{-}80m^3/h$ might be available towards the end of October, 1946. The cost of a test with this pump carried out by P.W.D. is estimated at LP.90.-

4. Should the demand made on the existing pumping plant in question be not more than that which can be met through a maximum of 8 hours run per day, i.e. 400 m^3 per day, replacement of the existing horizontal pump through a vertical one of equal output is recommended, and new tenders should be sent out asking for a vertical pumping plant to deliver $50m^3$ per hour against a total head of 120m. The purchase of new plant appears justified having regard to a) bad deterioration of the existing plant, b) wide fluctuations of water level which cannot safely be dealt with by a horizontal pump, c) lack of stand-by plant for a public supply.

See 152

5. The existing plant should, after installation of the new one, be completely overhauled and kept as an emergency stand-by.

6. I should like to stress the urgent necessity of ascertaining the maximum present and future ~~present~~ demands of the town before deciding whether the present output of the well will suffice, and before ordering new plant. If it can be shown that the present maximum demand of the town and also its future maximum demand is not likely to exceed the wells present <u>known</u> output then it would of course not be necessary to test the well.

E7. for

for ACTG. DIRECTOR OF PUBLIC WORKS

PUBLIC [illegible]

[illegible]

Subject :- [illegible]

Reference :- [illegible]

[illegible] of my letter [illegible] Public Lighting [illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

NO.T/24/17-148.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

20 June, 1946.

District Commissioner,
Samaria District.

Subject:- Tulkarm Municipal Water Supply.

The Chairman, Municipal Commission of Tulkarm writes as follows:

" The Water Supply Mechanic reports that the consumption of water in Tulkarm has so increased that the pump is now working practically continuously and that he notices that the motor is heating up. We fear that this may lead to the necessity of removing the motor for repairs when the water supply will, in consequence, be cut for about a week.

"2 You are aware that the said motor is the sole means of supplying water to Tulkarm town and that a breakdown will mean that Tulkarm will remain without water. As the Public Works Dept., have a reserve motor for emergencies, I request that they be addressed to hold it in readiness for Tulkarm when our machinery stops.

"3 The delay of the Public Works Dept. in deciding on the installation of a new pump and motor for our water supply lays us open continuously to the threat of the stoppage of the supply of water to the population. Has the time not come for the Public Works Dept. to pass its final opinion after the passage of one year since correspondence was started on 21/6/45 ? I request that they be pressed to make an early decision due to the gravity of the situation".

I would say in comment that the installation of a vertical pump to be used to relieve the present pump, and not to be run with it at the one time, is both reasonable and justifiable and sanction to proceed with such is strongly recommended.

Assistant District Commissioner,
Tulkarm.

20/6

See p 153

JS/AT

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الإجابة رقم ٨١/٥-١

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
44/17
18 JUNE 1946
TULKARM

طولكرم في ١٧/٦/١٩٤٦

سعادة مساعد حاكم اللواء بطولكرم المحترم

الموضوع: الماء في طولكرم

الاشارة: كتابكم رقم ٨٤/١٥٦ تاريخ ١٦/٧/١٩٤٥ 82

١- تقدم لي تقرير من ماكنست مشروع الماء يبين فيه ان استهلاك الماء في طولكرم قد ازداد الى حد كبير واصبح الموتور يشتغل باستمرار تقريباً وانه يلاحظ ارتفاعاً في درجة الحرارة بالموتور ويخشى ان يحتاج الامر الى اخراج الموتور من البئر وتصليحه وبذلك يتعطل سحب الماء من البئر لمدة اسبوعين تقريباً.

٢- تعلمون ان الموتور المركب في مشروع الماء هو الواسطة الوحيدة لتجهيز المدينة بالماء. واذا تعطل هذا الموتور عن العمل تبقى المدينة بدون ماء. وحيث انه يوجد لدى دائرة الاشغال العامة موتوراً احتياطياً للطوارئ فاني اجو مخابرة الدائرة المذكورة لتجهيز ذلك الموتور حتى يجري سحب الماء بواسطته حالما تتوقف آلات مشروع الماء عن العمل.

٢ ان تأخر دائرة الاشغال العامة في البت بموضوع تركيب موتور وطلمبة جديدة لمشروع الماء يجعلنا في دوام مهددين بانقطاع الماء عن السكان. اما الآن فالأولى ان تعطي دائرة الاشغال رأيها النهائي في الموضوع بعد مرور سنة على مخابرتنا الاولى من قبل الصدد بتاريخ ٢١/٦/١٩٤٥ رقم ٨٦ ش

ارجو لذا التأكيد عليهم للبت في الموضوع بوجه السرعة نظراً لخطورة الحالة

وتفضلوا بقبول فائق الاحترام

[illegible]
رئيس لجنة بلدية طولكرم

NO. T/24/17-146.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE 146

TULKARM.

19 June, 1946.

District Commissioner,
Samaria District.

Subject:- Tulkarm Municipal Water Supply. 145

Ref'nce:- Your No.515 dated 17.6.1946.

These were supplied to the Director of Public Works under my No.T/24/17-133 dated 23.3.46 and his reply, copy of which is attached received on the 4th April and immediately passed to the Chairman, Municipal Commission of Tulkarm. 134 137

Assistant District Commissioner,
Tulkarm.

JS/AT

145

GOVERNMENT OF PALESTINE.

IN REPLY PLEASE QUOTE

No. 515

DISTRICT COMMISSIONER'S OFFICES.
SAMARIA DISTRICT.
NABLUS.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
24/17
18 JUNE 1946

17 June, 1946

Asst.Dist.Commissioner,
Tulkarm. A.M

142

With reference to your letter No.T/24/17-142 dated the 29th May, 1946, regarding the Tulkarm Municipal Water Supply, I have the honour to enquire whether you have sent the quotations and specifications to the Director of Public Works for advice in connection with my letter No.515 dated the 19th March, 1946, and if so, whether you have received any reply from the Director. 132

P.P. 134 & 137

(Signed) [signature]
Ag.DISTRICT COMMISSIONER
SAMARIA DISTRICT

146

NO. T/24/17-144.

144

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

6 June, 1946.

District Commissioner,
Samaria District.

Subject:- Chlorination of Water at Tulkarm.

The Chairman, Municipal Commission of Tulkarm writes as follows:

" Prior to 1942 the Municipal Commission, of Tulkarm purified its water by the use of a powder which it secured from the P.H.D. It was then advised to instal a special plant to purify the water. This it did in mid 1942 and paid LP.160 to do so.

" After the installation of the apparatus, the results of water analysis by the P.H.D. showed that impurities remained. Up till now we nearly always receive reports that the water is impure, despite the improvements we have from time to time carried out to the apparatus.

" Nearly every month something goes wrong with the apparatus and we have to send parts to Jaffa for repair. During these periods, often a week long, the apparatus is not in use.

" The Municipal Commission incurs heavy expenses in the repair of this apparatus and yet despite these expenses the P.H.D. complains that the water remains impure.

" The well from which the water is drawn is near the main town sewer and the earth around it must, by now, be full of germs.

" For the above reasons it has now become necessary to hasten the boring of a fresh well on another site and to secure new purifying apparatus from Europe so that the purity of the water can be ensured.

" I ask for your approval of the boring of a new well and the securing of a new purifying apparatus".

I would comment as follows:

A new chlorinating apparatus is necessary and permission to purchase one as soon as possible is recommended.

Regarding the boring of a new well please see para 5 of your No. 515-4 dated 1st. Nov., 1945. /113

See p. 153

Assistant District Commissioner,
Tulkarm.

JS/AT

15/6/6

143

٥/٨٧
١٩٤٦/٥/٢٩

31. MAY

٤٤/١٧

سعادة مساعد حاكم اللواء في طولكرم المحترم.

الموضوع — تكرير الماء في طولكرم.

١: كانت بلدية طولكرم قبل سنة ١٩٤٢ تكرر المياه بواسطة مسحوق خاص تحصل عليه بإرشاد دائرة الصحة. ثم أشير علينا بأن نركب آلة خاصة للتكرير بواسطة محلول معلوم. وقد ركبت تلك الآلة في أواسط سنة ١٩٤٢ ودفعت نحو ١٦٠ مائة وستين جنيه.

٢: بعد تركيب تلك الآلة لم تكن نتائج فحص المياه في طولكرم من قبل دائرة الصحة مرضية. وفي أكثر الأحيان تأتينا التقارير بأن المياه ملوثة، ورغما عن الإصلاحات التي تدخل على الآلة لم تتحسن حالة المياه.

٣: لا يكاد يمر شهر إلا ويطرأ على الآلة خلل نضطر معه إلى إرسال قطع منها إلى يافا للإصلاح، وتبقى الآلة معطلة عن العمل لمدة أسبوع أو أكثر بينما تعود القطع بعد إصلاحها.

٤: تتحمل البلدية نفقات كثيرة في سبيل إصلاح آلة التكرير هذه. وعلى الرغم من تلك النفقات المستمرة لا تنفك دائرة الصحة عن الشكوى من عدم نظافة الماء.

٥: إن البئر الذي يسحب منه الماء يقع بالقرب من خط المجاري العمومية وقد أصبحت طبقات الأرض ملأى بالجراثيم مع مرور الزمن.

وللأسباب المبينة أعلاه أصبح من الضروري الإسراع بفتح بئر جديد في موقع آخر واستحضار آلة جديدة لتكرير الماء من أوروبا حتى نستطيع ضمان خلو الماء من الجراثيم بصورة ترضي دائرة الصحة. فأرجو صدور موافقتكم على فتح البئر الجديد، وعلى استحضار الآلة الجديدة للتكرير.

وتفضلوا بقبول فائق الاحترام.

رئيس بلدية طولكرم

نسخة لحضرة طبيب صحة طولكرم المحترم.

٤٤/١٧٧

NO. T/24/17-142.

142

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

29 May, 1946.

District Commissioner,
Samaria District.

Subject:- Tulkarm Municipal Water Supply.

The Chairman, Municipal Commission of Tulkarm writes as follows:

" Representatives of the P.W.D. came and inspected the well more than once. All assistance was given them to facilitate their work.

" We consider it very necessary to enter into an early contract with Mr. Burger, one of the two recommended by the Director of Public Works to supply and erect a new pump and motor, for consumption of water in Tulkarm is on the increase consistently and the present machinery has seen over eleven years service and can no longer be relied upon. This is the more so as the machinery in question is now working practically non-stop to supply the great demand for water. I believe you will share with me my opinion that the situation in Tulkarm would become disastrous should the present machinery stop working. And this is no longer a far fetched fear.

" The stoppage of the water supply in the town for one hour or two causes accusations to rain upon us from all sides. How then should the supply be cut off for days or weeks?

" I request the issue of your approval to enter into a contract to secure new machinery and to secure the necessary import licence".

Symapthetic consideration is urgently recommended.

Assistant District Commissioner,
Tulkarm.

JS/AT

E/295

[illegible]

Assistant District Commissioner's Office

[illegible]

4 [illegible], 194[illegible].

District Commissioner,

[illegible] District.

Subject.- [illegible]

[illegible] as follows:

[illegible]

[illegible]

[illegible]

[illegible]

Assistant District Commissioner,

[illegible]

141

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٨١/٥-١

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
27. MAY
TULKARM

طولكرم في ٢٧/٥/٩٤٦

سعادة مساعد حاكم اللواء لطولكرم المحترم

137

الموضوع :- مشروع الماء
الاشارة :- كتابكم رقم ط/٢٤/١٧ تاريخ ٨/٤/٩٤٦

حضر مندوبون عن دائرة الاشغال العامة للكشف عن البئر اكثر من مرة واحدة وقد قدمت اليهم كل المساعدات الممكنة لتسهيل مهمتهم وانا نجد من الضروري سرعة عقد الاتفاق مع الاخوين ب. بورجر احد الاثنين اللذين اوصى بهما جناب مدير الاشغال العامة من اجل توريد وتركيب موتور وطلمبة جديدين، لان استهلاك الماء في طولكرم بازدياد مضطرد والآلات الحالية مضت عليها اكثر من احدى عشرة سنة ولم يعد يستطاع الاعتماد عليها وعلى الاخص لان الآن تكاد تعمل بدون انقطاع لسد الحاجة الكبيرة للماء. اعتقد بانكم تشاركونني الرأي بان الحالة في طولكرم تصبح وخيمة جداً اذا توقفت آلات الماء الحاضرة عن العمل. وهذا الامر لم يعد بعيداً لاحتمال مطلقاً. ان انقطاع الماء في المدينة لساعة واحدة او ساعتين يجعل الشكاوى تتدفق علينا من كل صوب فكيف اذا انقطع الماء لعدة ايام او اسابيع!

أرجو صدور موافقتكم على عقد الاتفاقية لتوريد الآلات الجديدة والحصول على رخصة الاستيراد اللازمة.

وتفضلوا بقبول فائق الاحترام

[توقيع]

رئيس لجنة بلدية طولكرم

[illegible]

[illegible] ٢٧ [illegible] ١٩١١

[illegible]

[illegible]

[illegible] ١٩١١

[illegible]

[illegible]

[illegible]

NO. T/24/17-140.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE

TULKARM.

11 May, 1946.

District Engineer,
P. W. D.,
Nablus.

Subject:- Tulkarm Municipal Water Supply - Depth of Present Well.

Mr. Town of your Dept. called at my Office yesterday and asked me whether I could trace from our files the correct depth of the present Municipal Well at Tulkarm.

I informed him that all files prior to 1938 had been destroyed and that I could hold out no hope of finding what he desired.

In looking over my file I see that I had applied to you once before - my T/156/66 dated 26.1.45 to which you replied in your No. 3/1/2 dated 30.1.45 - for such back papers and wonder whether you can, from your files, supply the information requested.

Assistant District Commissioner,
Tulkarm.

JS/AT

NO.T/24/17-139.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE

TULKARM.

139

5 April, 1946.

District Commissioner,
Samaria District.

Subject:- Tulkarm Municipal Water Supply.

Ref'nce:- Your No.515 dated 3.4.1946. 135

The Chairman, Municipal Commission of Tulkarm writes as follows:

"The Municipal Engineer is exceedingly surprised at the allegation of the Public Works Department that he refused to give assistance in examing the water scheme at Tulkarm. Whenever he was informed that a Public Works Department representative was coming to inspect the well, he presented himself at the appointed time to meet and assist him although he was not told of the nature of the work the representative wished to carry out.

"Sometimes he awaited and the representative did not come and at times he heard of the postponement of the representative's coming.

"What I know is that the Municipal Engineer has not even once shown his lack of desire to coöperate with the Public Works Department or any others whether in the matter of the water supply or another even having no connection with Municipal works.

"The Engineer is still prepared to carry out all requests".


Assistant District Commissioner,
Tulkarm.

JS/AT

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٨١/٥



طولكرم في ١١/٤/١٩٤٦

P. 136

سعادة مساعد حاكم اللواء لطولكرم المحترم

الموضوع :- الماء لمدينة طولكرم

الاشارة :- كتابكم رقم ط/٢٤/١٧ تاريخ ٦/٤/١٩٤٦

يستغرب مهندس البلدية كل الاستغراب من ادعاء دائرة الاشغال العامة بأنه رفض تقديم اية مساعدة في سبيل فحص مشروع الماء في طولكرم لأنه كلما أخذ علماً بأن مندوباً عن دائرة الاشغال سيحضر للكشف على البئر كان يذهب في الوقت المعين للمقابلة والتعاون معه ولو أنه لم يكن يأخذ أية معلومات عن نوع العمل الذي سيقوم به المندوب وكان في بعض الاحيان ينتظر دون أن يصل المندوب وتارة يصله خبر تأجيل موعد الفحص .
والذي أعرفه أن مهندس البلدية لم يظهر مرة واحدة عدم رغبته في التعاون مع دائرة الاشغال العامة او مع غيرها سواء كان ذلك في موضوع مشروع الماء أو في خلافه من المواضيع ولو لم يكن له صلة في أعمال البلدية . ولا يزال مهندس البلدية على استعداد لكل عمل يكلف به .

وتفضلوا بقبول فائق الاحترام

[توقيع]
رئيس لجنة بلدية طولكرم

39

137

مكتب مساعد حاكم اللواء بطولكرم

٨/٤/١٩٤٦

الرقم — ص/٢٤/١٧

By Hand

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع :- مشروع الماء .

128 134

أشير الى كتابكم المرقم ٨١/٥ — أ والمؤرخ ٤/٣/١٩٤٦ وأنقل اليكم بطيه صورة كتاب ورد من سعادة مدير دائرة الاشغال العامة في الموضوع مع محتوياته .

أنصحكم قبل عقد أي مقاولة أن تؤمنوا ما جاء في المادة ٤ من التحرير عن قوة النبع في المشرع تجهيز ٨٠ م٣ في اليوم وذلك بدعوة مهندس الاشغال في نابلس وتقديم كل مساعدة ممكنة اليه في الكشف الذي كلف باجرائه من قبل مديرية الاشغال في القدس .

وتفضلوا بقبول الاحترام .

مساعد حاكم اللواء

بطولكرم

ارسل بالبريد محمد زيدى
٢٠/٤

136

مكتب مساعد حاكم اللواء بطولكرم

الرقم – ط/٢٤/١٧

٦/٣/١٩٤٦

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع = – الماء لمدينة طولكرم .

135

أنقل لكم طيه نسخة عن تحرير ورد من سعادة حاكم اللواء وأرجو اصدار التعليمات الضرورية لمهندس البلدية لتقديم المساعدة المطلوبة وللتعاون مع حضرة مهندس اللواء .

والسلام .

مساعد حاكم اللواء

بطولكرم

نسخة لحضرة مهندس اللواء بنابلس المحترم

مع نسخة عن تحرير سعادة الحاكم .

See P. 138

B.F. 20/4

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

135

GOVERNMENT OF PALESTINE.

IN REPLY PLEASE QUOTE
No. 515

DISTRICT COMMISSIONER'S OFFICES.
SAMARIA DISTRICT.
NABLUS.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
24/17
4 APR 46

3 April, 1946

Asst.Dist.Commissioner,
Tulkarm

I have been informed by the Director of Public Works that some time ago he requested the District Engineer, Nablus, to carry out certain tests on the Tulkarm Municipal Water Supply which would help in connection with the supply of a new pump. The Director has added that the Municipal Engineer is not willing to give any assistance in this respect.

2. I shall be glad if you will impress on the Municipal Commission the necessity for the tests and arrange with the Municipal Engineer and District Engineer direct for them to be carried out as soon as possible.

[signature]

Ag.DISTRICT COMMISSIONER
SAMARIA DISTRICT

ccc/136,137

REGISTERED

134

5/5/7

PUBLIC WORKS DEPARTMENT
JERUSALEM.

30th March, 1946

ASSISTANT DISTRICT COMMISSIONER
14 APR 1946
TULKAREM

24/17

Asst. District Commissioner
Tulkarem.

Subject :- Tulkarm Municipal Water Supply.

Reference:- Your T/24/17-133 of 23.3.46.

I recommend for consideration the offers of Messrs. A. Siniaver & Co. Engineers Ltd. and of Mr. M. Burger Mech. Engineer, Tel-Aviv.

2. Both offers are for Water-lubricating system which is considered as the most suitable for your requirements.

3. There is no appreciable difference in the price and I assume that you will consider the time of delivery as an important factor which is 6-10 weeks after placing of the order and 6 months from date of issue of the Import Licence respectively.

4. I can however not yet advise as to the essentiality of the provision of a new pumping plant and to the correctness of the specified data of head and quantity of the offered pumps until I have had a reply from the District Engineer, Nablus District, about the required pumping test of the existing plant which should also ascertain whether the well will yield 80m3 per hour.

5. The quotations and specifications are returned herewith.

R.H.Brook
for ACTG. DIRECTOR OF PUBLIC WORKS.

Copy to District Engineer, Nablus with a request to take immediate action with regard to test and report.

E6 C.E.M.E.

134

NO. T/24/17-133.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

133

23 March, 1946.

Director of Public Works,
Jerusalem.

127

Subject:- Tulkarm Municipal Water Supply.

Ref'nce:- Letter No. 515 dated 26.1.46 addressed to you by Dist. Commissioner, Samaria with copy to me.

I transmit, in origina, the quotations and specifications referred to.

Assistant District Commissioner,
Tulkarm.

Enc./5

JS/AT

Reg. 29/3

of Palestine.

S. F. 18.

.... Department

DISCREPANCIES.

.... Store at ....

10108 5000. 2.5.27—A.P.

	Actual Stock	Surplus	Deficiency	Remarks

.... Signature of Officer reporting or
.... Officers of Board of Sur[vey]

n immediately beneath the last item.

Date ....

132

GOVERNMENT OF PALESTINE.

IN REPLY PLEASE QUOTE
No. 515

DISTRICT COMMISSIONER'S OFFICES.
SAMARIA DISTRICT.
NABLUS.

19th March, 1946.

Assistant District Commissioner,
TULKARM.

131

With reference to your letter No.T/24/17-131 dated the 15th March, 1946, on the subject of a new vertical pump for the Tulkarm water supply, I should be grateful if you would transmit the actual quotations and specifications referred to in your letter No.T/24/17-126 dated the 18th January, 1946, direct to the Director of Public Works for advice.

[signature]

Ag/DISTRICT COMMISSIONER,
SAMARIA DISTRICT

Pl prepare draft to D.P.W. on lines of 126. Only a little over 3 weeks time has been lost! 22/3

Please see page 127. ...

NO. T/24/17-131.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

( ) March, 1946.

District Commissioner,
Samaria District.

Subject:- Tulkarm Municipal Water Supply
Ref'nce:- Your No. 5'5 dated 4.3.1946.

I have checked up with Municipal Commission of Tulkarm and find that the tenders were for a vertical pump.

The error in translating the Chairman, Municipal Commission's statement that occurred in para 2 of my T/24/17-126 dated 18.1.46 is regretted.

Assistant District Commissioner,
Tulkarm.

JS/AT

NO. T/24/17-130. 130

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

13 March, 1946.

District Commissioner,
Samaria District.

Subject:- Tulkarm Municipal Water Supply
Ref'nce:- Your No. 515 dated 26.1.46.

In his No. 81/5-1 dated 4.3.46 the Chairman, Municipal Commission of Tulkarm, writes:

" The financial year is rapidly drawing to a close with nothing done towards the erection of a new motor and pump for our water supply.

" Will you please contact the Public Work's Dept. that it may express its opinion regarding the offers submitted by various firms, as submitted by me.

" Please treat as very urgent."

Assistant District Commissioner,
Tulkarm.

JS/AT

[illegible]

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
[illegible]

[illegible], 1946.

District Commissioner,
[illegible]

Subject:- [illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

Assistant District Commissioner,
[illegible]

T/24/17

129

GOVERNMENT OF PALESTINE.

IN REPLY PLEASE QUOTE

No. 515

DISTRICT COMMISSIONER'S OFFICES,
SAMARIA DISTRICT,
NABLUS.

4 March, 1946

Asst.Dist.Commissioner,
Tulkarm

126

With reference to your letter No.T/24/17-126 dated the 18th January, 1946, regarding the Tulkarm Water Supply, I have the honour to enquire whether the tenders were in fact for a horizontal centrifugal pump. It should have been clear from the previous correspondence that what is required is a vertical pump.

5.

Ag.DISTRICT COMMISSIONER
SAMARIA DISTRICT


131

128

بلديــــة طولكرم

الرقم ١ ٨/٥ ـ ٦

التاريخ ٤/٣/٤٦



سعادة مساعد حاكم اللواء بطولكرم المحترم .

الموضوع . ـ مشروع الماء

الاشارة . ـ كتابي المؤرخ في ١٥/١/١٩٤٦

125

اوشكت السنة المالية على الانتهاء دون ان نقوم بعمل من اجل تركيب موتور وطلمبة جديدين لمشروع الماء . ارجوكم الاتصال بدائرة الاشغال العامة لكي تبدى رأيها في الطلبات المقدمة لنا من الشركات والاشخاص للقيام بهذا العمل كما جاء في كتابي السابق باسرع ما يمكن .

وتفضلوا بقبول فائق الاحترام .

[signature]

رئيس لجنة بلدية طولكرم

See 130

-127

No.515

GOVERNMENT OF PALESTINE

DISTRICT COMMISSIONER'S OFFICES
SAMARIA DISTRICT, NABLUS

26 January, 1946

Director of Public Works,
Jerusalem

With reference to your letter No.5/5/7 dated the 7th November, 1945, regarding the water supply, Tulkarm, I have the honour to inform you that the firms enumerated in your letter have been invited to tender for the supply and installation of the required pumping plant.

2. The following offers have been received for the erection of a horizontal pump:-

Name	Sums LP.	Period
1. Mr. Joseph Roszgold	1335	6-7 months
2. Mr. M.Burger	1381	6 "
3. Mr. Slobodosky	1600	2 weeks
4. Messrs S.Awad & Co.	2185	3 months
5. Mr. A.Siniaver & Co.	1390	2 months

3. I should be grateful of your advice on the tenders which are available at the office of the Asst.Dist.Commissioner and may be seen by your representative if you so desire.

(Sgd.) W. V. FULLER
Ag.DISTRICT COMMISSIONER
SAMARIA DISTRICT

Copy to:- Asst.Dist.Commissioner, Tulkarm,
ref.his T/24/17-126 of 18-1-46.

126

NO. T/24/17-126.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

126

18 January, 1946

District Commissioner,
Samaria District.

Reg

122

Subject:- Tulkarm Municipal Water Supply
Ref'nce:- Your No. 515 dated 7.12.45.

The Chairman, Municipal Commission of Tulkarm, replies as follows:

"The Municipal Commission of Tulkarm advertised in the Difa and Falastin Newspapers and addressed letters to the firms and persons named in the District Commissioner's letter, requesting them to tender for the erection of a horizontal pump for the Tulkarm Water Supply.

"Five offers have been received:-

Name	Sums	Period
1. Mr. Joseph Roszgold	LP. 1335	6-7 months
2. Mr. M. Burger	1381	6
3. Mr. Slobodosky	1600	2 weeks
4. Messrs. S. Awad and Co.	2185	3 months
5. Mr. A. Siniaver and Co.	1390	2 months

" May the opinion of the Public Works Dept., please be taken regarding the above as soon as possible. The tenders can be seen by a representative of the P.W.D. at this Office whenever he so desires."

Steps to enable the Municipal Commission to go ahead with the erection of a second pump with the least possible delay are recommended.

JS/AT

Assistant District Commissioner,
Tulkarm.

129

F. 119

GOVERNMENT OF PALESTINE

حكومة فلسطين

ממשלת פלשתינה (א"י)

№ 443728

Land Registry Office of Jaffa — مكتب تسجيل الاراضي في / משרד ספרי האחוזה ב

Name of Payer Keren Kayemeth Leisrael — اسم الدافع / שם המשלם

Nature of Transaction Mortgage — نوع المعاملة / טיבה של הטרנסאקציה

Consideration L. P. 26 ج.ف. פ"מ (א"י) — القيمة / סכום

Date 17-5-36 — التاريخ / תאריך

PP. 473—300 Bks. 1-2-36—40/S.

Remarks ملاحظات הערות	Particulars التفاصيل הפרטים	Fees Payable الرسوم المستحقة الدفع הסכום שצריך לשלמו — L. P. ج. ف. פ"מ (א"י)	Mils مل מיל
293/38	Mortgage		260 050
	TOTAL المجموع סך הכל	—	310

The sums shown above have been received by me

بلدية طولكرم

الرقم ١/٨١/٥ـ١

التاريخ ١٩٤٦/١/١٥

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
16. JAN.
TULKARM

24/17

سعادة مساعد حاكم اللواء بطولكرم المحترم

الموضوع . ـ مشروع المياه

الاشارة . ـ كتابكم رقم ط/٢٥/٢٠ تاريخ ٢١/١١/١٩٤٥

نشرت بلدية طولكرم اعلانا في جريدتي الدفاع وفلسطين وارسلت تحارير للشركات والاشخاص المذكورين في كتاب سعادة حاكم اللواء تدعوهم لتقديم عطاءاتهم من اجل تركيب طلمبة عمودية وموتور لمشروع الماء في طولكرم . وقد تقدمت خمسة عطاءات اورد لسعادتكم فيما يلي خلاصتها وهي . ـ

	القيمة جنيه	المدة شهر
١ ـ طلب من المهندس جوزف روتشولد	١٣٣٥	٦ ـ ٧
٢ ـ = = = م بوربر	١٣٨١	٦
٣ ـ = = = اسلوبودسكي	١٦٠٠	نصف شهر
٤ ـ = = شركة عوض الهندسية	٢١٨٥	٣
٥ ـ = = سينبارو وشركاه	١٣٩٠	٢

نارجو اخذ راى دائرة الاشغال العامة بهذه الطلبات باقرب وقت ممكن . وبامكانية استطاعة مندوب عن الدائرة المذكورة الاطلاع على العطاءات في دائرة بلدية طولكرم في اى وقت اراد . وتفضلوا بقبول فائق الاحترام .

[signature]

رئيس لجنة بلدية طولكرم

118

بلدية طولكرم

الرقم ١/٨١ /٥ ـ ٩

التاريخ ١٥ /١/ ١٩٤٦

سعادة مساعد حاكم اللواء بطولكرم المحترم

الموضوع ؟ ـ مشروع المياه

الاشارة ؟ ـ كتابكم رقم ط/٢٥ / ٢٠ تاريخ ٢١ /١١/ ١٩٤٥


نشرت بلدية طولكرم اعلانا في جريدتي الدفاع وفلسطين وارسلت تحارير للشركات والاشخاص المذكورين في كتاب سعادة حاكم اللواء تدعوهم لتقديم عطاءاتهم من اجل تركيب طلمبة عمودية وموتور لمشروع الماء في طولكرم ؟ وقد تقدم خمسة عطاءات اورد لسعادتكم فيما يلي خلاصتها وهي ؟ ـ

	القيمة جنيه	المدة شهر
١ ـ طلب من المهندس جورف روسجولد	١٣٣٥	٦ ـ ٧
٢ ـ = = = م بوربر	١٣٨١	٦
٣ ـ = = أسلوبودسكي	١٦٠٠	نصف شهر
٤ ـ = = شركة عوض الهندسية	٢١٨٥	٣
٥ ـ = = سينياور وشركاه	١٣٩٠	٢

فارجو اخذ راى دائرة الاشغال العامة بهذه الطلبات باقرب وقت ممكن ؟ وباستطاعة مندوب عن الدائرة المذكورة الاطلاع على العطاءات في دائرة بلدية طولكرم في اى وقت اراد ؟ وتفضلوا بقبول فائق الاحترام ؟

[توقيع]

رئيس لجنة بلدية طولكرم



„YOUVAL"
PUMPS, MACHINE WORKS & FOUNDRY
DOV BALKORE
Bnei-Brak, 9, R. Akiva St. Palestine

"יובל"
בית חרשת למכונות ויציקה
דב בעלקורא
בני־ברק, רחוב רבי עקיבא 9, ארץ־ישראל


Tel. Ramat-Gan 7149 טלפון: רמת־גן

63 124

The 3rd. December 45 יום



156



The Assistand Disttict Commissioner/
~~NATHANIA~~

probably Tulkarm JS.

Dear Sir,

Upon you recommendation I have received from the Municipality of Tulkarem an enquiry for a Deepwell Turbine Pump.

I beg to accept my gratitude and should like to point out that my pumps are in use in this country since 1932 and are working to the fullest satisfaction of their proprieters and I am convinced that the Municipality of Tulkarem will be satisfied with my pump if obliging me with their order.

Thanking you again

I am, Sir,

Yours truly

[signature]

Miscellaneous

15/12

[initials] 18/12

Gen. 5

ERVICE

ON HIS MAJESTY'S S

District O

TULKARM

123

P. 119

مكتب مساعد حاكم اللواء بطولكرم

١٩٤٥/١٢/١٢

الرقم - ط/٢٥/٢٠

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع = - الماء لمدينة طولكرم .

اشير الى كتابكم المرقم ٥/٨١ والمؤرخ ١٩٤٥/١١/٢٧ وانقل اليكم بطيه صورة كتاب ورد من سعادة حاكم اللواء .

وتفضلوا بقبول الاحترام .

مساعد حاكم اللواء
بطولكرم

١٢/١٢

(Copy)

GOVERNMENT OF PALESTINE

DISTRICT COMMISSIONER'S OFFICES,
SAMARIA DISTRICT,
NABLUS.

No.515-4.

17th November,1945.

Assistant District Commissioner,
Tulkarm.

With reference to your letter No.T/156/108 of the 5th October,1945 regarding the Tulkarm Water Supply I have received the following advice from the Director of Public Works whom I addressed on the subject of ways and means of getting a suitable pump.

" I propose that you advise the Municipal Commission to invite the following firms to tender for the supply and installation of the required pumping plant and to state in the tender the earliest possible date of completion.

1. Messrs. S.Awad & Co. Jaffa.
2. " A.Siniaver & Co. Engineers Ltd. Jaffa
3. Mr. A.Youval Pump Factory Bnei Brak
4. Mr. A. Newman " " Jaffa Tel-Aviv Road.
5. Mr. M.Burger, M.E. P.O.B.302, Tel-Aviv.
6. Mr. Joseph Rosengold M.E. P.O.B.632 Tel-Aviv."

(Sgd) W.V.FULLER

A/DISTRICT COMMISSIONER
SAMARIA DISTRICT.

(Copy)

GOVERNMENT OF PALESTINE

DISTRICT COMMISSIONER'S OFFICES,
SAMARIA DISTRICT,
NABLUS.

No. 515-4.

17th November, 1945.

Assistant District Commissioner,
Tulkarm.

With reference to your letter No. T/156/108 of the 5th October, 1945 regarding the Tulkarm Water Supply I have received the following advice from the Director of Public Works whom I addressed on the subject of ways and means of getting a suitable pump.

> " I propose that you advise the Municipal Commission to invite the following firms to tender for the supply and installation of the required pumping plant and to state in the tender the earliest possible date of completion.
>
> 1. Messrs. S. Awad & Co. Jaffa.
> 2. " A. Siniaver & Co. Engineers Ltd. Jaffa
> 3. Mr. A. Youval Pump Factory Bnei Brak
> 4. Mr. A. Newman " " Jaffa Tel-Aviv Road.
> 5. Mr. M. Burger, M.E. P.O.B. 302, Tel-Aviv.
> 6. Mr. Joseph Rosengold M.E. P.O.B. 632 Tel-Aviv."

(Sgd) W. V. FULLER

A/DISTRICT COMMISSIONER
SAMARIA DISTRICT.

122

No. 515

GOVERNMENT OF PALESTINE

DISTRICT COMMISSIONER'S OFFICES
SAMARIA DISTRICT, NABLUS

7 December, 1945

Asst. Dist. Commissioner,
Tulkarm

With reference to your letter No. T/25/20-120 dated the 28th November, 1945, regarding the Tulkarm Water Supply, the consumption still appears to me to be well within the capacity of the present bore and the position will be even more favourable when a new pump is supplied to the Kadoorie School.

Ag. DISTRICT COMMISSIONER
SAMARIA DISTRICT

121

23 NOV.

Municipality Of Tulkarm

No. 81/5 - A

28.11.1945

Dear Sir(s)

We have been advised by the Assistant District Commissioner to invite your firm to tender for the supply and installation of a pumping unit to our water supply .

The unit is to consist of a deep well turbine pump with ~~electric~~ electrical motor and accessories , preferably British make, for the following working data:

Depth of water level	65 m
Probable draw down	6 m
Total depth below	72 m
Lift above	42 m
Friction losses in the 600 ms.6" pipe line	8 m
Water quantity needed per hour	80 m3

Your are hereby invited to inspect our water scheme and to forward your quotation in which the earliest possible data of completion is to be stated .

H. Jayousi

Yours faithfully

Messrs. S. Awad & Co. Jaffa
" A. Siniaver & Co. Engineers Ltd. Jaffa
Mr. A. Youval Pump Factory Bnei Brak
Mr. A. Newman " " Jaffa
Mr. M. Burger M.E. Tel-Aviv
Mr. Joseph Roszgold M.E. P.O.B. 632 Tel-Aviv

Copy to:- A.D.C. Tulkarm.

28/11

Messrs S. Awad & Co. Jaffa

" A. Sinuani & Co. Engineers Ltd. Jaffa

Mr. A. Yuval Pump Factory Bnei Brak

Mr. A. Neuman " Jaffa

Mr. H. Burger M.E. Tel-Aviv

Mr. Joseph Roszgold M.E. P.O.B. 632 Tel-Aviv

Copy to:- A.D.C. Tulkarem.

NO. T/25/20-120.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

14 November, 1945.

District Commissioner,
Samaria District.

Subject:- Water Supply - Tulkarm.
Ref'nce:- Your No.515-4 dated 8.11.45.

The figures asked for are as follows:

	Cubic Meters
August, 1945	30,152
Sept., 1945	27,336

Assistant District Commissioner,
Tulkarm.

JS/AT

بلدية طولكرم

الرقم ١٨/٥

التاريخ ٢٧/١١/١٩٤٥

ASSISTANT DIS[TRICT]
[COMMISSIONER'S OFFICE]
27. NOV. 1[945]

1/25/20

سعادة مساعد حاكم اللواء بطولكرم المحترم٠

116

الموضوع٠ — الماء لمدينة طولكرم

الاشارة٠ — كتابكم رقم ط/٢٥/٢٠ تاريخ ١٢/١١/١٩٤٥

بلغت كميات الماء المستهلكة من بئر البلدية خلال شهري اغستوس وايلول سنة ١٩٤٥ بما في ذلك الماء المصروف للمساجد والمدارس وغيرها كما يلي ٠ —

متر مكعب	
٣٠١٥٢	في شهر اغستوس سنة ١٩٤٥
٢٧٣٣٦	= = ايلول = =

وتفضلوا بقبول فائق الاحترام

[توقيع]

رئيس لجنة بلدية طولكرم

1227

118

مكتب مساعد حاكم اللواء بطولكرم

٢١/١١/١٩٤٥ الرقم — ط/٢٥/٥

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع :- مشروع المياه .

1/P.106

اشير الى كتابكم المرقم ٨١/٥ — أ والمؤرخ في ٢/١٠/١
وانقل اليكم بطيه صورة كتاب ورد من سعادة حاكم اللواء للعمل
بموجبه .

وتفضلوا بقبول الاحترام .

مساعد حاكم اللواء
بطولكرم

٢٢/١١

ناحية	كبير الحمولة او العشائر	كبير العائلة	افراد العائلة	
	احمد محمد عزير	احمد محمد عزير ودكين مت.	يوسف عبد الله محمد الدين	
			ابراهيم محمود يونس	
			يوسف محمود محمد عليه ابو جمعه	
			حسين مسعود ابو جمعه	
			محمد احمد مسعود جمعه	
			صبح محمد ابو حمد ابو جمعه	
			محمود عبد الجليل ابو جمعه	
			مصطفى العبد المدني	
			محمد مصطفى العبد المدني	
			احمد مصطفى العبد المدني	
			صبح مصطفى العبد المدني	
			محمود ابراهيم يونس	
			شيخ رضا مصطفى احميد	
			حسن محمود احميد	
			محمد [illegible]	

GOVERNMENT OF PALESTINE

117

DISTRICT COMMISSIONER'S OFFICES,
SAMARIA DISTRICT,
NABLUS.

15/6

20 NOV 1945

No.515-4

17th November, 1945.

Assistant District Commissioner,
Tulkarm.

1 P. 108

With reference to your letter No.T/156/108 of the 5th October, 1945 regarding the Tulkarm Water Supply I have received the following advice from the Director of Public Works whom I addressed on the subject of ways and means of getting a suitable pump.

> " I propose that you advise the Municipal Commission to invite the following firms to tender for the supply and installation of the required pumping plant and to state in the tender the earliest possible date of completion.
>
> 1. Messrs. S. Awad & Co. Jaffa.
> 2. " A. Siniaver & Co. Engineers Ltd. Jaffa.
> 3. Mr. A. Youval Pump Factory Bnei Brak.
> 4. Mr. A Newman " " Jaffa Tel-Aviv Road.
> 5. Mr. M Burger, M.E. P.O.B. 302, Tel-Aviv.
> 6. Mr. Joseph Roszgold M.E. P.O.B. 632 Tel-Aviv. "

[signature]

A/DISTRICT COMMISSIONER,
SAMARIA DISTRICT.

116

مكتب مساعد حاكم اللواء بطولكرم

١٩٤٥/١١/١٢ الرقم – ص/٢٥/٢٠

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع :- الماء لمدينة طولكرم

115

انقل اليكم بطيه صورة كتاب وردني من سعادة

حاكم اللواء للتفضل بالاجابة عليه .

وتفضلوا بقبول الاحترام .

مساعد حاكم اللواء

بطولكرم

١٢/١١/٤٥

P. 116

...er [illegible] اسم الدافع
שם המשלם

...nsaction Sale نوع المعاملة
טיבה של הטרנסקציה

... L.P. 301.310 القيمة ج.ف.
התמורה פ"מ (א"י)

.../3/935 التاريخ
תאריך

27407—200 Bks—6.11 34—G.P

...rks ملا... ה...	Particulars التفاصيل הפרטים	Fees payable الرسوم المقتضي تحصيلها הסכום המשתלם L.P. ج.ف. (פ"מ א"י)	 Mils مل מיל
3	Sale fees Govt. share	4	520
...35	Wakf "	4	520
			050
	Total	9	090

...own above have been received by me.

استلمت المبالغ المدونة اعلاه
הסכומים הנ"ל נתקבלו על ידי

[signature]

...re of Payer
امضاء ال...
חתימת המ...

Signature of Registry clerk
امضاء كاتب التسجيل
חתימת הפקיד הרו...

115

GOVERNMENT OF PALESTINE

No. 515 - 4

DISTRICT COMMISSIONER'S OFFICES
SAMARIA DISTRICT, NABLUS

8 November, 1945

Asst. Dist. Commissioner,
Tulkarm

P 112

With reference to your letter No. T/25/20-112 dated the 2nd November, 1945, regarding Water Supply, I should be grateful if you would supply me with complete figures of the water supplied by the present well during the months of August and September, 1945, including water supplied to mosques, schools etc.

Ag. DISTRICT COMMISSIONER
SAMARIA DISTRICT

P 120

P. 116

مكتب مساعد حاكم اللواء بطولكرم

الرقم – ط/٢٥/٢٠ ٥/١١/١٩٤٥

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع :– مشروع المياه لمدينة طولكرم .

اشير الى تحريركم المرقم ٥/٨١ والمؤرخ ١/١١/١٩٤٥ وانقل

اليكم صورة كتاب ورد من سعادة حاكم اللواء تأييداً لمخابرته التلفونية المحولة اليكم في كتابي

المرقم ط٢٥/٢٠ والمؤرخ ٣٠/١٠/١٩٤٥ .

كنت قد حولت مطالعاتكم في الموضوع الواردة في كتابكم المشار اليه اعلاه

الى سعادة الحاكم قبل وصول كتابه . وتفضلوا بقبول الاحترام .

مساعد حاكم اللواء

بطولكرم

٦/١١/٤٥

C.P.C. 3 S.

...ولات لسنة ١٩٤٣

رقم الصفحة 95542

الموقع

الغذائية لسنة ١٩٤٢)

٤) __________ دونماً

ذرة ...				ذرة صفراء									
ما قدمه المزارع من البذار كيلو	المحصول المخمن كيلو	تخمين المحصول الناتج كيلو	تخمين المحصول الباقي كيلو	المساحة دونم	المساحة المتلفة دونم	ما قدمه المالك من البذار كيلو	ما قدمه المزارع من البذار كيلو	المحصول المخمن كيلو	تخمين المحصول الناتج كيلو	تخمين المحصول الباقي كيلو	محل اقامة المالك او المزارع اذا هو ليس قاطن في القرية	الاشارة الى رقم التسلسل في قائمة التوجيه	ملحوظات
١٣	١٤	١٥	١٦	١٧	١٨	١٩	٢٠	٢١	٢٢	٢٣	٢٤	٢٥	٢٦

No. 515-4

GOVERNMENT OF PALESTINE

DISTRICT COMMISSIONER'S OFFICES
SAMARIA DISTRICT, NABLUS

1st October, 1945

Asst. Dist. Commissioner,
Tulkarm

With reference to your letter No. T/156/92 dated the 28th August, 1945, regarding the Municipal Water Supply at Tulkarm, the Municipal Commission appear to be persuing two course simultaneously:

(a) Getting a reserve pump for their present well

(b) Boring a new well

2. With regard to the first of these proposals I have already stated in my letter No. 515-4 dated the 13th September, 1945, that a second pump is advisable for the present well and I am in correspondence with the Director of Public Works regarding the type he would advise as recommended in your letter No. T/156/108 dated the 5th October, 1945,

3. With regard to the second proposal the position must first be examined as to whether a second well is really necessary. I understand from you that the average monthly consumption during August & September this year (the two worst months in the twelve) was:

Army	2,114 m3
Police	2,230 m3
Railways	1,048 m3
Kadoorie School	5,665 m3
Tulkarm Town	5,660 m3
Total	16,717 m3

I further understood from you that the capacity of the well is 100 m3 per hour or 1,200 in a twelve hour day which I am advised is within the normal capacity of the pump. The well is therefore able to provide 36,000 m3 per month or over twice as much as the present consumption.

4. Further the Government has, I understand, under consideration the provision of a new pump for the Kadoorie School well. If this materialises the consumption will be reduced to 11,052 m3 per month and the present well in a 12 hour pumping day will be able to supply over three times the water required. This is more than adequate.

5. In the circumstances I cannot consider the expenditure on another well would be justified.

Ag. DISTRICT COMMISSIONER
SAMARIA DISTRICT

NO. T/25/20-112.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

112

2nd November, 1945.

District Commissioner,
Samaria District.

Subject:- Municipal Water Supply - Tulkarm Town.
Ref'nce:- Telephone Conversation on Figures Supplied to you by the Municipal Commission of Tulkarm.

The following are the comments of the Chairman, Municipal Commission of Tulkarm, on your enquiry:-

"The figures given refer to the water passing through meters to subscribers but do not include the quantities supplied gratis to Mosques, Schools, the Municipal Garden, sprinkling of streets and, temporarily, to Anabta.

"While it is possible that the quantity of water which the present well can supply may be three times what Tulkarm town needs if we exclude the Kadoorie Agricultural School, we should not depend on this well alone, however large the supply of water, as it is quite possible that a breakdown in the machinery may occur resulting in the Town being without water, a matter which all the experts we have contacted agree upon and advise us on the necessity of having another well independent of the present one.

"In addition to the above, the walls of the well are in poor condition as every one who goes down it brings to our attention. The water of the present well is contaminated and, despite treatment, is adversely reported on by the P.H.D. in their tests.

"All taken into consideration we are unable to dispense with another well to be situated at a distance from the present one and constitutioning an entirely separate unit. We look to the District Commissioner for his full support in this project".

Commenting on the above I would say that public opinion in Tulkarm is very desirous of making doubly sure that no breakdown could result in the stoppage of the Town Water Supply and that this has resulted in much pressure being brought to bear upon the Municipal Commission of Tulkarm.

I therefore strongly recommend that the Municipal Commission be permitted to proceed with testing for a new well.

Assistant District Commissioner,
Tulkarm.

JS/AT

3/11/45

See P 115

القرية ________ رقم البلوك ________ الموقع ________

مساحة البلوك ________ دونما الاراضي صنف (١) (٣) (٤) ________ دونما المساحة المراد توزيعها ________ دونما

GPP. 14394—900 Bks.—29-3-42 1994/8.

رقم التسلسل (١)	القسيمة (٢)	مساحة القسيمة دونم (٣)	اسم المالك (٤)	اسم المزارع (٥)	المساحة دونم (٦)	البذار كج (٧)	المحصول المخمن كج (٨)	المساحة دونم (٩)	البذار كج (١٠)	المحصول المخمن كج (١١)	المساحة دونم (١٢)	البذار كج (١٣)	المحصول المخمن كج (١٤)	المساحة المزروعة حاصلات شتوية اخرى بما في ذلك البطاطا والخضرة دونم (١٥)	المساحة المزروعة صيفي دونم (١٦)	الاراضي الغير مزروعة دونم (١٧)	ملحوظات (١٨)
المجموع																	

ملحوظات :ـــ ١) المساحة تؤخذ لاقرب دونم ٢) في حالة اختلاف مجموع المساحات في هذا الكشف عن المساحة المراد توزيعها يجب بيان السبب.

بلدية طولكرم
الرقم ٨١/٥
التاريخ ١/١١/١٩٤٥

7/25/20

1 - C/2

R 1/10

سعادة مساعد حاكم اللواء بطولكرم المحترم .

الموضوع . – الماء لمدينة طولكرم

الاشارة . – كتابكم رقم ط/٢٥/٢٠

ان الارقام التي قدمت لسعادة حاكم اللواء عن استهلاك الماء في طولكرم كما يأتي . –

متر مكعب			
عـــدد			
١٦٠٠٠	في شهر حزيران	سنة	١٩٤٥
١٧٧٧٤	= = اغستوس	=	=
١٥١٥٤	= = ايلول	=	=

وهذه الارقام تتعلق بالماء الذي تسجله العدادات على المشتركين ولكنها لا تشمل الماء الذي يستهلك مجانا في المساجد والمدارس وحديقة البلدية ورش الشوارع .

ان كمية الماء الممكن سحبها من البئر الحالي قد تكفي ثلاثة اضعاف حاجة طولكرم بعد حذف مدرسة الزراعة منها ومع ذلك فانه لا يجوز الاعتماد على هذا البئر وحده مهما كانت قوة الماء فيه كبيرة لانه يحتمل ان يطرأ خلل على آلات المشروع بسبب من الاسباب فتبقى المدينة بدون ماء وجميع الخبراء الذين اتصلنا بهم منذ انشائنا المشروع الحالي يشيرون علينا بضرورة وجود بئر ثان مستقل عن الآخر وفضلا عن ذلك فان جدران البئر بحالة سيئة وكل من ينزل فيه مرة يلاحظ ذلك ويلفت نظرنا اليه . وماء البئر الحالي ملوث بالجراثيم وعلى الرغم من استمرار تكرير الماء الذي يسحب منه فان التقارير الصحية التي تردنا عند فحص الماء من حين لآخر تشير بان الماء ملوث ولذلك كله فاننا لا نستطيع ان نستغني عن بئر آخر بعيد عن موقع البئر الحالي نقيم عليه مشروعا جديدا منفصلا عن المشروع الحاضر . ونأمل من سعادتكم مؤازرتنا في غايتنا هذه كل المؤازرة . ولسعادتكم جزيل الشكر . وتفضلوا بقبول فائق الاحترام .

[signature]

رئيس لجنة بلدية طولكرم

مكتب مساعد حاكم اللواء بطولكرم

الرقم – ط/٢٥/٢٠ ٣٠/١٠/١٩٤٥

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع = – الماء لمدينة طولكرم

ارجو تجهيزي بنسخة من الارقام التي قدمت من قبلكم

مؤخرا الى سعادة حاكم اللواء ·

ارجو ايضا ابداء مطالعاتكم على الرأى ان كمية الماء

الممكن سحبها من البئر الحالي تكفي ثلاث اضعاف حاجة طولكرم بعد حذف

مدرسة الزراعة منها · وتفضلوا بقبول الاحترام ·

مساعد حاكم اللواء

بطولكرم

Received
& Memo
30/10

F. 45

34

GOVERNMENT OF PALESTINE.

حكومة فلسطين ממשלת פלשתינה (א״י).

Tithe Bill for the village of.............................. in the Sub-District of..............................

قائمة اعشار قرية .... في قضاء

חשבון מעשרות לכפר .... בנפה

A copy of this bill will be sent to the Treasurer.

سترسل نسخة من هذه القائمة الى مدير المالية העתק מחשבון זה ישלח לראש בית האוצר

702 - 300 Bks. - 19.12.24 - L.J.S.P.

Serial No. from Tithe Assessment Register النمرة المتسلسلة في سجل تخمين الاعشار המספר הסדורי בפנקס הערכת המעשרות	NAME OF CULTIVATOR اسماء المزارعين שמות האכרים	Amount due المبلغ المستحق הסכום המגיע	
		£.E. جنيه לא״מ	m/ms ملیم מילים

109

مكتب مساعد حاكم اللواء بطولكرم

٥/١٠/١٩٤٥ الرقم – ١٥٦/١٠٩

P. 77

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع :- مشروع المياه .

اشير الى كتابكم المرقم ٨٦/٥ والمؤرخ ٢١/٦/١٩٤٥ وانقل اليكم اوراق العطاء المقدمة من المهندس روشجولد والتي كانت لدى ادارة الاشغال العامة واعيدت الآن .

وتفضلوا بقبول الاحترام .

مساعد حاكم اللواء
بطولكرم

١٢/١٠/٤٥

GOVERNMENT OF PALESTINE.

Ref. No. C.

DISTRICT OFFICES,
TULKARM.

Date

To:

Subject:- Postmortem Examination.

In accordance with Article 4 of the Coroners' Ordinance, 1926, I hereby direct you to make a postmortem examination on the body

NO.T/156/108.

108

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

5th Oct.,1945.

District Commissioner,
Samaria District.

P. 95

Subject:- Municipal Water Supply - Tulkarm.
Ref'nce:- Your No.515-4 dated 13.9.45.

The contents of the above were duly passed to the Chairman, Municipal Commission of Tulkarm.

On the return of Hashim Eff Jayyusi from leave, he has replied and I give hereunder a translation thereof:-

" I have read the opinion of the experts as conveyed in the District Commissioner's letter. I trust that time will prove the correctness of their view and that our fears and pessimism had no justification. But I am exceedingly sure that were the blame to fall, in future, on the P.W.D. they would not be satisfied with ~~the~~ agreement with our proposal but would have asked for yet another motor and pump.

Nevertheless I cannot but express yet once again, that the matter is a very serious one and that to allow the opportunity of the existance of a suitable motor and pump to pass without benefitting therefrom, puts us in continual perturbation lest we may not have the same opportunity when we become in dire need thereof. For should we be faced suddenly with a breakdown of the motor or pump, the town of Tulkarm will remain without water for months before we can import the machinery suitable for the scheme from abroad.

In view of the District Commissioner's final opinion on the subject, I see no way out of the problem but to follow up the contents of his paras (b) and (d) and to hasten to secure a Vertical Centrifugal pump for our installation and, as the final opinion in this matter rests with the P.W.D., I request that the P.W.D. advise us as soon as possible on the make of Vertical Centrifugal it recommends and the method of getting such in the quickest way.

I request that you pass the above verbatim to the District Commissioner with your recommendation for speed in securing the advice and information necessary from the P.W.D.

I pray almighty God that the Vertical Centrifugal Pump and its motor reach us before any accident takes place to our present installation as the whole town depends on it alone for its water supply."

I fully endorse the request that no time be lost in securing the type of pump considered best suited.

See P. 111

Assistant District Commissioner,
Tulkarm.

JS/AT

Taken by the A.D.C.
8/10/45

GOVERNMENT OF PALESTINE

Ref.No.3/1/2. PUBLIC WORKS DEPARTMENT
NABLUS.
28th September,1945.

Assistant District Commissioner,
Tulkarm.

Subject:- Tulkarm Municipal W.S.

Reference:- Your T/156/99 dated 19.9.1945.

Enclosed herewith the documents refered to.

DISTRICT ENGINEER
NABLUS DISTRICT.

Copy to:-A/D.P.W.Ref.his5/5/7 of 27.8.1945.

994/AT.

106

بلدية طولكرم

الرقم ٠ ــ ١ /٨/ ٥ ــ ١

التاريخ ٠ ــ ٢ /١٠/ ١٩٤٥

156
2 - OCT. 1945
P. 101
P. 96

سعادة مساعد حاكم اللواء في طولكرم المحترم ٠

الموضوع ٠ ــ مشروع المياه

الاشارة ٠ ــ كتابكم رقم ١٥٦ تاريخ ١٨ /٩/ ٤٥ و ١٩ /٩/ ١٩٤٥

اطلعت على ما جاء في تقرير الخبير الذى انتدبته دائرة الاشغال العامة وفي كتاب سعادة حاكم اللواء وأرجو ان تثبت الايام صواب رأيهما في موضوع مشروع الماء لبلدية طولكرم وبأن خوفنا وتشاؤمنا لم يكن لهما ما يبررهما غير اني جد مقتنع بانه لو كانت الملامة في المستقبل تقع على عاتق دائرة الاشغال لما اكتفت بالموافقة على اقتراحنا بل طلبت ايضا موتور وطلمبة آخرين ٠ ومع ذلك لايسعني الا ان أصرح مرة أخرى بان الامر جد خطير وبان تركنا لفرصة وجود موتور وطلمبة بالاثمان مشروعنا تفوت دون ان نستفيد منها يجعلنا في قلق مستمر خشية ان لا تسنح فرصة مثالها عندما نصبح في اشد الحاجة اليها ٠ فلو فوجئنا بخراب طارئ على الموتور والطلمبة فان مدينة طولكرم تبقى بدون ماء لمدة أشهر بينما نستطيع استيراد الالات التي تصلح للمشروع من الخارج ومع ذلك كله فاني بازاء رأى سعادة الحاكم الاخير في الموضوع لا اجد مخرجا لحل المشكلة الا ان اتشبث بما جاء في الفقرتين ب و د من كتابه وان اسارع للحصول على الطلمبة العمودية المقترحة لمشروع الماء ٠ وبما ان الرأى الاخير في هذا الصدد سيكون لدائرة الاشغال العامة فاني ارجو ان تشير علينا دائرة الاشغال باقرب وقت مستطاع عن نوع الطلمبة العمودية التي توصي بها وعن السبيل للحصول عليها باقصر مدة ممكنة ٠

رجائي الكبير اليكم ان تنقلوا ما جاء بكتابي هذا اليكم حرفيا لسعادة حاكم اللواء مع توصيتكم بالاستعجال في اخذ الارشادات والمعلومات المطلوبة من دائرة الاشغال العامة ٠ واسأل الله تعالى ان تصلنا الطلمبة العمودية وموتورها قبل ان يطرأ اى خلل على الالات الحاضرة اذ تعتمد المدينة عليها وحدها في ما تحتاج اليه من الماء ٠

وتفضلوا بقبول فائق الاحترام ٠

[signature]

رئيس لجنة بلدية طولكرم

See 108

105

GOVERNMENT OF PALESTINE

No. 515 - 4

DISTRICT COMMISSIONER'S OFFICES
SAMARIA DISTRICT, NABLUS

26 September, 1945

Asst. Dist. Commissioner, ✓
Tulkerm

p. 103

156
27 SEP. 1945

With reference to the District Engineer's letter No. 3/1/2 dated the 20th September, 1945, to me, with a copy to you, concerning the water supply at Tulkarm, I have the honour to request you to reply direct to the District Engineer with a copy to me.

Seen by A.D.C.
See p. 104 pl.

[signature]
Ag. DISTRICT COMMISSIONER
SAMARIA DISTRICT

Copy to:- Dist. Engineer, Nablus.

NO.T/156/104. 104

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

27th Sept.,1945.

District Engineer,
P. W. D.,
Nablus.

Subject:- Water Supply Tulkarm Municipality.
Ref'nce:- Your No.3/1/2 dated 20.9.45.

The air impeller fan is now working.

p.103

29/9.

Assistant District Commissioner,
Tulkarm.

JS/AT Copy to: D.C.,Samaria

1/10/45

		Sheikh Rashid 'Abdel Salam.
		'Iz el Din Mouhamad Khader.
	Hamd-allah Baker Hurem.	Hamd-allah Baker Hurem.
		Khalil Baker Hurem.
		Sa'id Khalil Baker Hurem.
		El Haj Mouhamad 'Oosman Baker.
		'Oosman Mouhamad Baker.
		Rashid el Sha-fi'i.
		'Oomar Hassan.
	'Abdel Latif Dablan.	'Abdel Latif Dablan.
		'Abdel Hafeez Dablan.
		Sheikh Mustapha Srour.
		Mouhamad Mustapha Srour.
		Rashid Mustapha Srour.

GOVERNMENT OF PALESTINE

PUBLIC WORKS DEPARTMENT
NABLUS.
30.9.1945.

No. 3/1/2

District Commissioner,
Samaria District.

Sub:- Water Supply Tulkarm Municipality.

Ref:- My 3/1/2 of 30.8.45.

It is now desired to carry out further tests of performance of the above mentioned municipal pumping plant. May I be informed when repairs to air impeller fan are complete as this is a vital necessity to supply air to workers at bottom of well.

DISTRICT ENGINEER
NABLUS DISTRICT

Copy to: A.D.C. Tulkarm.

994/HS.

102

مكتب مساعد حاكم اللواء بطولكرم

الرقم – ١٥٦ P.93/39C. ١٩٤٥/٦/١٦

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع = – مشروع المياه .

انقل اليكم بطيه صور كتاب وتقرير وردا من حضرة

مهندس الاشغال .

وتفضلوا بقبول فائق الاحترام .

مساعد حاكم اللواء

بطولكرم

101

مكتب مساعد حاكم اللواء بطولكرم

١٩٤٥/٩/١٩ الرقم ـ ١٥٦

P. 97

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع =ـ مشروع المياه .

P. 96

اشير الى كتابكم المرقم ٥/٨٦ والمؤرخ ٤٥/٩/١٦ .

نظرا لما جاء في كتاب سعادة حاكم اللواء المرسل اليكم طي كتابي المرقم ١٥٦ والمؤرخ ١٩٤٥/٩/١٨ لا فائدة من تقديم ما جاء في كتابكم المشار اليه اعلاه .

على اني ارى أن تسجلوا كل عطل وتوقيف بالضبط لكي نعرف سعادة الحاكم عنها من وقت الى آخر .

وتفضلوا بقبول فائق الاحترام .

مساعد حاكم اللواء

بطولكرم

See P. 106

NO. T/156/100.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

100

19th Sept., 1945.

District Commissioner,
Samaria District.

P. 92

Subject:- Municipal Water Supply Tulkarm Purchase of a New Pump.

Ref'nce:- My T/156/92 dated 28.8.45.

The Chairman, is pressing for permission to commence work.

Assistant District Commissioner,
Tulkarm.

B.F. 16/10

JS/AT

22/9/45
1-3

to these By-laws, the amounts of tax payable in respect of the said trades or businesses are different, tax shall be paid on that or business in respect of which the amount payable under the said Schedule is higher than the amount payable in respect of any other of the said trades or businesses.

Payment of tax.

4. The tax shall be paid:-

(a) in respect of any specified trade or business which any person carries on at the date of the publication of these By-laws in the Gazette, by two equal instalments as follows:-

(i) the first instalment within thirty days after the said date; and

(ii) the second instalment upon the 1st. day of October, 1945;

(b) in respect of any specified trade or business which any person begins to carry on after the date of the publication of these By-laws in the Gazette by two equal instalments as follows:-

(i) the first instalment within thirty days after the date on which he began to carry on such trade or business; and

(ii) the second instalment within three months after the date mentioned in paragraph (b)(i) of this by-law.

Persons carrying on specified trade or business to give notice.

5.-(1) Any person who-

(a) at the date of the publication of these By-laws in the Gazette carries on any specified trade or business within the Local Council Area of Qalqilya shall, within one month from the date,

(b) after the date of the publication of these By-laws in in the Gazette, begins to carry on any specified trade or business within the Local Council Area of Qalqilya, shall, within 15 days from the date when he begins to carry on such trade or business,

NO.T/156/99.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE 99
TULKARM.

19th Sept.,1945.

District Engineer,
Nablus.

Subject:- Tulkarm Municipal Water Supply.

Ref'nce:- Letter No.5/5/7 dated 27.8.45 from Director of Public Works,Jerusalem,to me with copy to you.

P-94

May the enclosures under reference please be returned at your convenience.

Assistant District Commissioner,
Tulkarm.

P.F. 3/10

see P. 107 pl

22/9/45

JS/AT

Provided that where, in accordance with the First Schedule to these By-laws, the amounts of tax payable in respect of the said trades or businesses are different, tax shall be paid on that or business in respect of which the amount payable under the said Schedule is higher than the amount payable in respect of any other of the said trades or businesses.

Payment of tax.

4. The tax shall be paid:-

(a) in respect of any specified trade or business which any person carries on at the date of the publication of these By-laws in the Gazette, by two equal instalments as follows:-

(i) the first instalment within thirty days after the said date; and

(ii) the second instalment upon the 1st. day of October, 1945;

(b) in respect of any specified trade or business which any person begins to carry on after the date of the publication of these By-laws in the Gazette by two equal instalments as follows:-

(i) the first instalment within thirty days after the date on which he began to carry on such trade or business; and

(ii) the second instalment within three months after the date mentioned in paragraph (b)(i) of this by-law.

Persons carrying on specified trade or business to give notice.

5.-(1) Any person who-

(a) at the date of the publication of these By-laws in the Gazette carries on any specified trade or business within the Local Council Area of Qalqilya shall, within one month from the date,

(b) after the date of the publication of these By-laws in in the Gazette, begins to carry on any specified trade or business within the Local Council Area of Qalqilya, shall, within 15 days from the date when he begins to carry on such trade or business,

(٦٤)

بلدية طولكرم

صندوق البريد رقم ٩

التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٥/٨١

P. 91

P. 88

طولكرم في ١٦/٩/١٩٤٥

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
17. SEP 1945
TULKARM

156/11

سعادة مساعد حاكم اللواء في طولكرم المحترم ٠

الموضوع — مشروع الماء الجديد في طولكرم ٠

الاشارة — كتابي رقم ٥/٨١ تاريخ ٨/٨/١٩٤٥ و ٢٣/٨/١٩٤٥

ان حالة مشروع الماء في طولكرم الحاضرة لا تبيح لي مطلقا ان اتغافل واتقاعس في موضوع انشاء مشروع جديد للماء ٠ ولا يجوز لنا ان نعتمد على المشروع الحاضر حتى بعد ان تركب له الالات الجديدة ٠لذلك فانني استمحكم العذر اذا انا عدت وطلبت من سعادتكم البت في هذا الموضوع باقرب وقت مستطاع ٠

وتفضلوا بقبول فائق الاحترام ٠

نمر محمد كمال

وكيل رئيس لجنة بلدية طولكرم ٠


(97)

مستعجل

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٥/٨٦



طولكرم في ١٦/٩/١٩٤٥

P.77 P.89 P.84 P.81

سعادة مساعد حاكم اللواء في طولكرم المحترم،

الموضوع ـ مشروع المياه

الاشارة ـ تحاريرنا رقم ٥/٨٦ المؤرخة في ٢١/٦/١٩٤٥ و ١٤/٧/١٩٤٥ و ٢٩/٧/١٩٤٥ و ٩/٨/١٩٤٥

اضطرت البلدية لوقف توزيع الماء على السكان في الليلة الماضية من جراء عجز آلات مشروع الماء التي تقادم عليها العهد وأجهدها العمل المتواصل عن مجاراة الاستهلاك المتزايد للماء • ومع ان وقف التوزيع كان مؤقتا فقد حمل الناس على البلدية حملة شعواء وسلقوها بالسنة حداد ولست أرغب ان اصور موقفنا تجاه الجمهور اذا توقف توزيع الماء لمدة طويلة •

الحالة ولا ريب تدعو الى القلق الكبير اذ يحتمل في كل آن ان تتعطل آلات الماء عن العمل وتبقى المدينة بدون ماء • ولا يسعني بعد أن شرحت لسعادتكم الوضعية باسهاب في مخابراتي السابقة والححت في طلب الموافقة على شراء الموتور والطلمبة من المهندس "روشبولد" الا ان أضع مقدرات مدينة طولكرم وسكانها بين يديكم فاما تصريح عاجل من مراقب الصناعات الثقيلة بشراء الموتور والطلمبة المذكورين وهما الوحيدان في فلسطين اللذان يوافقان مشروعنا واما عطش محقق لمدينة طولكرم لا نملك اية وسيلة لتلافيه •

وتفضلوا بقبول فائق الاحترام •

101 ...

[توقيع]

وكيل رئيس لجنة بلدية طولكرم

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

مستعجل

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٥/٨٦

طولكرم في ١٦/٩/١٩٤٥

سعادة مساعد حاكم اللواء في طولكرم المحترم.

الموضوع ــ مشروع المياه

الاشارة ــ تحاريرنا رقم ٥/٨٦ المؤرخة في ٢١/٦/١٩٤٥ و ١٤/٧/١٩٤٥ و ٢٩/٧/١٩٤٥ و ٩/٨/١٩٤٥ .

اضطرت البلدية لوقف توزيع الماء على السكان في الليلة الماضية من جراء عجز آلات مشروع الماء التي تقادم عليها العهد وأجهدها العمل المتواصل عن مجاراة الاستهلاك المتزايد للماء . ومع ان وقف التوزيع كان موقتا فقد حمل الناس على البلدية حملة شعواء وسلقوها بالسنة حداد ولست أرغب ان اتصور موقفنا تجاه الجمهور اذا توقف توزيع الماء لمدة طويلة .

الحالة ولا ريب تدعو الى القلق الكبير اذ يحتمل في كل آن ان تتعطل آلات الماء عن العمل وتبقى المدينة بدون ماء . ولا يسعني بعد أن شرحت لسعادتكم الوضعية باسهاب في مخابراتي السابقة والحث في طلب الموافقة على شراء الموتور والطلمبة من المهندس "روشيلد" الا ان أضع مقدرات مدينة طولكرم وسكانها بين يديكم تماما بصريح عاجل من مراقب الصناعات الثقيلة بشراء الموتور والطلمبة المذكورين وهما الوحيدان في فلسطين اللذان يوافقان مشروعنا واما عطش محقق لمدينة طولكرم لا نملك اية وسيلة لتلافيه .

وتفضلوا بقبول فائق الاحترام .

فخري عبد الهادي

وكيل رئيس لجنة بلدية طولكرم.

96

p. 89

مكتب مساعد حاكم اللواء بطولكرم

١٨/٩/١٩٤٥

الرقم — ١٥٦

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع :- مشروع المياه .

اشير الى تحريركم المرقم ٨١/٥ - أ والمؤرخ ٦/٨/١٩٤٥ وانقل اليكم جواب سعادة حاكم اللواء النهائي في الامر .

وتفضلوا بقبول فائق الاحترام .

p. 95.

مساعد حاكم اللواء
بطولكرم

see p. 101 Al.
see p. 106 A

95

GOVERNMENT OF PALESTINE

DISTRICT COMMISSIONER'S OFFICES,
SAMARIA DISTRICT,
NABLUS.

15. SEP. 1945

No.515-4 156

13 September, 1945.

Assistant District Commissioner,
Tulkarm.

---

p.90

With reference to your letter No.T/156/90 of the 10th August, 1945 regarding the purchase of a pump for Tulkarm Water Supply I have the honour to inform you that I have now completed my enquiries.

2. I am advised:-

(a) That the present pump is in fairly good condition and a serious break down need not be expected in the near future.

(b) Nevertheless a second pump is advisable though in view of (a) above the matter is not ~~so~~ urgent as to prevent a search for ~~this~~ the best possible type of pump.

(c) That the type of pump suggested by the Mayor being a horizontal type is unsuitable owing to the fluctuations in water level of the well.

(d) That the ideal type is a Vertical Centrifugal pump.

3. In the circumstances I cannot support the purchase of the pump suggested.

See p. 96 pl.

A/DISTRICT COMMISSIONER,
SAMARIA DISTRICT.

See p. 108 pl.

(94)

PUBLIC WORKS DEPARTMENT
JERUSALEM

5/5/7. 156

August 27th, 1945.

Assistant District Commissioner
Tulkarm.

P. 78

<u>Subject</u>: Tulkarm Municipal Water Supply.

<u>Reference</u>: Your T/156/78 of 25.6.45.

I have handed the papers enclosed with your letter to the District Engineer Nablus who will return them to you in due course.

for ACTG. DIRECTOR OF PUBLIC WORKS.

Copy to: District Engineer Nablus.

T5.

GOVERNMENT OF PALESTINE

No. 3/1/2.

PUBLIC WORKS DEPARTMENT,
NABLUS.
30th August, 1945.

District Commissioner,
Samaria.

Subject :- Water Supply - Tulkarm Municipal Well.

..... I attach, herewith, a copy of a report from my Electro-Mechanical Foreman. I suggest that immediate action be taken to repair "Air Impeller" on top of well and reinstate electric cables.

2. With these two points attended to, the efficiency and general performance of the existing plant, now considered to be in a fair condition, will appreciatively improve.

..... 3. I return, herewith, letter and pamphlets from Mr. Roszgold of Tel Aviv.

DISTRICT ENGINEER
NABLUS DISTRICT

Copy to :- Director of Public Works, } With copy of report.
" " :- Asst. Dist. Commissioner, Tulkarm }

57/SH.

District Engineer,
Nablus District.

93(a)

In accordance with your instructions, I visited Tulkarm Municipal Pump House and obtained the following information :-

1. Pump:- Makers. Mather and Platt, Manchester. Serial No. 31945. Type - Centrifugal Horizontal. Pump plate is marked (1) 220 galls., (2) 456 Head and (3) 3000 Revs. I presume the figure 456 Head refers to Feet.

2. Motor:- Makers. Lancashire Dynamo and Crypto, Manchester. Marked Maxtorc. 380 volts. 57 amps. 40 B.H.P. 2910 R.P.M. Contin. rating. 3 phase. 50 cycles.

The inspection of the plant was carried out at the bottom of the well under extreme discomfort, no lights were on, the lamps which should light up the bore were burnt out. The air impeller fan which normally supplies fresh air to the bottom was also out of order and the atmosphere was exceptionally humid, very hot and stuffy. Great difficulty was experienced in breathing.

The pump appears to be in good order, bearings tight, no undue noises, fairly clean and a minimum of drip from stuffing boxes. The bye-pass stop-cock on the non-return valve requires slight attention, a small quantity of water is being forced back through pump owing to back pressure through this stop cock.

The motor is in fair condition, some rust could be seen on ventilator vanes and rotor shaft inside the motor. Bearings tight, no undue noises. However, the motor is running exceptionally hot, it was impossible to bear the naked hand on casing. The cables to this motor are far too long, the extra cable is not clipped to wall and is draped in an untidy manner over the beams and around the motor. The main cables end in cast iron connecting boxes from which lighter cables are taken to motor. These boxes were originally ~~xxxxxx~~ clamped in an upright position on the wall. They are now hanging upside down adjacent to the motor. Owing to the heat, the compound has run out and dripped onto the cables and beams. I have drawn the attention of the Town Engineer to this point and recommended that the air impeller be repaired as soon as possible to ensure a flow of cool air to bottom of well. Also that the connecting boxes be reinstalled correctly.

The motor to pump drive is of the flexible coupling pin and rubber bushing type and is in good order.

A test of rise and fall of water level was then carried out with the following results :-

The pump was started and it was found that the water level fell rapidly during the first 35 minutes and then remained steady. Readings taken every fifteen minutes are as under :-

	Time	Fall
Start	12.20 p.m.	0
	12.40 p.m.	40 cms.
	1.5 p.m.	60 cms.
	1.20 p.m.	60 cms.
	1.45 p.m.	60 cms.
	2.00 p.m.	60 cms.

Further readings showed level to be steady.

The salient point is the fact that once the water level has dropped some 60 cms. it remains steady.

The rate of recovery of well was very rapid, readings being taken every five minutes as under :-

Water level during pumping. 60 cms. below rest level.

(Contd.)

Water level 5 minutes after pumping ceased. 20 cms. below rest Level.
" " 10 " " " " 10 " " rest level.
" " 15 " " " " 0 " " " "

Thus water level rose 40 cms. in first 5 minutes and 10 cms. each five minutes after. Total time required for recovery being 15 minutes only.

To sum up therefore :- (1) The plant is in fair condition and should continue to give good service provided the points regarding air impeller and cables are attended to early. (2) The drawdown of the water is not more than 60 cms. (3) The time of recovery is fifteen minutes.

I note from your 3/1/2 of 23.8.45 that you mention that the rising mains are of 6" Ø. Please note that the suction pipe of pump is of 4" Ø x 2 metres from pump to 6" Ø mains.

For your information.

(Sgd.) T. Downs,

ELECTRO-MECHANICAL FOREMAN,
P.W.D., NABLUS.
29.8.45.

SH.

[illegible]

[illegible]

[illegible]

[illegible]

For your information.

[illegible]

[illegible]

NO. T/156/92.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

92

28th August, 1945.

District Commissioner,
Samaria District.

REGISTERED

8-74

Subject:- Municipal Water Supply Tulkarm Purchase of a New Pump.
Ref'nce:- Your No. 515-4 dated 25.2.45

The Chairman, Municipal Commission of Tulkarm, writes that the matter was taken up with Dr. Loehnberg, an expert in water prospecting, whose reply is attached.

The Commission have now given the project their full consideration and ~~now~~ propose that the necessary survey and tests be made on the Southern part of the site to be expropriated by the Municipal Commission as a public Sports Field. If these prove successful the Municipal Commission will purchase an additional piece of land~~s~~ lying South of the playground for the purpose of boring a well. Should the test fail, the site, already approved as a Sports Field, will in no way suffer.

The Chairman, Municipal Commission therefore asks that sanction be given to commence the work on the lines indicated in the last para of Dr. Loehnberg's letter.

Budget provision exists in Head X Sub-Head 8 - the sum being LP. 2500.

Approval is recommended.

Assistant District Commissioner,
Tulkarm.


See P 113

Rep. 100 L. 29/8/45

JS/AT

91

بلدية طولكرم
٢٣ /٨/١٩٤٥
رقم ٨١/٥



156
P.88

سعادة مساعد حاكم اللواء في طولكرم المحترم ·

الموضوع — مشروع الماء الجديد في طولكرم

الاشارة — كتابي المؤرخ في ٨/٨/١٩٤٥

ينتظر مجلس بلدية طولكرم ما يتم عليه رأي سعادتكم في موضوع حفر البئر على الطرف الجنوبي من قطعة ارض الملعب · يود المجلس ان يتمكن من استعمال المخصصات المدرجة في ميزانية البلدية للسنة الحاضرة لانشاء مشروع جديد للماء قبل ان يفوت عليه الوقت لان المشروع الحاضر كما تعلمون ضعيف لا يركن اليه ·

اكون ممتنا اذا اعتبرتم هذا الموضوع من الامور المهمة والمستعجلة ·

وتفضلوا بقبول فائق الاحترام ·

[signature]

رئيس لجنة بلدية طولكرم

NO. T/156/90.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

10th August, 1945.

District Commissioner,
Samaria District.

Subject:- Purchase of Pump for the Tulkarm Municipal Commission Water Supply.

Ref'nce:- My T/156/83 dated 18.7.45 and recent telephone conversation between Messrs Worsfold and Somerville.

The Chairman, Municipal Commission of Tulkarm, has written forwarding a letter - copy attached - from Mr. S. Shiloni on the subject.

The Chairman goes on to say that he regards the matter as a very serious one and appeals that a decision may be reached with the least possible delay.

13/8

Assistant District Commissioner,
Tulkarm.

JS/AT

89

بلدية طولكرم

الرقم ٨١/٥ - أ

التاريخ ٩/٨/٩٤٥

156

9 AUG. 1945

سعادة مساعد حاكم اللواء في طولكرم المحترم

P.82

الموضوع: مشروع المياه

الإشارة: كتابكم رقم ٨٢/١٥٦ تاريخ ١٦/٧/٤٥

P.84

عطفاً على كتابي المؤرخ في ٢٩/٧/٩٤٥، اقدم لسعادتكم الآن صورة عن كتاب ورد لي بخصوص الموتور والمضخة المبحوث عنها وتطلب مني اعطاء الجواب بعودة البريد.

أكون ممتناً اذا اعطيتموني رأيكم الأخير في هذا الصدد حتى أتمكن من اعطاء الجواب. وبهذه المناسبة اود ان اذكر لسعادتكم مرة اخرى بان ثمن الموتور والمضخة زهيد لا يتعدى المبلغ المصرح لبلدية طولكرم انفاقه عليه دون مناقصة او مصادقة، وبأنني ارغب في تأسيس حركة توزيع الماء في المدينة قبل سفري في اجازة سنوية في اوائل الشهر القادم.

وتفضلوا بقبول فائق الاحترام

[signature]
رئيس لجنة بلدية طولكرم

Sale
90 pe.
96 pe

Copy

84(a)

Tel-Aviv
1-8-45

The Municipality
of Tulkarm

We shall be glad to know if you intend to purchase the pumping unit offered to you by Mr. Roszgold.

The latter requested us to ask for your decision since he has other customers for this unit and your reply per return mail will be greatly appreciated.

Yours faithfully

(Sgd) S. Shiloni

Copy

Tel-Aviv
[illegible]1-XI-45

To
The Municipality
of Tul Karem

We shall be glad to know if you intend to purchase the pumping unit offered to you by Mr. Roszgold.
The latter requested us to ask for your decision since he has other customers for this unit and your reply per return mail will be greatly appreciated.

Yours faithfully

S. Shiloni (sgd)

88

بلدية طولكرم

الرقم ٨١/٥

1566

التاريخ ٨/٨/١٩٤٥

سعادة مساعد حاكم اللواء في طولكرم المحترم

الموضوع — مشروع الماء الجديد في طولكرم

طلبنا الدكتور لوينرغ الخبير في شؤون المياه ليكشف على منطقة طولكرم ويبحث لنا عن المحل المناسب لحفر بئر جديد في طولكرم. حضر الخبير ونتيجة الكشف قدم لنا تقريرا ارفق بكتابي هذه نسخة عنه. وهو يقول في الفقرة المعلمة بالاحمر على الصفحة الرابعة من تقريره ان انسب موقع للحفر هو الجهة الغربية والجهة الشمالية من مدينة طولكرم.

لقد بحث المجلس البلدي هذا الموضوع في اجتماعه المنعقد هذا اليوم فاقترح ان يكون حفر البئر على الطرف الجنوبي من قطعة الارض التي تسعى البلدية لاستملاكها من اجل الملعب فاذا نجحت التجربة تستملك البلدية قطعة اخرى ملاحقة لارض الملعب من الجنوب لمشروع البئر الجديد وسواء انجحت التجربة ام لم تنجح فان قطعة ارض الملعب لا تتضرر منها لان العملية عبارة عن انزال ١٢ الانابيب الانابيب من سطح الارض دون القيام بعمليات حفر. والمجلس البلدي يرغب في الوقوف على رأي سعادتكم في الموضوع فاذا وافقتم على الاقتراح ينظر في طلب الاخصائيين لمقاولتهم على العمل.

وتفضلوا بقبول فائق الاحترام.

[signature]

رئيس لجنة بلدية طولكرم

9.8.45

Copy.

20th July, 1945.

Secretary,
Municipality,
TULKAREM.

Dear Sir,

Subject: Water supply.

On 11th July, 1945, I visited the Tulkarem area with a view to examine the possiblities of sinking a new well at near Tulkarem in order to increase the quantity of water available for the municipal water supply system. During my visit and subsequently I collected geolgical information and data regarding existing important bores and wells.

The main existing bores and wells are:

1. Municipal well No.1, situated between the main road and municipal garden. This well represents now the main source of water for Tulkarem town. It was drilled by Government and is registered as bore No.2720; the watter table rests at approximately 220 ft. below ground, i.e. at about 17.3 ms. above sea level. After being drilled in 1934 test pumping yielded about 20 m^3/h of water at a small draw down. A larger quantity may be pumped allowing a greater draw-down. The salinity is 5.2 parts per 100,000. The description of the formations as given by the Government is as follows:

0 - 230 ft.	Unknown (shaft).
230 - 245 "	Soft limestone.
245 - 250 "	Soft limestone and some clay.
250 - 255 "	Soft limestone.
255 - 260 "	Soft white limestone (probably Turonian).
260 - 265 "	White limestone.
265 - 270 "	Soft white flinty limestone.
270 - 275 "	Yellow marly limestone.
275 - 290 "	Marly limestone.
290 - 310 "	White limestone.
310 - 315 "	Hard yellow limestone.
at 315 ft.	Quartz sand and loose yellow sand.

2. Municipal Well, Government No.676; yield about 8 m^3/h. Formations:

0.0 - 12.0 ms.	Chalk.
12.0 - 13.0 "	Hard limestone.
13.0 - 24.5 "	Chalk.
24.5 - 25.5 "	Hard limestone.
25-5 - 95.0 "	Chalk.

This bore situated on the southern side of the main road is not in use.

3. Municipal bore, Government No.678; water table above sea 20.62 ms. Yield $3m^3/h$.

Formations:

0.0 - 40.0 ms.	Chalk.
40.0 - 75.0 "	Hard limestone.
75.0 - 77.5 "	Chalk.
77.5 -129.5 "	(?) hard porous limestone.

This bore again is not in use.

4. Well Kadoorie School. Formations:

0.0 - 8.0 ms.	Unknown.
8.0 - 58.0 "	Chalk.
58.0 - 62.0 "	Hard limestone

Yield 29.2 m^3/h. at 2.77 ms. draw down; salinity 5 parts per 100,000.

5. Kamal well. Drilled 1944-45 by Messrs. Emmanuel & Rifkind to 61 ms.

depth. This well is situated north of the main road from Tulkarm to Nablus. Water level 58 ms. below ground; a vertical pump installed at .4 ms. below gr und and delivered during 17½ hours of test pumping a quantity of approximately 39-40 m^3/h. at a drawdown 9.5 ms.

6. Army bore. This bore was drilled in 1942-43 by Messrs. Hassadeh Tel-Aviv for the Army, at a distance of 500 ms. west - northwest of the station building of Tulkarem Railway station. Total depth 80 ms.; water level 29 ms. below ground, yield 74 m^3/h at 2.1 ms. drawdown. The bore is cased with blind pi es of 14" diameter from the surface of the ground to 56.5 ms. and between 61.5 - 67 ms. depth. Perforated pipes of 10" diameter are inserted between 56.5 - 61.5 ms. and between 67-80 ms. depths.

Formations:

0.0 - 1.5	ms.	Brown-grey loamy soil.
1.5 - 2.8	"	Do. with limestone breccie and limestone boulders.
2.8 - 10.6	"	Boulders (?) consisting of hard limestone and flint
10.6 - 58.5	"	Light-coloured greyish yellowish marl.
58.5 - 61.6	"	Sandy soft marl.
61.6 - 66.6	"	Greyish-greenish marly clay.
66.6 - 80.0	"	White hard porous limestone (water-bearing).

As may be seen from the existing bores and wells conditions for the supply of water at and near Tulkarem are not regular; One bore did not open up a suitable supply to nearly 130 ms depth although a second one at a small distance only from the former one and brought down to less depth yields a good supply. Formations at Tulkarem consist of chalks and marls which belong to lower Seconian layers of Cretacious formations. These strata are usually no -water-bearing. They are underlain by hard and sometimes porous limestones of Turnonian age which under favourable conditions are good water-bearing layers. Both the marls and chalks as also the limestones dip in the direction of coastal plain where they are covered by any increasing t ickness of soil, loam, and clay. At a short distance westwards of Tulkarem the mo ntain layers - invisible from the faulted down. This is evident from a deep bore near Bir Burin about 2.5 kms. west of Tulkarem which did not reach the limestone formations to a great depth.

It appears from the facts collected that the water travels mainly in the hard and porous limestone layers in th form of fissures and cracks and not as a regular horizon. The development of a water horizon which would be sager for drilling and for water supply appears more to the west of Tulkarem town that at Tulkarem itself or east it. We should, therefore, think that the best area for drilling northwest and west of Tulkarem town where a bore site would have to be selected at a suitable distance from one of the existing wells in order not to be influenced by them.

After all, what can be said on the basis of the existing bores a and the general geological conditions, a new bore would have to be brought down to at least 80 ms. if not to 100 ms. depth.

According to information received from engineer Shiloni, Tel-Aviv the main 6" pipeline runs from the municipal well to the main resevoir. An extension of this pipeline is said to go a certain distance in the direction of the Railway Station. If a new well were therefore, be made west or northwest of the town as proposed it might be possible to use the existing pipes.


In order to decrease the risks which are inevitable connected with the drilling of a new well it is proposed that a number of geophsical measurements should be carried out to test the subsoil at various places. Such geophsical measurements as we carry out afford more security for the selection of a favourable bore site than can be obtained on the basis of geological data alone. A geophysical survey to select the best bore wite near Tulkarem and to indicate the depth to which the bore would have to be drilled would cost .110.-. The time for carrying out the survey would be about one week and two weeks previous notification would be necessary for the start of the measurements. In the event that the municipality would decide to have such a survey carried out, the fees for this report would be deducted from the cost of the survey.

Yours faithfully,

Sgd.

Dr.A.& E.LOEHNBERG

AL/ET.



Copy.

20th July, 1945.

Secretary,
Municipality,
TULKAREM.

Dear Sir,

Subject: Water supply.

On 11th July, 1945, I visited the Tulkarem area with a view to examine the possiblities of sinking a new well at near Tulkarem in order to increase the quantity of water available for the municipal water supply system. During my visit and subsequently I collected geolgical information and data regarding existing important bores and wells.

The main existing bores and wells are:

1. Municipal well No.1, situated between the main road and municipal garden. This well represents now the main source of water for Tulkarem town. It was drilled by Government and is registered as bore No.2720; the watter table rests at approximately 230 ft. below ground, i.e. at about 17.3 ms. above sea level. After being drilled in 1934 test pumping yielded about 20 m³/h of water at a small draw down. A larger quantity may be pumped allowing a greater draw-down. The salinity is 5.2 parts per 100,000. The description of the formations as given by the Government is as follows:

0 - 230 ft.	Unknown (shaft).
230 - 245 "	Soft limestone.
245 - 250 "	Soft limestone and some clay.
250 - 255 "	Soft limestone.
255 - 260 "	Soft white limestone (probably Turonian).
260 - 265 "	White limestone.
265 - 270 "	Soft white flinty limestone.
270 - 275 "	Yellow marly limestone.
275 - 290 "	Marly limestone.
290 - 310 "	White limestone.
310 - 315 "	Hard yellow limestone.
at 315 ft.	Quartz sand and loose yellow sand.

2. Municipal Well, Government No.676; yield about 8 m³/h. Formations:

0.0 - 12.0 ms.	Chalk.
12.0 - 13.0 "	Hard limestone.
13.0 - 24.5 "	Chalk.
24.5 - 25.5 "	Hard limestone.
25-5 - 95.0 "	Chalk.

This bore situated on the southern side of the main road is not in use.

3. Municipal bore, Government No.673; water table above sea 20.62 ms. Yield 3m³/h.
Formations:

9.0 - 40.0 ms.	Chalk.
40.0 - 75.0 "	Hard limestone.
75.0 - 77.5 "	Chalk.
77.5 -129.5 "	(?) hard porous limestone.

This bore again is not in use.

4. Well Kadoorie School. Formations:

0.0 - 8.0 ms.	Unknown.
8.0 - 58.0 "	Chalk.
58.0 - 62.0 "	Hard limestone

Yield 29.2 m³/h. at 2.77 ms. draw down; salinity 5 parts per 100,000.

5. Kamal well. Drilled 1944-45 by Messrs. Emmanuel & Rifkind to 81 ms.

depth. This well is situated north of the main road from Tulkarm to Nablus. Water level 58 ms. below ground; a vertical pump installed at 74 ms. below gr und and delivered during 17½ hours of test pumping a quantity of approximately 39-40 m^3/h. at a drawdown 9.5 ms.

6. Army bore. This bore was drilled in 1942-43 by Messrs. Hassadeh Tel-Aviv for the Army, at a distance of 300 ms. west - northwest of the station building of Tulkarem Railway station. Total depth 80 ms.; wate level 29 ms. below ground, yield 74 m^3/h at 2.1 ms. drawdown. The bore is cased with blind pi es of 14" diameter from the surface of the ground to 56.5 ms. and between 61.5 - 67 ms. depth. Perforated pipes of 10" diameter are inserted between 56.5 - 61.5 ms. and between 67-80 ms. dept

Formations:

0.0 - 1.5	ms.	Brown-gray loamy soil.
1.5 - 2.8	"	Db. with limestone breccie and limestone boulder
2.8 - 10.6	"	Boulders (?) consisting of hard limestone and fl
10.6 - 58.5	"	Light-coloured greyish yellowish marl.
58.5 - 61.6	"	Sandy soft marl.
61.6 - 66.6	"	Greyish-greenish marly clay.
66.6 - 80.0	"	White hard porous limestone (water-bearing).

As may be seen from the existing bores and wells conditions for the supply of water at and near Tulkarem are not regular; One bore did not open up a suitable supply to nearly 130 ms. depth although a second one at a small distance only from the former one and brought down to les depth yields a good supply. Formations at Tulkarem consist of chalks an marls which belong to lower Seconian layers of Cretaceous formations. These strata are usually no -water-bearing. They are underlain by hard and sometimes porous limestones of Turnonian age which under favourable conditions are good water-bearing layers. Both the marls and chalks as also the limestones dip in the direction of coastal plain where they ar covered by any increasing thickness of soil, loam, and clay. At a shor distance westwards of Tulkarem the mo ntain layers - invisible from th faulted down. This is evident from a deep bore near Bir Burin about 2.5 kms. west of Tulkarem which did not reach the limestone formations to a great depth.

It appears from the facts collected that the water travels mainly in the hard and porous limestone layers in th form of fissures and cracks and not as a regular horizon. The development of a water horizon which would be safer for drilling and for water supply appears more to the west of Tulkarem town that at Tulkarem itself or east it. We should, therefore, think that the best area for drilling northwest and west of Tulkarem town where a bore site would have to be selected at a suitable distance from one of the existing wells in order not to be influenced by them.

After all, what can be said on the basis of the existing bores and the general geological conditions, a new bore would have to be brought down to at least 80 ms. if not to 100 ms. depth.

According to information received from engineer Shiloni, Tel-A the main 6" pipeline runs from the municipal well to the main resevoir An extension of this pipeline is said to go a certain distance in the direction of the Railway Station. If a new well were therefore, be ma west or northwest of the town as proposed it might be possible to use existing pipes.

In order to decrease the risks which are inevitable connected with the drilling of a new well it is proposed that a number of geoph-sical measurements should be carried out to test the subsoil at vari places. Such geophsical measurements as we carry out afford more sec for the selection of a favourable bore site than can be obtained on t basis of geological data alone. A geophysical survey to select the b bore wite near Tulkarem and to indicate the depth to which the bore w have to be drilled would cost .110.-. The time for carrying out the survey would be about one week and two weeks previous notification w be necessary for the start of the measurements. In the event that t municipality would decide to have such a survey carried out, the fe for this report would be deducted from the cost of the survey.

Yours faithfully,

Sgd.

Dr. A. & F. LOHNBERG

AL/ET.

Copy.

20th July, 1945.

Secretary,
Municipality,
TULKAREM.

Dear Sir,

Subject: Water supply.

On 11th July, 1945, I visited the Tulkarem area with a view to examine the possiblities of sinking a new well at near Tulkarem in order to increase the quantity of water available for the municipal water supply system. During my visit and subsequently I collected geolgical information and data regarding existing important bores and wells.

The main existing bores and wells are:

1. Municipal well No.1, situated between the main road and municipal garden. This well represents now the main source of water for Tulkarem town. It was drilled by Government and is registered as bore No.2720; the watter table rests at approximately 220 ft. below ground, i.e. at about 17.3 ms. above sea level. After being drilled in 1934 test pumping yielded about 20 m³/h of water at a small draw down. A larger quantity may be pumped allowing a greater draw-down. The salinity is 5.2 parts per 100,000. The description of the formations as given by the Government is as follows:

0 - 230 ft.	Unknown (shaft).
230 - 245 "	Soft limestone.
245 - 250 "	Soft limestone and some clay.
250 - 255 "	Soft limestone.
255 - 260 "	Soft white limestone (probably Turonian).
260 - 265 "	White limestone.
265 - 270 "	Soft white flinty limestone.
270 - 275 "	Yellow marly limestone.
275 - 290 "	Marly limestone.
290 - 310 "	White limestone.
310 - 315 "	Hard yellow limestone.
at 315 ft.	Quartz sand and loose yellow sand.

2. Municipal Well, Government No.676; yield about 8 m³/h. Formations:

0.0 - 12.0 ms.	Chalk.
12.0 - 13.0 "	Hard limestone.
13.0 - 24.5 "	Chalk.
24.5 - 25.5 "	Hard limestone.
25-5 - 95.0 "	Chalk.

This bore situated on the southern side of the main road is not in use.

3. Municipal bore, Government No.678; water table above sea 20.62 ms. Yield 3m³/h.
Formations:

0.0 - 40.0 ms.	Chalk.
40.0 - 75.0 "	Hard limestone.
75.0 - 77.5 "	Chalk.
77.5 -129.5 "	(?) hard porous limestone.

This bore again is not in use.

4. Well Kadoorie School. Formations:

0.0 - 8.0 ms.	Unknown.
8.0 - 58.0 "	Chalk.
58.0 - 62.0 "	Hard limestone

Yield 29.2 m³/h. at 2.77 ms. draw down; salinity 5 parts per 100,000.

5. Kamal well. Drilled 1944-45 by Messrs. Emmanuel & Rifkind to 81

depth. This well is situated north of the main road from Tulkarm to Nablus. Water level 58 ms. below ground; a vertical pump installed at 74 ms. below gr und and delivered during 17½ hours of test pumping a quantity of approximately 39-40 m³/h. at a drawdown 9.5 ms.

6. Army bore. This bore was drilled in 1942-43 by Messrs. Hassadeh Tel-Aviv for the Army, at a distance of 800 ms. west - northwest of the station building of Tulkarem Railway station. Total depth 80 ms.; water level 29 ms. below ground, yield 74 m³/h at 2.1 ms. drawdown. The bore is cased with blind pi es of 14" diameter from the surface of the ground to 56.5 ms. and between 61.5 - 67 ms. depth. Perforated pipes of 10" diameter are inserted between 56.5 - 61.5 ms. and between 67-80 ms. depth
Formations:

0.0 - 1.5 ms.		Brown-grey loamy soil.
1.5 - 2.8	"	Do. with limestone breccie and limestone boulders
2.8 - 10.6	"	Boulders (?) consisting of hard limestone and fli
10.6 - 58.5	"	Light-coloured greyish yellowish marl.
58.5 - 61.6	"	Sandy soft marl.
61.6 - 66.6	"	Greyish-greenish marly clay.
66.6 - 80.0	"	White hard porous limestone (water-bearing).

As may be seen from the existing bores and wells conditions for the supply of water at and near Tulkarem are not regular. One bore did not open up a suitable supply to nearly 130 ms. depth although a second one at a small distance only from the former one and brought down to less depth yields a good supply. Formations at Tulkarem consist of chalks and marls which belong to lower Seconian layers of Cretacious formations. These strata are usually no -water-bearing. They are underlain by hard and sometimes porous limestones of Turnonian age which under favourable s conditions are good water-bearing layers. Both the marls and chalks as also the limestones dip in the direction of coastal plain where they are covered by any increasing t ickness of soil, loam, and clay. At a short distance westwards of Tulkarem the mo ntain layers - invisible from the faulted down. This is evident from a deep bore near Bir Burin about 2.5 kms. west of Tulkarem which did not reach the limestone formations to a great depth.

It appears from the facts collected that the water travels mainly in the hard and porous limestone layers in th form of fissures and cracks and not as a regular horizon. The development of a water horizon which would be sager for drilling and for water supply appears more to the west of Tulkarem town that at Tulkarem itself or east it. We should, t erefore, t ink that the best area for drilling northwest and west of Tulkarem town where a bore site would have to be selected at a suitable distance from one of the existing wells in order not to be influe ced by them.

After all, what can be said on the basis of the existing bores s and the general geological conditions, a new bore would have to be brought down to at least 80 ms. if not to 100 ms. depth.

According to informati n received from engineer Shiloni, Tel-Avi the main 6" pipeline runs from the municipal well to the main resevoir. An extensi n of this pipeline is said to go a certain distance in the direction of the Railway Station. If a new well were therefore, be made west or northwest of the town as proposed it might be pos ible to use the existing pipes.

In order to decrease the risks which are inevitable connected with the drilling of a new well it is proposed that a number of geophsical measurements s ould be carried out to test the suxbsoil at various places. Such geophsical measurements as we carry out afford more securi for the selection of a favourable bore site than can be obtained on the basis of geological data alone. A geophysical survey to select the best bore wite near Tulkarem and to indicate t e depth to which the bore would have to be drilled would cost .110.-. The time for carrying out the survey would be about one week and two weeks previ us notification would be necessary for the start of the measurements. In the event that the municipality would decide to have such a survey carried out, the fees for this report would be deducted from the cost of the survey.

Yours faithfully,

Sgd.

AL/ET. Dr.A.& E.LOEHNBERG

Copy.

29th July, 1945.

Secretary,
Municipality,
TULKAREM.

Dear Sir,

Subject: Water supply.

On 11th July, 1945, I visited the Tulkarem area with a view to examine the possiblities of sinking a new well at near Tulkarem in order to increase the quantity of water available for the municipal water supply system. During my visits and subsequently I collected geolgical information and data regarding existing important bores and wells.

The main existing bores and wells are:

1. Municipal well No.1, situated between the main road and municipal garden. This well represents now the main source of water for Tulkarem town. It was drilled by Government and is registered as bore No.2720; the water table rests at approximately 220 ft. below ground, i.e. at about 17.3 ms. above sea level. After being drilled in 1934 test pumping yielded about 20 m³/h of water at a small draw down. A larger quantity may be pumped allowing a greater draw-down. The salinity is 5.2 parts per 100,000. The description of the formations as given by the Government is as follows:

0 - 230 ft.	Unknown (shaft).
230 - 245 "	Soft limestone.
245 - 250 "	Soft limestone and some clay.
250 - 255 "	Soft limestone.
255 - 260 "	Soft white limestone (probably Turonian).
260 - 265 "	White limestone.
265 - 270 "	Soft white flinty limestone.
270 - 275 "	Yellow marly limestone.
275 - 290 "	Marly limestone.
290 - 310 "	White limestone.
310 - 315 "	Hard yellow limestone.
at 315 ft.	Quartz sand and loose yellow sand.

2. Municipal Well, Government No.676; yield about 8 m³/h. Formations:

0.0 - 12.0 ms.	Chalk.
12.0 - 13.0 "	Hard limestone.
13.0 - 24.5 "	Chalk.
24.5 - 25.5 "	Hard limestone.
25.5 - 95.0 "	Chalk.

This bore situated on the southern side of the main road is not in use.

3. Municipal bore, Government No.678; water table above sea 20.62 ms. Yield 3m³/h.
Formations:

0.0 - 40.0 ms.	Chalk.
40.0 - 75.0 "	Hard limestone.
75.0 - 77.5 "	Chalk.
77.5 -129.5 "	(?) hard porous limestone.

This bore again is not in use.

4. Well Kadoorie School. Formations:

0.0 - 8.0 ms.	Unknown.
8.0 - 58.0 "	Chalk.
58.0 - 62.0 "	Hard limestone

Yield 29.3 m³/h. at 2.77 ms. draw down; salinity 5 parts per 100,000.

5. Kamal well. Drilled 1944-45 by Messrs. Emanuel & Rifkind to 81 ms.

depth. This well is situated north of the main road from Tulkarm to Nablus. Water level 58 ms. below ground; a vertical pump installed at 1 ms. below gr und and delivered during 17½ hours of test pumping a uantity of approximately 39-40 m^3/h. at a drawoown 9.5 ms.

Army bore. This bore was drilled in 1942-43 by Messrs. Hassadeh Tel-Aviv for the Army, at a distance of 500 ms. west - northwest of the station building of Tulkarem Railway station. Total depth 80 ms.; water level 29 ms. below ground, yield 74 m^3/h at 8.1 ms. drawdown. The bore is cased with blind pi es of 14" diameter from the surface of the ground to 56.5 ms. and between 61.5 - 67 ms. depth. Perforated pipes of 10" diameter are inserted between 58.5 - 61.5 ms. and between 67-80 ms. depths
Formations:

0.0 - 1.5 ms.		Brown-grey loamy soil.
1.5 - 2.8	"	Ib. with limestone breccie and limestone boulders.
2.8 - 10.6	"	Boulders (?) consisting of hard limestone and flir
10.6 - 58.5	"	Light-coloured greyish yellowish marl.
58.5 - 61.6	"	Sandy soft marl.
61.6 - 66.6	"	Greyish-greenish marly clay.
66.6 - 80.0	"	White hard porous limestone (water-bearing).

As may be seen from the existing bores and wells conditions for the supply of water at and near Tulkarem are not regular. One bore did not open up a suitable supply to nearly 130 ms depth although a second one at a small distance only from the former one and brought down to less depth yields a good supply. Formations at Tulkarem consist of chalks and marls which belong to lower Seconian layers of Cretaceous formations. These strata are usually non-water-bearing. They are underlain by hard and sometimes porous limestones of Turnonian age which under favourable xx conditions are good water-bearing layers. Both the marls and chalks as also the limestones dip in the direction of coastal plain where they are covered by any increasing thickness of soil, loam, and clay. At a short distance westwards of Tulkarem the mountain layers - invisible from the faulted down. This is evident from a deep bore near Bir Burin about 2.5 kms. west of Tulkarem which did not reach the limestone formations to a great depth.

It appears from the facts collected that the water travels mainly in the hard and porous limestone layers in th form of fissures and cracks and not as a regular horizon. The development of a water horizon which would be safer for drilling and for water supply appears more to the west of Tulkarem town that at Tulkarem itself or east it. We should, t erefore, think that the best area for drilling northwest and west of Tulkarem town where a bore site would have to be selected at a suitable distance from one of the existing wells in order not to be infl enced by them.

After all, what can be said on the basis of the existing bores s and the general geological conditions, a new bore would have to be brought down to at least 80 ms. if not to 100 ms. depth.

According to informati n received from engineer Shiloni, Tel-Aviv the main 6" pipeline runs from the municipal well to the main reservoir. An extensi n of this pipeline is said to go a certain distance in the direction of the Railway Station. If a new well were therefore, be made west or northwest of the town as pr posed it might be pos ible to use the existing pipes.

In order to decrease the risks which are inevitable connected with the drilling of a new well it is proposed that a number of geophsical measurements s ould be carried out to test the suxbsoil at various places. Such geophsical measurements as we carry out afford more security for the selection of a favourable bore site than can be obtained on the basis of geological data alone. A geophysical survey to select the best bore wite near Tulkarem and to indicate t e depth to which the bore would have to be drilled would cost .110.-. The time for carrying out the survey would be about one week and two weeks previ us notification would be necessary for the start of the measurements. In the event that the municipality would decide to have such a survey carried out, the fees for this report would be deducted from the cost of the survey.

Yours faithfully,

Sgd.

AL/ET.   Dr.A.& E.LOEHNBERG

NO.T/156/87.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

3rd.August,1945.
26th Sept. 1945

Asst.Liaison Officer,
Samaria.

Subject:- Tyres for Tulkarm Municipal Water Truck.

The Chairman,Municipal Commission of Tulkarm submits that two of the tyres on the Municipal Water Truck,Tulkarm, need replacement.

You will recollect that this water truck,did extra duty la last autumn moving drinking water from Tulkarm to Anabta in view of the breakdown of the Anabta Water Supply, a total of 214 journeys of 19 kilometers each being made.

Your assistance is securing the above would be much appreciated.

I attach the application forms duly filled out.

N 26/9.

Assistant District Commissioner,
Tulkarm.

JS/AT P.S. It took all that time for the M.C., TK. to secure the forms and fill them in. (Sgd) J.S. 26/9

[illegible]

[illegible]

[illegible]

[illegible]

Subject:- Funds for Nilgiris Municipal Water Board.

The Chief, Central Commission of [illegible] reports that two of the [illegible] on the [illegible] need replacement.

You will recall that this water truck did extra duty [illegible] in view of the breakdown of the [illegible] water supply, a total of 416 journeys of 45 Kilometers each being made.

Any assistance in expediting the above would be much appreciated.

I attach the application forms duly filled in.

Assistant District Commissioner.

[illegible]

Note.

Spoke with the C.C. of Tulkarm Municipality four times, on 27.8.45, 3.9.45, 6.9.45., 12.9.45. and reminded him to send the forms.

[signature]

12.9.45.

B.F. when the forms received

[signature]

Mohd. Eff. Busheng of the Municipality will receive the required forms today.

[signature]

22.9.45.

a.o.c.

Application is now attached.

[signature]

25.9.45

C.C.

There are forms which we must fill

at. Pl ask Ch. W.C. of Th to receive such

and complete them. They can then be

forwarded with above.

[illegible] 2/8

??

C.C. Pl. arrange early

[illegible] 27/8

Authority to thresh or gather crops

تصريح لدرس المحصولات او جمعها

רשות לדוש תבואה או לקבצה.

The crops as assessed above and inspected by me may now be threshed or gathered

ان المحصولات المخمنة اعلاه والتي عوينت من قبلي يجوز درسها او جمعها

היבול אשר הוערך כדלעיל ואשר בקרתיו יוכל עתה להיות נדוש או מקובץ

Inspector
المفتش
המפקח

Date .... التاريخ
התאריך

[illegible] where
they came fr
9/1

KAR

I receive forgery

Spone with the C.C. of
Municipality 4 times & they
[illegible] from [illegible] S.C. [illegible]

جراه وانه في الصابون وفي هذا الشهر

ثمن كل رطل ثمانية وسبعون مل فيكون الفر

هذا وفي الختام نرجو ان تنصفونا نحن

واقبلوا احترامنا .

بلدية طولكرم

صندوق البريد رقم ٩

التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة

رقم ٣/٤٤

ASSISTANT DISTRICT COMMISSIONER

1 AUG. 1945

156

86

طولكرم في ١/٨/١٩٤٥

سعادة مساعد حاكم اللواء في طولكرم المحترم.

الموضوع - سيارة رش الشوارع

الاشارة - كتابكم رقم ١٥٦ /٥٤ تاريخ ٢٦/٩/٤٤

بلغ عدد نقلات الماء التي نقلتها سيارة رش الشوارع الى عنهتا ٢١٤ نقله . وحيث ان سيارة الرش اصبحت بحاجة الى دولابين كاوتشوك خارجيين (تاير) من قياس ٣٠/٥ ودولابين داخليين (تيوب) لذلك فانني اكون ممتنا اذا اوصيتم باعطاء بلدية طولكرم التصاريح اللازمة لشرائها .

وتفضلوا بقبول فائق الاحترام .

رئيس لجنة بلدية طولكرم

NO.T/156/85.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

1st.August,1945.

District Commissioner,
Samaria District.

Subject:- Purchase of Pump for the Tulkarm Municipal Commission Water Supply.

Ref'nce:- My No.T/156/83 dated 18.7.45.

A copy of Director of Public Work's No.5/5/7 dated 13.7.45 was passed to the Chairman,Municipal Commission of Tulkarm who now comments thereon as follows:-

" The Municipal Commissinn of Tulkarm has studied the Director of Public Work's letter and has authorized me to reply as follows:

1) The Municipal Commission of Tulkarm will keep in mind all the points raised by the Director of Public Works when it commences on its new water supply scheme in Tulkarm, even as it has already commenced to seek the best site through experts.

2) As regards the motor and pump it proposes to purchase now, there are to be in reserve to supplement the motor and pump now existent on which the whole supply depends and which, as has been the case several times during the war years, may fail. We searched long and did not find in all Palestine anything suitable to our needs other than a pump at the firm of the Engineer Rothgold, a motor for which he expects to receive in the next few days. Had we wanted to get plant from outside we should have to wait at least ten months to receive it. We therefore consider this an opportunity which we should not miss and we may find ourselves with nothing when we are in the direct need.

3) The Director of Public Works agreed that the price of the motor and pump is reasonable. It so happens that this price does not exceed our budget provision. I therefore consider that we should contract for the purchase thereof and apply for the necessary release permits. I therefore attach an official application for the purchase of the pump and motor from Messrs Rothgold with the request that such be forwarded to the appropriate authorities with your recommendation in view of the importance thereof to the public interest.

4) We shall carry out the instructions of the Director of Public Works as far as such can be applied to the pump and motor we propose to purchase.

5) I shall be very grateful if you will consider this request as of an urgent nature."

I fully endorse the request.

Reg. 218 [illegible]

Assistant District Commissioner,
Tulkarm.

JS/AT

Enc.3

[illegible]

[illegible]
[illegible]

[illegible]

[illegible]
[illegible]

Subject: [illegible]
[illegible]

Reference: [illegible]

[illegible] follows:-

[illegible]

[illegible] as follows:

(1) [illegible]

(2) [illegible]

(3) [illegible]

(4) [illegible]

[illegible]

I fully [illegible] the [illegible].


[illegible]
[illegible]

84

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء أن تذكروا عند الاجابة
رقم ٥/٨٦



P. 82

طولكرم في ٢٩/٧/١٩٤٥

سعادة مساعد حاكم اللواء في طولكرم المحترم

الموضوع ـ مشروع المياه

الاشارة ـ كتابكم رقم ١٥٦/٢/٨ تاريخ ١٦/٧/١٩٤٥

اطلع مجلس بلدية طولكرم على كتاب سعادة مدير الاشغال العامة المرفق بكتابكم المشار اليه اعلاه وفوضني باعطاء الجواب على الوجه الآتي ـ

أ ـ ستأخذ بلدية طولكرم بعين الاعتبار جميع النقاط التي اشار اليها سعادة مدير الاشغال العامة عندما تقوم بانشاء المشروع الجديد للمياه في طولكرم على البئر الذي شرعت في البحث عن موقعه بواسطة خبراء فنيين

٢ ـ اما الموتور والطلمبة المزمع شراؤهما الآن فليست الا من قبيل الاحتياط لكي تقوم مقام الموتور والطلمبة التي يعتمد المشروع الحالي عليهما وحدهما الآن حتى لا ينقطع الماء في المدينة اذا طرأ عليهما خلل كما حدث لعدة مرات في سني الحرب. ولقد بحثنا طويلاً فلم نجد في فلسطين ما يوافق مشروعنا واذا طلبنا الآلات من الخارج علينا ان ننتظر عشرة اشهر حتى نحصل عليها . وكان من حسن الحظ وجود طلمبة صالحة لمشروعنا عند المهندس سروشجولد وتوقع وصول موتور لها خلال ايام معدودات وهذه فرصة ينبغي ان لا تفوتنا ابدا فقد لا تسنح لنا مرة اخرى عندما نجد انفسنا في امس الحاجة اليها

٣ ـ لقد وافق سعادة مدير الاشغال العامة على ان ثمن الموتور والطلمبة معقول وعادل . وهو بذات الوقت لا يتجاوز الحد الاعلى المصرح لبلدية طولكرم بالتعاقد عليه لذلك فاني ارجو ان تمادي لعقد الاتفاق وطلب الحصول على التصاريح الرسمية . وبناء على ذلك فاني اقدم لسعادتكم الطلبات الرسمية للحصول على التصاريح لشراء الموتور والطلمبة من المهندس سروشجولد راجيا تقديمها الى السلطات المرخصة مع توصيتكم للاسراع باصدارها نظرا لاهميتها للصلحة العامة .

٤ ـ سنعمل بتعليمات سعادة مدير الاشغال العامة بالقدر الذي ينطبق عليه على الموتور والطلمبة المزمع شراؤهما وضمن حدود الامكان

٥ ـ اكون ممتنا جدا اذا اعتبرتم طلبي هذا من الامور المستعجلة

وتفضلوا بقبول فائق الاحترام .

[توقيع]

رئيس لجنة بلدية طولكرم

NO.T/156/83.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

18th July, 1945.

District Commissioner,
Samaria District.

Subject:- Purchase of Pump for the Tulkarm Municipal Commission Water Supply

Ref'nce:- My No.T/156/78 dated 25.6.45. and our conversation.

I transmit herewith a copy of the Director of Public Work's reply to my above.

The Chairman, Municipal Commission of Tulkarm feels that the pump in question being actually available at Tel-Aviv and the price being reasonable, permission to purchase, subject to the make and efficacy being satisfactory, is very desirable.

To lose further time in seeking bids etc is, in his opinion worth avoiding. especially as several of the firms mentioned were visited when the quest for a suitable pump was being carried out.

Assistant District Commissioner,
Tulkarm.

JS/AT

مكتب مساعد حاكم اللواء بطولكرم

١٦/٧/١٩٤٥

الرقم ــ ١٥٦/٨٢

سعادة رئيس لجنة بلدية طولكرم المحترم

اشير الى كتابك المرقم ٨٦/٥ والمؤرخ ١٤/٧/١٩٤٥ .
انقل اليكم بطيه جواب سعادة مدير الاشغال العامة . وتفضلوا بقبول الاحترام .

مساعد حاكم اللواء
بطولكرم

١٧/٧/٤٥


181

الرجاء ان تذكروا عند الاجابة
رقم ٥/٨٦

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

طولكرم في ١٤/٧/١٩٤٥


16. JULY 1945

سعادة مساعد حاكم اللواء المحترم.

الموضوع. مشروع المياه

الاشارة. كتابي رقم ٥/٨٦ تاريخ ٢١/٦/١٩٤٥

حضر المهندس روشجولد الى طولكرم يوم ٢٥/٦/١٩٤٥ ومعه الاتفاقيات لشراء الطلمبة والموتور حسبما بحثت لسعادتكم في كتابي السابق ومعه ايضا الطلبات الرسمية للسلطات المرخصة لاجل اصدار تصريح للبلدية لشراء الموتور والطلمبة. ولكنا بناء على اشارة تلفونية من سعادتكم علمنا بانكم طلبتم رأى دائرة الاشغال العامة في الموضوع ولذلك فاننا ارجأنا توقيع الاتفاقيات مع المهندس روشجولد على أمل ان تاخذوا جوابا من دائرة الاشغال وتصلنا موافقتكم بوقت قريب.

تعلمون بان مشروع الماء في طولكرم يقوم على موتور وطلمبة وحيدين ويخشى ان يطرأ خلل في الالات فينقطع الماء عن المدينة في هذا الفصل الحار من السنة ويعاني السكان من جراء ذلك ضائقة كبيرة. وثمن الموتور والطلمبة الجديدين زهيد جدا قد تزيد عنه نفقات اصلاح الالات الحالية اذا طرأ عليها خلل. ولهذه الاسباب اتيت ارجوكم بان توافقوا على امضاء المقاولة لشراء الطلمبة والموتور الجديدين باقرب وقت مستطاع حتى تتمكن من انجاز معاملات التصريح من السلطات المرخصة والقيام بالتحضيرات اللازمة واستلام الموتور والطلمبة وتركيبها دون اى تأخير.

وتفضلوا بقبول فائق الاحترام.

[signature]

رئيس لجنة بلدية طولكرم

Letter to P.W.D., N. [initials] 16/7

see 82 pl.

5/5/7.

PUBLIC WORKS DEPARTMENT
JERUSALEM
13th July, 1945.

80

Assistant District Commissioner,
Tulkarm.

P.78

Subject : Tulkarm Municipal Commission - Water Supply - Purchase of Pump.
Reference: Your T/156/78 of 25.6.1945.

156, P.61 G.T.

This matter should be dealt with under G.R.306. The following comments however made with the superficial information available to me may be of use.

a) The Municipal authorities should be satisfied that the well can yield as much water as the pump can deliver, throughout the year. If the pump 'beats' the well it will suck air, with damaging results.

b) The figures quoted in the first paragraph of the suppliers' letter relating to total manometric head should be confirmed.

c) The depth of water level in the well appears to fluctuate by 5 metres. The pump would have to be placed at least a metre above the highest water level. In this position it would have a suction lift of 6-6.5 metres when water level was at its lowest. Even if the supplier can guarantee it, such a large suction head is undesirable. It would reduce the life of the pump, and be a constant source of trouble.

d) A reflux valve should be provided on the rising main near to the pump with an arrangement for priming the pump.

e) No mention is made in the offer to provide suitable starting gear. The motor specified (380/660 volts) should be "Delta" or "Mesh" connected, and be connected to a "star delta" or preferably an Auto-Transformer Starter. The starting current should not exceed twice the full load current.

f) The price of the plant offered is considered fair and reasonable.

g) An electrically driven vertical centrifugal pump is considered more suitable for this well with its fluctuating water level. This type of pump should also be provided with a suitable starter to ensure that the starting current does not exceed twice the full load current.

2. It is not known whether the offer which you have sent to me for my advice is the only tender that has been made. It is advised that tenders should be called from at least 6 firms, to ensure obtaining the best quotations available. It is also advised that firms which are asked to quote for this plant should be told that British pumping plant is acceptable, and that offers need not be confined to foreign made pumping units.

See 83

3. I append a list of firms who deal in pumping plant.

1. Messrs.A. Sidaver & Co. Eng. Ltd., P.O.B.271, Tel Aviv.
2. Messrs.Engineering & Manufacturing Co.Ltd., P.O.B.1191, Tel Aviv.
3. Mr.A. Koch, Engineering Works & Supplies, P.O.B.707, Jerusalem.
4. Messrs.Industrial & Engineering Enterprises Ltd., P.O.B.152 J'lem.
5. Mr.M. Burger Mech.Engineering, P.O.B. 302, Tel Aviv.
6. Mr.J. Roszgold " " " 632 " "
7. Mr.A. Zallel, Eng. " 173 " "
8. Messrs.General Engineering Co. of Palestine & Levant, P.O.B.1419, Tel Aviv.
9. Messrs.Haifa Engineering Co.Ltd., P.O.B. 1449, Haifa.
10. Messrs.S.Awad & Co.(Wagner Engineering Section), Jaffa-Tel Aviv Road, Jaffa.

Copy to: District Engineer, Nablus District.
T2. C.E.M.E.

for R.F.C.Brooks
ACTING DIRECTOR OF PUBLIC WORKS

'NO.T/156/79.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

79

7th July,1945.

Director of Public Works,
Jerusalem.

Subject:- Purchase of Pump for the Tulkarm Municipal Commission Water Supply.

Ref'nce:- My No.T3156/78 dated 25.6.45.

May I know how this matter now stands.

Assistant District Commissioner,
Tulkarm.

9/7/45

JS/AT

NO.T/156/78. 78

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

25th June, 1945.

Director of Public Works,
Jerusalem.

REGISTERED

Subject:- Purchase of Pump for the Tulkarm Municipal Commission Water Supply

The Municipal Commission of Tulkarm has budge provision this year for the purchase and erection of supplementary pump for its Water Supply.

The make recommended to them as being best suited to meet their requirements is a Fairbanks - Morse, details of which are given in the attached letter and enclosures.

The water level in their well stands at 65-70 meters depth and the minimum quantity of water required daily is 500 cubic meters.

In view of the fact that the old pump - a 45 H.P. centrifugal raising 50 m3 per hour - is not reliable, the Chairman has made an appeal that the matter be treated as urgent.

Kindly return enclosures with your reply.

26/6

Assistant District Commissioner,
Tulkarm.

Copy to: District Commissioner.
Samaria District. ref his No.515-4
dated 25.?.45.

See p. 94

see 87 sup. 80 see 79

Enc.3

JS/AT

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٥/٨٦

١٩٤٥/٦/٢١



طولكرم في

سعادة مساعد حاكم اللواء المحترم .

الموضوع - مشروع المياه

بحثنا طويلا بواسطة خبراء يعتمد عليهم عن موتور يوافق مشروع المياه الحاضر في طولكرم حتى اذا طراء خلل على الموتور المركب في البئر تستعمل الموتور الجديد حالا دون ان تتوقف حركة توزيع الماء في المدينة . لم نجد في فلسطين موتوراً صالحا لمشروعنا وأخيرا تقدم لنا عطاء من المهندس روشجولد يعرض علينا فيه طلمبة جديدة وموتور وتوابعهما صنع معامل فيربانكس مورس بامريكا وهي من احدث الالات وتوافق بصورنا كل الموافقة وثمن الموتور والطلمبة كما هو مبين في العطاء الذى اقدمه لسعادتكم ربطا ٣٩٨ جنيها . الطلمبة جاهزة في تل ابيب وينتظر ان يصل الموتور خلال شهر ونصف .
سيحضر المهندس روشجولد الى طولكرم في الاسبوع القادم وربما كان ذلك يوم الاثنين في ٢٥/٦/٤٥ ومعه الاتفاقيات للتوقيع عليها والطلب للسلطات المرخصه لاجل أصدار تصريح للبلدية بشراء الموتور والطلمبة واننا نحتاج الى موأزرة سعادتكم لسرعة الحصول على التصريح المطلوب . اكون ممتنا اذا اعدتم لنا العطاء مع الكتالوجات المرفقة به بعد اطلاعكم عليها .

وتفضلوا بقبول فائق الاحترام .

[signature]

رئيس لجنة بلدية طولكرم

See P. 109 pl.

76

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٨٥ / ٥

٧ / ٣ / ١٩٤٥

8 MAR 1945

سعادة مساعد حاكم اللواء في طولكرم المحترم

P.75

الموضوع :- بئر المدينة
الاشارة :- كتابكم رقم ١٥٦ تاريخ ٢ / ٣ / ١٩٤٥

بحث مجلس بلدية طولكرم في ما تضمنه كتاب سعادة حاكم اللواء فقرر الشروع بالمفاوضة لتركيب طلمبة جديدة لمشروع الماء. وقرر ايضاً البحث عن قطعة ارض في محل مناسب بمساحة دونم تقريباً لاستعمالها مداخل حفر بئر فيها وسينفق عن كل ذلك من الاعتماد الموضوع في الباب ٩ الفصل ٨ من قسم المفروضات في ميزانية بلدية طولكرم لسنة ١٩٤٥ / ٤٦ . اما تركيب الالات للمشروع الجديد فتقرر اجادته لحين ظهور نتيجة العمل في حفر البئر.

وتفضلوا بقبول فائق الاحترام

[signature]
رئيس لجنة بلدية طولكرم

ADC 9/3
DO
SC 10/3

مكتب مساعد حاكم اللواء بطولكرم

٢/٣/١٩٤٥

الرقم - ١٥٦

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع :- بئر المدينة .

اشير الى كتابكم المرقم ٨٥/٥ والمؤرخ ١١/٢/١٩٤٥
وانقل اليكم جواب سعادة حاكم اللواء ؛

وتفضلوا بقبول فائق الاحترام .

مساعد حاكم اللواء
بطولكرم

see page 76 pt.

GOVERNMENT OF PALESTINE.

IN REPLY PLEASE QUOTE
NO. 515 - 4

156

28 FEB 1945

DISTRICT COMMISSIONER'S OFFICES.
SAMARIA DISTRICT.
NABLUS.
25th February, 1945

Asst. Dist. Commissioner,
Tulkarm

P.73

Subject:- Municipal Water Supply Tulkarm Purchase of a new pump.
Reference: Your T/156/73 of 20-2-45.

I agree that the Chairman may start negotiations for the purchase of the new pump for which provision is made in the draft 1945/46 budget.

2. I suggest that provision should also be made in the 1945/46 budget for the cost of sinking a new well. There should be no need to provide for the erection of a pump thereon untill this new well has been sunk and proven. If provision to such a new well is made in the new budget I have no objections to preliminary negotiations for execution of the work.

D.C. [signature]

DISTRICT COMMISSIONER
SAMARIA DISTRICT

Pages 75 & 76
Inf. 92 M.

No. T/156/73.

13

Assistant District Commissioner's Office,
Tulkarm.

20th February, 1945.

District Commissioner,
Samaria District.

Municipal Water Supply Tulkarm-Purchase of a new pump.

The Chairman, Municipal Commission of Tulkarm asks whether he may be permitted to start negotiations for the purchase of a new pump to supplement the present motor pump.

He also asks whether he may be permitted to start negotiations for the sinking of a second well and erection of pump thereon.

The former, which has been considered for some time, appears very reasonable, especially as it forms part of the Budget Estimates.

The latter is, I think, somewhat premature.

Assistant District Commissioner
Tulkarm.

JS/KT.

20/2

see p. 74.

بلدية طولكرم

صندوق البريد رقم ٩

التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة رقم ٨٥/ه

12 FEB 1945

156

72

طولكرم في ١١/٢/١٩٤٥

سعادة مساعد حاكم اللواء في طولكرم المحترم

P.71

الموضوع :- بئر المدينة

الاشارة :- كتابكم رقم ١٥٦ تاريخ ٨/٢/١٩٤٥

51

لقد سمعت واطلعت على رأي كثيرين من الخبراء من عرب وغيرهم في موضوع مشروع الماء لطولكرم من جميع الوجوه وانى أعرف تماماً بأن مشروع الماء الحالي ناقص ومن المحتمل ان ينقطع الماء عن المدينة من حين لآخر. وانما بحاجة قصوى لمشروع جديد يؤمن توزيع المياه في المدينة بدون انقطاع. وهذه الحقائق كنت انقلها لسعادة مساعد الحاكم في مناسبات عديدة. وانى بصورة خاصة ألفت نظركم الى القسم الأخير من كتابي رقم ٨٥/ه تاريخ ٢٦/٦/١٩٤٤ وقد بينت فيه بصريح العبارة تخوفي من وقوع عطل في الآلات وانقطاع الماء.

٢ اما فيما يتعلق بارتفاع الماء في البئر فاننا قد قمنا سنة ١٩٤٢ برفع الموتور والطلمبة فوق اعلى مستوى وصل اليه الماء في تاريخ بئر طولكرم. ولم تعهد حالة البئر تسمح برفعها أكثر من ذلك وهذا رأي جميع الخبراء الذين كشفوا على البئر. اما ارتفاع الماء الاستثنائي هذه السنة فلم يكن في الحسبان. ولم تختص الطوارئ ببلدية طولكرم وحدها فهذه مدرسة خضوري الزراعية ومشروع مارجنين قد وقع لها نفس المشكل. بل هذه طرق عديدة بين مدن فلسطين قد أغلقت من جراء فيضان المياه عليها بمقدار لم يسبق له مثيل.

لقد قمنا الآن برفع الموتور الكبير والطلمبة الى علو مترين عن سطح الماء الحالي وقد اجمع الخبراء على أن الماء لن يصل للموتور مهما كثرت الامطار. وفي حالة انخفاض الماء كما هو منتظر في الصيف القادم فيبقى هذا الموتور قادراً عن السحب وفي حالة تعذر ذلك يبقى الموتور الصغير والطلمبة المخروقة الآن على عمق ثلاثة امتار بالبئر قادراً على سد حاجة المدينة الضرورية ليجري تنزيل الموتور الكبير الى مكانه الاساسي.

٢ اني اشكر لسعادتكم اهتمامكم في هذا الموضوع الحيوي لمدينة طولكرم وكم أكون ممتناً اذا أرشدتموني لحل أزمة المياه بصورة نهائية في مدينة طولكرم. وهي على رأي الخبراء تحل بالشكل الآتي :-

(أ) الخطوة العاجلة الأولى :- استحضار طلمبة عمودية تركب في أعلى البئر بدلاً من الطلمبة الحالية المركبة في أسفل البئر وتركيب الموتور الكهربائي الحاضر على الطلمبة الجديدة وبذلك يصبح ارتفاع الماء وانخفاضه عديم التأثير على مشروعنا ولا يبقى أي لزوم للنزول الى البئر من قبل الماكنجي وتخف نفقات صيانة المشروع لدرجة كبيرة. على أن هذا الحل يجب ان يعتبر مؤقتاً لأن حالة البئر على كل حال ليست مرضية ومياهه ملوثة، ولأنه من الضروري لمدينة مثل طولكرم أن يكون فيها بئرين منفصلين ولكل بئر مشروع مستقل حتى اذا طرأ على احدهما خلل يفي الآخر بحاجة المدينة.

72(A

(ب) نفر بئر في جهة والمنة حول المدينة والأرجح أنه تكون في الجهة الشمالية بسبب التجربة التي قام بها إسم افففكي ونظيرانا كانت تجربة ناجحة ، وتركيب أدوات حديثة لمشروع الماء تستورد من انكلترا أو من اميركا .

وبما أن الاستقصاء على طلبة وتركيبا بموجب الفقرة (أ) السابقة تكلف من (٧٠٠) الى (١٠٠٠) جنيه فاني أرجو أن تصرحوا لنا بالمفاوضة لاستحضارها باقرب وقت ممكن ثم توافقون لنا على اعتماد مبلغ من المال سلفاً من الموفر لسد هذه النفقات وفي نفس الوقت نتمكن على الحل الملائم للبئر الجديد ثم على مفاوضة الشركات المختصة لتقرير ولاستيراد الالات اللازمة للمشروع الجديد . فاذا تحقق مدينة طولكرم من أزمة مياهها بشكل مضمون مع عهد سعادتكم فان المدينة تبقى مدينة لكم الى الأبد .

وتفضلوا بقبول فائق الاحترام

[signature]

رئيس لجنة بلدية طولكرم

71

مكتب مساعد حاكم اللواء بطولكرم

رقم ـ ١٥٦
٨/٢/١٩٤٥

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع :- بئر المدينة

لا بد وأن الطارئ التي (الذي) وقع على بئر المدينة قد كان له شيء من التأثير غير الحسن على الرأي العام سواء كان ذلك بحق او بغير حق .

في هكذا ظروف من المعقول أن يدرس الأمر من كل وجوهه كي يؤمن عدم تكراره ان امكن .

ان التعديل الذي يحدث في مستوى ارتفاع الماء في البئر أمر مستوى اذ يزيد في الشتاء وينقص في الصيف بصورة متوالية وفي كلا الحالتين يحتاج المحرك الى رفع او انخفاض ولا بد من فترة تنقطع فيهما الماء .

نظرا لما جاء اعلاه وبمناسبة اطلاع الخبراء من عرب وغير عرب على الوضع اقترح عليكم مجرح (استمزاج) رأيهم في كيفية افضل الطرق لتأمين استمرار رفع الماء في المدة التي تنفذ فيها عملية الرفع او الانخفاض اذ في نوال ذلك ليس فقط المصلحة العامة بل رد كل انتقاد وازعاج .

وتفضلوا بقبول فائق الاحترام

مساعد حاكم اللواء
بطولكرم

See page 72 pl.

مكتب مساعد حاكم اللواء بطولكرم

٨/٢/١٩٤٥ الرقم – ١٥٦

<u>سعادة رئيس لجنة بلدية طولكرم المحترم</u>

لا بد وأن الط

70

مكتب مساعد حاكم اللــواء بطولكــرم

٢/٢/١٩٤٥   الرقم ــ ١٥٦

P. 61

سـعادة رئيس لجنة بلـدية طـولكــرم المحـترم

المـوضوع = ــ ملكية الارض التي انشئ عليها خزان الماء ٠

اشــير الى كتابكــم المرقــم ١/٥ والمؤرخ ٨/١/١٩٤٥

وارسل اليكــم صور التحارير المرســلة الي مــن قبل مـهندس الاشــغال في نابلـس في المــوضوع ٠

وتــفضلــوا بـقبول فائق الاحـــترام ٠

مــساعد حاكــم اللـــواء

بطولكــرم

١٠/٥
ﻃﻪ

GOVERNMENT OF PALESTINE

69

PUBLIC WORKS DEPARTMENT,
No. 3/1/2 NABLUS.
30th Jan., 1945.

1 FEB 1945 150

Asst. Dist. Commissioner,
Tulkarm.

P. 66

Sub:- Ownership of the Land on which the Tulkarm Municipal Water Reservoir Stands.

Ref:- Your letter No. T/156/66 dated 26th Jan., 1945.

Herewith, please.

DISTRICT ENGINEER
NABLUS DISTRICT

76/HZ.

694

Copy

10th October, 1935.

7/3

District Officer,
Tulkarm.

Subject :- Tulkarm Water Supply.

Reference :- Your 16/8 of 1.10.35.

The exact position of reservoir together with land reservation of 990 M2 area are marked on the plan of the State Domain properties No. D/Tul/41 and 42, returned, herewith.

DISTRICT ENGINEER
NABLUS DISTRICT

/SH.

COPY 28.9.35. 64

District Engineer, Nablus Dist.

Sub:- Tulkarm Water Supply.

I enclose herewith copy of the Director of Land Registration letter No.LD.73/8 of 12.9.35 and shall be glad if you will forward to me a copy of the plan showing the tracing, the exact position, and the area of the site required for the reservoir.

DISTRICT OFFICER

C O P Y

No. LD.73/8

Director of Land Registration,
P.O.B.356,
Jerusalem.
12th September, 1935.

District Officer,
Tulkarm.

Subject :- Tulkarm Water Supply.
Reference :- My LD.73/8-7078 of 27th August, 1935.

I enclose herewith the tracing of the plan of the State Domain properties D/TUL/41 and 42 and should be glad if you would, in consultation with the Registrar of Lands, Tulkarm, arrange for a survey to be made with a view to showing on the tracing the exact position, and the area, of the site required for the reservoir.

(Sgd)
For Director of Land Registrar.

Copy to:-Registrar of Lands, Tulkarm
File D/TUL/42.

مكتب مساعد حاكم اللواء بطولكرم

68

١٩٤٥/٢/١   الرقم — ١٥٦

P. 63

سعادة رئيس لجنة بلدية طولكرم المحترم

الموضوع = — رسوم الماء ·

الاشارة = — كتابكم رقم ٨١/٥ تاريخ ١٩٤٥/١/١٧ ·

اخبركم أن سعادة حاكم اللواء قد صادق على جدول الرسوم للمياه في طولكرم بموجب المادة السابعة عشر من نظام (مشروع مياه) طولكرم لسنة ١٩٤٤ واني ارفق طيه بنسخة من امر الموافقة للعمل بموجبه اعتبارا من اليوم الاول من شهر شباط سنة ١٩٤٥ ؛

وتفضلوا بقبول فائق الاحترام ·


مساعد حاكم اللواء

بطولكرم

64

GOVERNMENT OF PALESTINE.

In reply please quote
Ref. No. 515 - 4



COMMISSIONER'S
DISTRICT/OFFICES.
NABLUS.

26th January, 1946

Asst.Dist.Commissioner,
Tulkarm

P.64

Subject:- Water Rates - Municipal Commission of Tulkarm.
Reference: Your T/156/64 of 18-1-45.

Appended herewith is the required approval, in duplicate.

D.C. MacGillivray

DISTRICT COMMISSIONER
SAMARIA DISTRICT

GOVERNMENT OF PALESTINE

COMMISSIONER'S
DISTRICT OFFICES.
NABLUS.

26th January, 1946

Asst. Dist. Commissioner,
TULKARM

Subject:- Water Rates - Municipal Commission of Tulkarm.
Reference: Your T/1756/8a of 16-1-46.

Returned herewith is the required approval, in duplicate.

DISTRICT COMMISSIONER
NABLUS DISTRICT

MUNICIPAL CORPORATIONS ORDINANCE, 1934

TULKARM (WATER SUPPLY) BY-LAWS, 1944.

In accordance with By-law 17 of the Tulkarm(Water Supply) By-laws, 1944, I Donald Charles MacGillivray, District Commissioner, Samaria District, do hereby approve, with effect from 1st February, 1945, and until further notice the charges and fees contained in resolution No. 100 of the Municipal Commission of Tulkarm, dated the 16th January, 1945, and stated in the following schedule:-

SCHEDULE

	LP. mils
1. Water Rates	
a. Minimum rate	-.060
b. Per meter cube (up to one hundred meters cube)	-.030
c. Per meter cube (from one hundred and one meters cube to five hundred meters cube)	-.020
d. Per meter cube(above five hundred meters cube)	-.010
2. Meter Rents:	
Per month or part thereof	-.040
3. Amounts of Deposit	
Per subscriber (His Majesty's Forces, the Government of Palestine and official institutions excepted)	-.500
4. Connection Fees	
a. For ½ inch pipes	4.-
b. For ¾ inch pipes	4.500
c. For 1 inch pipes	6.-
d. For 2 inch pipes	8.-

D C MacGillivray
DISTRICT COMMISSIONER
SAMARIA DISTRICT

26th January, 1945.

NO. T/156/66. 60/

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

26th January, 1945.

District Engineer,
Nablus.

Subject:- Ownership of the Land on which the Tulkarm Municipal water Reservoir Stands.

Ref'nce:- Your 3/1/2 of 16.1.45. P 65

The file concerning this subject was destroyed. I shall be grateful if you will supply me with copies of all letters referred to by you in your above quoted letter.

With apologies for the trouble.

Assistant District Commissioner,
Tulkarm.

BF 72.

26/1

see p. 69

تكمل صحته ويسترد عافيته ،

وتفضلوا بقبول فائق الاحترام .

المخلص

[signature]

مساعد حاكم اللواء

بطولكرم

65

GOVERNMENT OF PALESTINE

----

138 JAN

PUBLIC WORKS DEPARTMENT
NABLUS.

No. 3/1/2. 16th January 1945.

Asst.Dist.Commissioner,
Tulkarm.

P 62

Subject:- Ownership of The Land on which the Tulkarm Municipal Water Reservoir Stands.

Ref'nce:- Your TUL.138/34 of 12.1.45.

I have no copy of the lease concluded between the Government and the Municipality of Tulkarm in respect of the above land, but I believe that arrangements for concluding such a lease were made between the District Officer Tulkarm and the Director of Land Registration as under his 16/8 of 28.9.35, the District Officer Tulkarm sent me a copy of a letter No.LD/73/8 of 12.9.44 from the Director of Land Registration in which he asked me to issue him with a plan showing the exact position and the area of the site required for the reservoir. This information was supplied under my 7/3 of 10.10.35.

[signature]
DISTRICT ENGINEER
NABLUS DISTRICT

58/HS.

P 66

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

18th January, 1945.

District Commissioner,
Samaria District.

Subject:- Water Rates - Municipal Commission, of Tulkarm.

At its meeting on the 16.1.45, the Municipal Commission of Tulkarm passed the following resolution, No.100:
"By virtue of the authority granted to it under Section 17 of the Tulkarm (Water Supply) By-Laws, 1944, the following water rates meter rent, amount of deposit, and connection fees have been fixed:

1. Water Rates.

	Mils
a) Minimum rate	60
b) Per cubic meter from one to one hundred units:	30
c) " " " " one hundred to five hundred.	20
d) Per cubic meter above five hundred	10

2. Meter Rent.
40 mils p.m. or part thereof.

see p. 67

3. Amount of Deposit.
500 mils per subscriber, His Majesty's Forces, the Government of Palestine and official institutions excepted.

4. Connection Fees.
For 1/2 inch pipes LP.4.000, 3/4 inch pipes LP.4.500, 1 inch pipes LP.6.000 and 2 inch pipes LP.8.000. The subscriber must in each Case submit all the papers necessary for the Connection and pay all expenses with the exception of the cost of the water meter which is supplied by the Municipal Commission.

Submitted for approval in time to enable it being put into force as from the 1.2.45."

Approval is recommended.

J.S.

Assistant District Commissioner,
Tulkarm.

18/1



156

17 JAN 1945

سعادة مساعد حاكم اللواء في طولكرم المحترم

الموضوع :- رسوم الماء

ان مجلس بلدية طولكرم استناداً الى الصلاحية المخولة له في المادة ١٧ من نظام (مشروع مياه) طولكرم لسنة ١٩٤٤ قد اتخذ قراراً رقم ١٠٠ بتاريخ ١٩٤٥/١/١٦ عين بموجبه رسم المياه واجرة العداد ومبلغ التأمين ورسم الوصل كما يأتي :-

	سعر المتر المكعب مل
اولاً : رسم المياه عن الاستهلاك الشهري لكل مشترك	
(أ) الحد الأدنى (٦٠) ستون ملاً .	
(ب) من متر مكعب واحد لغاية ١٠٠ متر مكعب	٢٠
(ج) ما زاد عن المئة متر مكعب لغاية ٥٠٠ متر مكعب	٢٠
(د) ما زاد عن ٥٠٠ متر مكعب	١٠

See P. 68

ثانياً : اجرة العداد (٤٠) اربعون ملاً في الشهر او جزء من الشهر

ثالثاً : مبلغ التأمين (٥٠٠) خمسمائة مل عن كل مشترك باستثناء المصالح التابعة لقوات جلالته وحكومة فلسطين والمؤسسات الرسمية فانها لا تدفع تأميناً .

رابعاً : رسم الوصل من الانابيب قياس ½ الانش اربعة جنيهات وقياس ¾ الانش اربعة جنيهات و ٥٠٠ مل وقياس الانش ستة جنيهات وقياس الانش ثمانية جنيهات . على ان يقدم المشترك في جميع الحالات كل الادوات اللازمة للربط ويدفع جميع النفقات باستثناء ثمن عداد الماء الذي تقدمه البلدية .

أكون ممتناً اذا تفضلتم بالمصادقة على مقررات المجلس هذه للعمل بموجبها اعتباراً من اول شهر شباط سنة ١٩٤٥ وفقاً لقرار المجلس البلدي .

وتفضلوا بقبول فائق الاحترام

[signature]
رئيس لجنة بلدية طولكرم

A.D.C.
Please see page 1113 P.G. 1371 Supplement No. 2 - Section (17) attached.
[initials]
17.1.

See P 64

NO.TUL.138/34. 62

COPY

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

12th January,1945.

District Engineer,
P.W.D.
Nablus

Subject:- Ownership of the Land on which the Tulkarm Municipal Water Reservoir stands.

The Municipal Commission of Tulkarm has been asked to to produce their authority for the use of this State Domain for the pupose ofthe erection of Water Reservoir.

In his reply the Chairman,Municipal Commission of Tulkarm states that the said Reservoir was erected by the Public Work Department in 1935,and that the authority to do so must have been granted to them but that the Municipality has no copy of such.

I should be grateful if you could supply me with a copy of such correspondence as may bear on the subject.

Sgd J. SOMERVILLE

8 61
/

Assistant District Commissioner,
Tulkarm.

Copy to; Chairman,
Municipal Commission,Tulkarm.
Ref,:his No 5/1 date 8.1.45.

BF 27.1

61

بلدية طولكرم

رقم – ١/٥

١٩٤٥/١/٨

P. 60

سعادة مساعد حاكم اللواء في طولكرم المحترم

الموضوع = – سوق الحيوانات بطولكرم

الاشارة = – كتابكم رقم ١٣٨ تاريخ ١٩٤٥/١/٥

بما أن دائرة الأشغال العامة هي التي قامت بانشاء مشروع الماء لبلدية طولكرم ومن ضمنه خزان الماء ، فان المخابرات لانشاء الخزان على أرض الحكومة جرت مع دائرة الأشغال رأسا • ولذلك فاني أكون ممنونا اذا اتصلتم بمهندس الأشغال بنابلس وحصلتم على صورة عن تلك المخابرة حتى يستطيع الاستناد عليها لطلب تسجيل القطعة باسم البلدية •

٢ – لقد أتم مساح دائرة الطابو تحضير الخرائط لأملاك بلدية طولكرم ودفعنا الرسوم التي ترتبت عليها • ولم يبق الا أن نسجل الأملاك في دائرة الطابو ونستلم شهادات التسجيل • وينتظر أن يتم ذلك قريبا • وتفضلوا بقبول فائق الاحترام ،

(امضاء) هاشم الجيوسي

رئيس لجنة بلدية طولكرم

P. 70

P. 62

مكتب مساعد حاكم اللواء بطولكرم

نسخة

الرقم — ١٣٨

٥/١/١٩٤٥

حضرة رئيس لجنة بلدية طولكرم المحترم

P. 31 file 138

الموضوع — سوق الحيوانات بطولكرم

الاشارة — كتابكم رقم ١/٥ تاريخ ٣٠/١٢/١٩٤٤

لا يزال الوضع كما ذكر في الفقرة الاولى من تحريري المرقم ٣٢/٤٨٤ والمؤرخ ٤/١٢/١٩٤٣ ارجو اعلامي بما تم في أمر محتويات الفقرة الثانية والثالثة .

وتفضلوا بقبول فائق الاحترام .

مساعد حاكم اللواء بطولكرم

See P.

No. TUL. 156/59. 59

Assistant District Commissioner's Office,
Tulkarm.

25th October, 1944.

District Engineer,
P.W.D.
Nablus.

Subject :- Water drawn by P.W.D. at Tulkarm.

The Chairman, Municipal Commission of Tulkarm, has addressed a letter to your representative at Tulkarm, with copy to this Office, protesting against the manner in which water for P.W.D. use is drawn.

2. As I happened to be passing when a truck load was being drawn, I feel it might help if I set down what actually takes place.

3. The water is drawn in a dozen or more asphalt barrels loaded in a truck. These are filled by using a bent piece of galvanized iron sheeting. As a result and in consequence of one or more of the barrels possibly being perforated, much water was being spilt and flowing down the road in no small quantity.

4. I suggest that more care could easily be taken.

Assistant District Commissioner,
Tulkarm.

Copy to : Chairman,
Municipal Commission of Tulkarm.

26/10

58

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
21 OCT 1944
TULKARM

دائرة بلدية طولكرم
No. ٥/٨٥ رقم
Date ١٩/١٠/١٩٤٤ تاريخ
Tulkarm Municipality

حضرة مراقب أشغال طولكرم المحترم

الموضوع :- الماء الذي تستهلكه دائرة الاشغال

يأخذ عمال دائرتكم الماء الذي تستهلك في عمليات تعبيد الطرق والانشاءات الأخرى من حنفية الماء المركبة في الساحة العامة لأجل تعبئة سيارة رش الشوارع . ولقد تسبب عن ذلك وقوع خلل في الحنفية أكثر من مرة ونتج عنه تشويش في تعيين كمية الماء المستهلك ومقدار الحساب الذي تستحقه البلدية . وعلى الرغم من هذه المزعجات فاني لم أقدم على منع الماء عن دائرتكم خشية عرقلة أعمالكم . ولكن الأمر تطور فأصبحت تلك الحنفية منبعاً للأخطار الصحية إذ يسيل الماء منها ويتجمع بشكل مستنقع ثم يفيض عن جوانب الشارع الرئيسي في البلدة فيشوه منظره ويعرقل حركة السير . لذلك فاني اقترح ان تنصبوا فرعاً من من الانابيب بجوار دائرتكم وتضعوا عليه حنفية خاصة يستطيع عمال دائرتكم اخذ ما يلزمهم من الماء منها . وبهذه الطريقة نستريح من مشقة المحاسبة عن الماء المستهلك لأنه يدخل في حساب دوائر الحكومة الذي يسجله عداد الماء العمومي ، ونأمن سلامة حنفية رش الشوارع ، لانها اذا بقيت على حالتها الحاضرة ستضطر للاغلاق ورفعها بالمرة حرصاً على الصحة العامة ونظافة الشوارع ومنظرها .

وتفضلوا بقبول فائق الاحترام

رئيس لجنة بلدية طولكرم

نسخة الى :
سعادة مساعد حاكم اللواء المحترم

p. 59

18 OCT 1944

515

COMMISSIONER'S

16th October, 1944.

Chief Secretary.

Submitted herewith, for your approval and publication in the Gazette, are three copies in English and three copies in Arabic of by-laws made by the Municipal Commission of Tulkarm for the control of the supply of water.

2. These by-laws follow verbatim (except for the substitution of the words "Municipal Commission of Tulkarm" for "Municipal Commission of Jenin") the Jenin (Water Supply) By-laws, 1944 which were published on page 705 of Supplement No.2 to the Gazette No.1348 of 27th July, 1944.

DISTRICT COMMISSIONER,
SAMARIA DISTRICT.

Copy to:- Assistant District Commissioner, Tulkarm (Ref. his TUL.156/56 of 4/10/44).

IA.

No.TUL.156/56. 56

Assistant District Commissioner's Office,
Tulkarm.

4th October, 1944.

District Commissioner,
Samaria District.

Subject :- Water Supply By-Laws - Municipal Council of Tulkarm.

Ref'nce :- Your No. 1402 dated the 29.8.44.

I submit herewith, in quadruplicate, in both English and Arabic the proposed Water by-laws and as submitted by the Municipal Commission of Tulkarm.

2. These are identical with those of the Municipal Commission of Jenin.

Assistant District Commissioner,
Tulkarm.

Copy to: File No. 1290

P 8 File 1290

1/10
K.

P 57

MUNICIPAL CORPORATIONS ORDINANCE, 1934.

BY-LAWS MADE BY THE MUNICIPAL COMMISSION OF TULKARM UNDER SECTION 99.

[illegible] vested in them by section 99 of the Municipal Corporations Ordinance, 1934, the Municipal Commission of Tulkarm have made the following by-laws :- No.1 of 1934.

1. These by-laws may be cited as the Tulkarm(Water Supply)By-laws, 1934. Citation.

2. In these by-laws, unless the context otherwise requires - Interpretation.

"Area", "Council" and "Corporation" shall mean the Municipal Area, the Municipal Council and the Municipal Corporation of Tulkarm, respectively.

"Connection" shall mean the pipe which extends from the water main of the Corporation to the service and shall include the meter, all stopcocks, valves, surface boxes and any water meter chamber used or to be used for or in connection with the supply of water by the Corporation.

"Connection fee" shall mean any charge prescribed by the Council, with the approval of the District Commissioner, for the installation of a connection.

"Deposit" shall mean an amount prescribed by the Council with the approval of the District Commissioner, and payable in advance by the subcriber as a security for the payment of his water rate and/or meter rent.

"Domestic use" shall mean human consumption, household washing, flushing and cleaning and shall not include a supply of water for cattle or for horses, or for washing vehicles or for steam engines or for railway purposes or for warming or ventilating purposes in public buildings or for working any machine or apparatus or for any trade, manufacture or business whatsoever, or for watering gardens by means of any tap, tube, pipe or other like apparatus, or for fountain or for public baths or wash houses, or for any ornamental purposes whatsoever.

"Meter" shall mean the appliance which is installed for the purpose of measuring and ascertaining the amount of water drawn from the water works in respect of any premises.

"Meter rent" shall mean the charge prescribed by the Council with the approval of the District Commissioner, for the use of a meter being the property of the Corporation.

"Owner" shall mean the person who is in receipt of rents or profits of any premises in respect of which the word is used, whether on his own account or as agent, trustee or guardian for any other person, or who would so receive the same if the premises were leased, whether or not he is in possession, or is the reputed or registered owner, and shall include any co-owner, and shall also include the mutawall of any waqf.

"Premises" shall mean buildings and lands of any tenure whether open or enclosed, whether built upon or not, whether public or private and whether maintained or not under statutory authority.

"Public fountain " shall mean any fountain, standpipe, valve, tap or appliance used or intended to be used for or in connection with the supply of water for public use and erected by the Corporation and which is the property of the Corporation.

/2.

"Service" shall mean all pipes, valves, cisterns, cocks, fittings and other appliances starting at the meter or where there is no meter, at the termination of the Corporation's connection situated within the boundaries of premises through which water flows or is intended to flow from the water works and being the property of the owner of such premises.

"Subscriber" shall mean any person registered by the Council as a subscriber to take water in conformity with these by-laws.

"Water rate" shall mean the charge prescribed by the Council with the approval of the District Commissioner, and payable by the subscriber for water supplied.

2. "Water works" shall

channels, wells, cisterns, tunnels, filterbeds, mains, pipes, fountains, valves, pumps, engines, apparatus and all other

[illegible] of the Corporation and are the property of the Corporation or which shall hereafter be used or constructed as such.

Administration of water supply & water works.

3. The Council shall have the custody and administration of the water works and of the water therein and the management of the water supply and its distribution.

Power of entry.

4. Any Officer of the Corporation, duly authorised by the Council may, at any time between eight o'clock in the morning and six o'clock in the evening, and upon giving reasonable notice, enter upon any premises for the purpose of examining, repairing or removing any water pipe, fitting or other apparatus. Any person who hinders or obstructs such an officer in the execution of such duty shall be liable to the penalties provided in these by-laws.

Laying of pipes

5. The Council may carry any water pipe through, across, or under any public thoroughfare or any place laid out or intended as a public thoroughfare.

Construction of public fountains.

6. The Council may construct public fountains in any public thoroughfare or public place.

Suspension of water supply.

7. It shall be lawful for the Council in any emergency, to disconnect, withhold or suspend, stop, turn off, or divert the supply of water through or by means of any service or public fountain either wholly or in part whenever the Council shall think necessary or proper and without prejudice to any sums due or to become due under these by-laws.

Application for supply.

8. (1) Any person desiring to be supplied with water shall first apply in writing to the Council on the form prescribed in the schedule hereto.

(2) The Council shall thereupon specify the conditions including the amount of the deposit and water rate, under which the application will be granted and may refuse to supply water until all such conditions have been executed and the deposit paid.

(3) Upon receipt by the Council of written acceptance by the applicant of the said conditions the applicant shall be registered by the Council as a subscriber.

/3.

"Service" shall mean all pipes, valves, cisterns, cocks, fittings and other appliances starting at the meter or where there is no meter, at the termination of the Corporation's connection situated within the boundaries of premises through which water flows or is intended to flow from the water works and being the property of the owner of such premises.

"Subscriber" shall mean any person registered by the Council as a subscriber to take water in conformity with these by-laws.

"Water rate" shall mean the charge prescribed by the Council with the approval of the District Commissioner, and payable by the subscriber for water supplied.

"Water works" shall mean all reservoirs, tanks, ~~channels, wells, cisterns, apparatus and all other~~ structures and appliances used or constructed for the storage, conveyance, supply, measurement or regulation of water which are used or have been constructed by or on behalf of the Corporation and are the property of the Corporation or which shall hereafter be used or constructed as such.

3. The Council shall have the custody and administration of the water works and of the water therein and the management of the water supply and its distribution. — Administration of water supply&water works.

4. Any Officer of the Corporation, duly authorised by the Council may, at any time between eight o'clock in the morning and six o'clock in the evening, and upon giving reasonable notice, enter upon any premises for the purpose of examining, repairing or removing any water pipe, fitting or other apparatus. Any person who hinders or obstructs such an officer in the execution of such duty shall be liable to the penalties provided in these by-laws. — Power of entry.

5. The Council may carry any water pipe through, across, or under any public thoroughfare or any place laid out or intended as a public thoroughfare. — Laying of pipes.

6. The Council may construct public fountains in any public thoroughfare or public place. — Construction of public fountains.

7. It shall be lawful for the Council in any emergency, to disconnect, withhold or suspend, stop, turn off, or divert the supply of water through or by means of any service or public fountain either wholly or in part whenever the Council shall think necessary or proper and without prejudice to any sums due or to become due under these by-laws. — Suspension of water supply.

8.(1) Any person desiring to be supplied with water shall first apply in writing to the Council on the form prescribed in the schedule hereto. — Application for supply.

(2) The Council shall thereupon specify the conditions including the amount of the deposit and water rate, under which the application will be granted and may refuse to supply water until all such conditions have been executed and the deposit paid.

(3) Upon receipt by the Council of written acceptance by the applicant of the said conditions the applicant shall be registered by the Council as a subscriber.

9. The subscriber shall sign a contract with the Council embodying the conditions prescribed by the Council for the supply of water in accordance with by-law 8(2) of these by-laws and shall pay all fees and expenses in connection with such contract. Contract.

10. Upon the registration of a subscriber by the Council the service shall be provided and maintained in sound condition by and at the expense of the owner of the premises in accordance with the prescribed conditions and under the supervision of an Officer of the Corporation authorised in that behalf by the Council. Installation of service.

11. The connection to the main shall be made by the Council and a connection fee and any other expenses involved shall be paid in advance by the owner of the premises. No person shall open, close or in any way interfere with any pipes, valves or appliances of the connection under any pretext whatever save with the authority of the Council. Connection.

12. The subscriber shall, as soon as his name has been registered by the Council, pay to the treasury of the Corporation the prescribed deposit. The Council shall have the right to recover from the deposit any fees or rates or charges that may become due from the subscriber under these by-laws. Deposit.

13. The size and kind of pipes necessary for the service and connection and the proper point of introduction of water to the premises shall be determined by the Council. Determination of kind and size of pipes.

14.-(1) A meter or meters may be installed at any time by the Council on any premises supplied with water. Installation of meters.

(2) Where a meter has been installed the subscriber shall be liable to pay meter rent for the use of the meter.

(3) Every meter shall be the property of the Corporation and shall be kept in repair by the Council.

15. Where a meter has been installed by the Council it shall be kept in a concrete chamber the door of which shall be provided with two keys, one of which shall be kept by the subscriber and the other by an officer appointed by the Council for the inspection of water. The subscriber shall not under any circumstances be permitted to touch or remove the meter: this may only be done by an authorised officer appointed by the Council. Safeguarding of meter.

16. Any interference with the meter shall render the subscriber liable to disconnection of the supply. Interference with meter.

17. The water rate, the meter rent, the amount of the deposit, the connection fee and other fees or charges shall be as determined by resolution of the Council with the approval of the District Commissioner and shall be subject to alteration from time to time in the same manner. Charges and fees.

18. -(1) Where a meter has been installed the quantity of water charged to the subscriber shall be that recorded by the meter. Calculation of water rates.

(2) Should the Council be satisfied that the meter is defective or fails or failed to indicate the correct quantity of water consumed, or is broken or damaged, the water charge for the period during which the meter was out of order shall be based on the quantity drawn by the subscriber during a period of similar length during the same season of the preceding year.

[illegible] was not recorded by meter during the [illegible] of the preceding year, the quantity [illegible] shall be assessed at the discretion of the Council, whose decision shall be final.

(3) Where no meter has been installed a flat rate shall be charged.

19.-(1) Where a meter has not been installed the subscriber shall pay half yearly in advance the amount due for the supply of water. The two instalments shall become due in April and in September. Where water is supplied by meter, the subscriber shall pay monthly in arrears the water rate and the meter rent due.

Time of payment.

(2) The amount payable for the supply of water for use in the construction of a building or in other building operations shall, unless such water be supplied by meter, be paid to the Corporation in full upon the issue of the relative building permit or licence authorising such construction or operations.

20. Any subscriber who fails to settle his account within eight days from the date of its service upon him, or who fails, after due warning in writing by the Mayor, to prevent any waste or abuse of water or any nuisance, shall be liable to have the supply of water to his premises disconnected and shall not be entitled to have the supply reconnected until he shall have paid the outstanding sums due or rectified the defect, he shall in addition be liable to pay such fees as may be prescribed by the Council with the approval of the District Commissioner, for re-opening the supply and the costs of re-connection. Any person appointed by the Council shall have the right to enter upon such premises without giving notice at any time between eight o'clock in the morning and six o'clock in the evening for the purpose of stopping, cutting off or diverting the supply of water.

Suspension of water supply for non-payment of fees or for waste or bad use of water.

21. The Council may exempt from water charges any schools, mosques and churches. The Council may also exempt from water charges any charitable institutions such as hospices, hospitals and takiyes provided they are used exclusively for the gratuitous accommodation of pilgrims or patients.

Exemption from charges.

22. No subscriber or occupier of a subscriber's premises or any other person shall instal any service or alter, extend or interfere with a service laid or fixed by or with the authority of the Council before having first obtained the written permission of the Council so to do.

No installation or alteration of service without permission.

23.-(1) No person shall permit an ashpit, cesspit, percolating pit or other unclean area or receptacle or thing to be near any service.

Cesspit, etc. not to be near any service.

(2) The owner shall be responsible for the removal, repair or alteration of such ashpit, cesspit, percolating pit or other unclean area, receptacle or thing whatsoever, when required by a written notice by the Mayor so to do. If the owner fails to remove, repair or alter the things required by the said notice within the time and in the manner indicated therein, the Council shall be entitled to effect the removal, repairs or alteration and to recover the expense thereof from the owner.

Waste of water prohibited.

24. No subscriber or occupier of a subscriber's premises to which water is laid on shall permit any waste of the water by reason of any defective fitting or by leaving any fitting or tap open. Any defect in the fittings shall be reported immediately to the Council by the subscriber and the owner of the premises shall cause the requisite measures to rectify the defect to be taken immediately.

Authorised blacksmiths.

25.-(1) No person shall execute or be permitted to execute any installation, alteration or repair of any service unless he is the holder of a blacksmith's licence granted to him by the Council and authorising him to execute any such work.

The holder of such a licence shall produce the same on demand at any time to any person authorised by the Council or to the owner of any premises.

(2) If the Council is of opinion at any time that a person holding a licence to practice as a blacksmith under these by-laws is committing or failing to execute work to the Council's satisfaction, the Council may cancel such licence and such blacksmith shall no longer be per-mitted to practise as a blacksmith under these by-laws.

Use of water.

26. No subscriber, or occupier of a subscriber's premises or any other person, shall use or permit to be used the water supplied by means of a service for any purposes except as prescribed in the contract for the supply of water to such service.

Removal of water prohibited.

27. No subscriber, or occupier of a subscriber's premises to which water is laid on, shall without the written agreement of the Council permit any person to remove from such premises water for any use whatever.

Pollution of water supply prohibited.

28. No person shall :-

(a) bathe or wash in any part of the water works;

(b) throw or cause or permit to enter into any water works, any animal or any clothes, materials or thing;

(c) wrongfully open or close any lock, cock, valve sluice, tap, or man-hole belonging to the water works;

(d) do any thing that will cause the pollution of water or the obstruction of its flow;

(e) construct, dig, erect or instal within the area any reservoir of water, tank, well, cistern, tunnel, filterbed, main or additional pipe, fountain, valve, pump, engine, or any other structure or appliance for the purpose of storage, conveyance, supply, measurement or regulation of water before having first secured a written permission from the Council in respect thereof.

Service of documents.

29. Any statement of accounts, demand note, notice warning or any similar document required to be served on a subscriber for the purposes of these by-laws, shall be deemed to be sufficiently served on him if it is transmitted to him by ordinary post or delivered at his business premises or at his residence, and if it is transmitted by post as aforesaid service thereof shall be deemed to have been effected on the day following the day of its posting to the subscriber. Service effected by delivery at the subscriber's business premises or at his residence shall be considered to have been duly effected if the document is handed over by an officer of the Corporation to such subscriber or to any person working in the subscriber's

business premises or to any of the adult members of the subscriber's family residing with him in his residence, or if it is affixed to the door of such business premises or residence.

30. The owner or occupier of any premises to which water is supplied by the Corporation at the date of the coming into force of these by-laws shall, within a period of one month from that date, submit an application to the Council in accordance with by-law 8 of these by-laws. If the owner or occupier fails to submit such application to the Council within the said period, the Council shall be entitled to cut off the water supply to such premises as aforesaid. Transitory provision.

31. Any person contravening any provision of these by-laws shall be liable to a fine not exceeding twenty pounds for any one offence and in the case of a continuing offence to an additional fine not exceeding one pound for every day during which the offence is continued after service of a written notice by the Mayor of such contravention or, if there is no such written notice, after conviction. Penalties.

32. These by-laws shall come into force on the date of their publication in the Gazette. Commencement.

SCHEDULE.

FORM OF APPLICATION FOR THE SUPPLY OF WATER BY THE TULKARM MUNICIPAL CORPORATION (BY-LAW 8 OF THE JENIN (WATER SUPPLY) BY-LAWS, 1944).

I, ...

hereby make application for the supply of water:-

(a) for domestic use at the premises at..................................

....

....

(1) which are occupied by...

....(2)

(b) for the water of a garden of......................square metres

(c) for a private garage

(d) for watering of the following animals...............................

(e) for the following commercial or business premises...................

(f) for building purposes.

....
Signature of applicant.

Date......................

(1) Insert full description of premises. If applicant is not the owner of the premises state owner's name.

(2) Give full particulars of the number and [illegible] of [illegible] occupying the premises.

Hashem Jayousi

Chairman, Tulkarm Municipal Commission.

Confirmed.

By His Excellency's Command.

Chief Secretary.

قانـــون البلديات لسـنة ١٩٣٤

رقم ١ لسنة ١٩٣٤ ان لجنة بلدية طـولكـــرم ، استنادا الى الصلاحية المخولة لها في المادة الثلاثة والتسعين من قانون البلديات لسنة ١٩٣٤ ، قد اصدرت النظام التالي :-

اسم النظام — المادة ١ يطلق على هذا النظام اسم نظام (مشروع مياه) طولكـــرم لسنة ١٩٤٤

تفسير اصطلاحات — المادة ٢ يكون للالفاظ والعبارات التالية الواردة في هذا النظام المعاني المخصصة لها ادناه ، الا اذا دلت القرينة على غير ذلك :-

تعني عبارة " منطقة البلدية " منطقة بلدية طـولكـرم و " مجلس البلدية " مجلس بلدية طـولكـــرم و " هيئة البلدية " هيئة بلدية طـولكـــرم

وتنصرف لفظة " الوصلة " الى الانبوب الممتد من انابيب المياه الرئيسية العائدة لهيئة البلدية حتى دورة المياه ، وتشمل العداد وجميع المحابس والصمامات والصناديق السطحية وعبوة عداد المياه ، المستعملة او التي يراد استعمالها في توريد المياه من قبل هيئة البلدية او فيما يتعلق بذلك

وتفيد عبارة " رسم الوصل " الرسم الذى تقرره اللجنة ، بموافقة حاكم اللـــواء ، من اجل تركيب الوصلة

ويراد بلفظة " التامـين " المبلغ الذى يقرره المجلس ، بموافقة حاكم اللواء ، ويدفعه المشترك مقدما ، لضمان دفع رسم المياه و / او اجرة ~~العمال~~ العداد

وتعني عبارة " الماء المخصص للشؤون المنزلية " الماء الذى يستهلكه الانسان او يستعمل لغسل ادوات البيت والشطف والتنظيف ، ولكنها لا تشمل المياه التي تستعمل للابقار او الخيول اوغسل المركبات او المحركات او الآلات البخارية او السكك الحديدية ، او لتدفئة الابنية العمومية او تهوائها ، او لتشغيل الماكنات والآلات ، او لاية حرفة او صناعة او متجر مهما كان نوعه ، او لسقي الحدائق بواسطة الحنفيات ، او الخراطيم ، او الانابيب ، او ما شابه ذلك من الاجهزة ، او للنوافير (الشاذروانات) او الحمامات العمومية ، او اماكن الغسيل او لاى غرض من اغراض الزينة مهما كانت

وتنصرف لفظة " العداد " الى الجهاز الذى يركب في العقار لقياس وضبط كمية المياه التي تسحب من انشاآت مشروع المياه الى ذلك العقار

وتفيد عبارة " اجرة العداد " الاجـرة التي يقررها المجلس ، بموافقة حاكم اللواء ، لاستعمال العداد الذى يخص البلدية

وتنصرف لفظة " المالك " ، فيما يتعلق باى عقار ، الى الشخص الذى يتقاضى بدل ايجار او ريع ذلك العقار ، سواء اكان ذلك لحسابه الخاص ام بصفته وكيلا عـن شخص آخر ، او قيما او وصيا عليه ، او الى الشخص الذى يتقاضى بدل الايجار او الريع المذكور فيما لو اوجر العقار ، سواء اكان ذلك الشخص متصرفا بالعقار او مالكه المعروف ام لم يكن ، وسواء اكان العقار مسجلا باسمه ام لم يكن ، وتشمل ايضا الشريك ومتولي الوقف

وتعني لفظة " العقار " الابنية والاراضي مهما كان صنفها ، مسورة كانت ام غير مسورة مبنيا عليها ام خالية ، عمومية ام خصوصية ، وسواء اكانت محتفظا بها ام تدار بموجب سلطة قانونية ام لم تكن

وتعني عبارة " الحنفية العمومية " حنفية او حنفية قائمة على انبوب او صمام او صنبور او

جهاز ما تنشؤه او تركبه هيئة البلدية وتستعمل او تنوي استعماله لتوريد المياه للجمهور او فيما يتصل بذلك ويكون ملك البلدية

وتنصرف عبارة " دورة المياه " الى جميع ما يخص مالك العقار من انابيب وصمامات وآبار (صهاريج) وحنفيات ووصلات وغير ذلك من الادوات ، ابتداء من العداد (ان كان ثمة عداد) ، وان لم يكن هناك عداد ، فابتداء من نهاية وصلة البلدية الكائنة ضمن حدود العقار المسحوبة اليه المياه او الذي يراد سحب المياه اليه من انشاآت مشروع المياه

وتفيد عبارة " المشترك " اى شخص مسجل لدى المجلس كمشترك لأخذ المياه وفقا لأحكام هذا النظام

وتعني عبارة " رسم المياه " الرسم الذي يقرره المجلس ، بموافقة حاكم اللواء ، ويستوفى من المشترك مقابل المياه التي تورد اليه

وتنصرف عبارة " انشاآت مشروع المياه " الى جميع الخزانات ، والاحواض والاقنية والآبار ، والصهاريج ، والانفاق ، والمصافي ، والانابيب الرئيسية ، والانابيب الفرعية ، والحنفيات والصمامات ، والمضخات ، والمحركات ، والاجهزة ، وسائر الانشاآت والادوات الاخرى المستعملة او المنشأة لخزن المياه ، او نقلها او توريدها ، او قياسها ، او تنظيمها ، والتي استعملتها او انشأتها البلدية ، او انشئت بالنيابة عنها وهي ملك لها ، ، والتي ستستعملها او تنشئها فيما بعد من اجل الغايات الآنفة الذكر

ادارة انشاء مشروع المياه وتوريد المياه

المادة ٣ يتولى المجلس العناية بانشاآت مشروع المياه والمياه الموجودة فيها وادامتها وادارتها والاشراف على توريد وتوزيع المياه

صلاحية الدخول الى العقار

المادة ٤ يجوز لأي موظف من موظفي البلدية ، مفوض حسب الاصول من المجلس ، أن يدخل الى اى عقار لفحص اى انبوب او وصلة او جهاز آخر من اجهزة المياه ، او لاصلاحه او لازالته ، وذلك في اى وقت بين الساعة الثامنة صباحا والسادسة مساء ، وبعد اعطاء اشعار معقول بذلك ، وكل شخص يعترض او يعيق الموظف المذكور عن القيام بهذا الواجب يعرض نفسه للعقوبات المنصوص عليها في هذا النظام

مد الانابيب

المادة ٥ يجوز للمجلس ان يمد اى انبوب من انابيب المياه في اى طريق عام او مكان مخطط كطريق عام او يراد استعماله كذلك ، او ان يمده من الجانب الواحد منه الى الآخر او تحته

الحنفيات العمومية

المادة ٦ يحق للمجلس أن ينشيء حنفيات عمومية في اى طريق عام او مكان عام

قطع المياه

المادة ٧ يحق للمجلس ، في اية حالة طارئة ، أن يقطع المياه الموردة من قبله بواسطة أى جهاز من اجهزة المياه او اية حنفية عمومية ، او ان يمتنع عن توريد المياه أو أن يوقفها او يغير مجراها ، كليا أو جزئيا ، كلما رأى المجلس ذلك ضروريا او ملائما ، دون أن يجحف ذلك في المبالغ المستحقة له او التي تستحق له بمقتضى هذا النظام

تقديم الطلبات لتوريد المياه

المادة ٨ – " ١ " يترتب على كل شخص يرغب في توريد المياه اليه ، أن يقدم بادىء ذى بدء طلبا كتابيا بذلك الى المجلس على النموذج المعين في ذيل هذا النظام

" ٢ " يعين المجلس عندئذ الشروط التي يمنح الطلب بموجبها بما في

ذلك بمقدار التأمين ورسم المياه ، ويجوز له أن يرفض تزويد المياه الى أن يتم تنفيذ الشروط ودفع التأمين

" ٣ " حينما يستلم المجلس موافقة الطالب خطيا على الشروط المذكورة يسجل الطالب كمشترك

العقود المادة ٩ يترتب على المشترك أن يعقد عقدا مع المجلس ، يشتمل على الشروط التي يفرضها المجلس لتزويد المياه اليه وفقا للفقرة " ٢ " من المادة الثامنة من هذا النظام ، وأن يدفع جميع الرسوم والمصاريف المتعلقة بذلك العقد

وصل اجهزة المياه المادة ١٠ حينما يسجل المجلس مشتركا ، يتولى المالك على نفقته اقامة دورة المياه وتركيبها وصيانتها في حالة جيدة ، وفقا للشروط المعينة وباشراف موظف من موظفي البلدية مفوض بذلك الشأن من المجلس

ربط اجهزة المياه المادة ١١ يقوم المجلس بوصل دورة المياه بالمواسير الرئيسية ، ويدفع المالك رسم الوصل وجميع المصاريف الناشئة عن عملية الوصل ، ولا يجوز لأى شخص أن يفتح او يقفل الانبيب او صمامات او ادوات الوصل ، او أن يعبث بها على اى وجه آخر ، مهما كان السبب الذى يتذرع به الا بتفويض من المجلس

التأمين المادة ١٢ يترتب على المشترك ، حالما يسجل اسمه لدى المجلس ، أن يدفع التأمين المقرر الى امين صندوق البلدية ، ويحق للمجلس أن يستوفي من التأمين المذكور اية رسوم اوعوائد او تكاليف قد تستحق على المشترك بمقتضى هذا النظام

تعيين حجم ونوع الأنابيب المادة ١٣ يقرر المجلس حجم ونوع الأنابيب التي ستستعمل في دورة المياه والوصلة ، والمكان الملائم لادخال المياه منه الى العقار

تركيب العداد المادة ١٤ — " ١ " يجوز للمجلس ، في اى وقت من الأوقات ان يركب عدادا او اكثر في اى عقار تورد اليه المياه

" ٢ " في الأحوال التي يركب فيها عداد ، يلزم المشترك بدفع اجرة العداد مقابل استعماله

" ٣ " يكون العداد ملكا للبلدية ، ويتولى المجلس حفظه في حالة جيدة

صيانة العداد المادة ١٥ اذا ركب المجلس عدادا يقتضي أن يحفظ ذلك العداد في خزانة من الاسمنت وأن يكون لباب الخزانة مفتاحان يحتفظ المشترك بأحدهما ويبقى الثاني لدى الموظف المعين من قبل المجلس لتفتيش المياه ، ولا يحق للمشترك بأية حالة من الحالات أن يعبث بالعداد اوأن ينقله من مكانه او يزيله ، ولا يجوز اجراء ذلك الا من قبل موظف مفوض معين من المجلس

العبث بالعداد ~~ولا يجوز~~ المادة ١٦ ان اى عبث يلحق ~~الخ~~ بعداد المياه يعرض المشترك لقطع المياه عنه

الرسوم الخ .. المادة ١٧ يعين المجلس في قرار يتخذه يقترن بموافقة حاكم اللواء رسم المياه ، واجرة العداد ومبلغ التأمين ورسم الوصل ، وغير ذلك من الرسوم والمصاريف . ويجوز تغيير هذه الرسوم والاجور والمبالغ من وقت الى آخر بالصورة الآنفة الذكر

حساب رسم المياه المادة ١٨ — " ١ " حيثما ركب عداد تكون كمية المياه التي يطالب المشترك بدفع ثمنها هي الكمية التي يسجلها العداد

" ٢ " اذا اقتنع المجلس بأن في عداد المياه خللا ، أو بانه لم يسجل او قد لا يسجل الكمية الصحيحة للمياه المستهلكة ، او بأنه مكسور او معطوب ، تقدر رسوم

المياه عن المدة التي كان العداد فيها معطوبا على اساس الكمية التي استهلكها المشترك خلال مدة تساوى تلك المدة من الفصل ذاته في السنة الماضية . واذا كانت كمية الماء التي وردت خلال الفصل ذاته من السنة الماضية لم تحسب بواسطة عداد ، فتحسب كمية المياه الموردة وفقا لما يراه المجلس ، ويكون قراره بهذا الشأن نهائيا مبرما

" ٣ " في الأحوال التي لم يركب فيها عداد ، تستوفى فئة مقطوعة

موعد الدفع — المادة ١٩ ـ " ١ " اذا لم يركب عداد في اى عقار ، يترتب على المشترك ان يدفع مقدما رسم المياه المستحق عن نصف السنة التالية ، ويستحق دفع القسطين نصف السنويين في نيسان وايلول . واذا كانت المياه الموردة الى المشترك تحسب بواسطة العداد ، فيقتضي عليه أن يدفع في آخر كل شهر رسم المياه التي استهلكها في ذلك الشهر مع اجرة العداد

" ٢ " ان المبلغ الواجب دفعه عن المياه التي تستعمل في انشاء بناية او في اية عملية من عمليات البناء ، يدفع بكامله الى البلدية حين اصدار رخصة البناء المتعلقة بذلك الانشاء او بعملية البناء المذكورة ، الا اذا كانت المياه المبحوث عنها تورد بواسطة عداد

قطع المياه للتخلف عن الدفع او تبذير المياه او العبث بها — المادة ٢٠ اذا حدث ان تخلف مشترك عن تسجيل حسابه خلال ثمانية ايام من تاريخ تبلغه بيانا بالحساب ، او تخلف عن منع تبذير المياه او سوء استعمالها او عن ازالة اية مكرهة ناشئة عنها ، بعد تبليغه اخطارا كتابيا بذلك من رئيس البلدية ، يتعرض ذلك المشترك بقطع المياه عن عقاره ، ولا يحق له ان يعاد وصل المياه بعقاره الا بعد ان يسدد كافة المبالغ المستحقة عليه او اصلاح الخلل المشار اليه . ويقتضي عليه بالاضافة الى ذلك ، ان يدفع الرسم الذى يقرره المجلس بموافقة حاكم اللواء ، مقابل اعادة توريد المياه اليه ، مع نفقات اعادة الوصل . ويحق لأى شخص معين من قبل المجلس ان يدخل الى اى عقار كهذا في اى وقت من الأوقات بين الساعة الثامنة صباحا والسادسة مساء ، دون اعطاء اشعار ، من اجل توقيف توريد المياه ، او قطعها او تحويلها

الاعفاء من الرسوم — المادة ٢١ يجوز للمجلس ان يعفي من رسم المياه المدارس والمساجد ، والكنائس ، كما يجوز له ايضا أن يعفي من رسم المياه مؤسسات البر والاحسان ، كالمثابات (الهوسبيس) والمستشفيات ، والتكايا ، بشرط أن تكون مستعملة كلها لاقامة الحجاج او قبول المرضى مجانا

حظر التركيب او التغيير دون اذن — المادة ٢٢ لا يجوز لأى مشترك ، او لأى شخص يسكن في عقار المشترك او لأى شخص آخر ان يركب دورة المياه ، او أن يغير او يوسع او يعبث باية دورة مياه وضعت او ركبت من قبل المجلس او بتصريح منه الا بعد الحصول على اذن خطي بذلك من المجلس

حظر مجاورة حفر المراحيض للأنابيب — المادة ٢٣ ـ " ١ " لا يجوز لأى شخص ان يسمح بوجود حفرة للرماد ، او للقاذورات او وجود مرحاض او حفرة راشحة او مكان او وعاء او شيء غير نظيف بالقرب من دورة المياه

"٢" يكون المالك مسؤولا عن ازالة او اصلاح او تغيير اية حفرة رماد او حفرة قاذورات او حفرة مرحاض او حفرة راشحة او مكان او وعاء او شيء غير نظيف اذا كلفه رئيس البلدية بذلك باشعار كتابي ، فاذا تخلف المالك عن اجراء ما كلف به في الاشعار من نقل او اصلاح او تغيير ضمن المدة المعينة بالاشعار وعلى الوجه المقرر

يقع فيه ، يحق للمجلس أن يقوم بعملية الازالة او الاصلاح او التغيير وان يحمل النفقات من المالك

حظر تبذير المياه — المادة ٢٤ لا يجوز لأي مشترك او لشخص يسكن في عقار مشترك تورد اليه المياه ، ان يسمح بتبذير المياه بسبب وجود خلل في اية وصلة ، او ترك اية وصلة او حنفية مفتوحة ، ويترتب على المشترك ان يبلغ المجلس فورا عن اي خلل كهذا ، كما يترتب على مالك العقار ان يتخذ التدابير الضرورية في الحال لاصلاح ذلك الخلل

السنكريون المفوضون — المادة ٢٥ "١" لا يجوز لأي شخص ان يركب جهاز مياه او يغيره ، او يصلحه ، كما لا يجوز السماح لأي شخص القيام بما سبق ذكره ، الا اذا كان ذلك الشخص يحمل شهادة سنكرى صادرة من المجلس يصرح له بالقيام بالعمليات المذكورة ويقتضي على حامل رخصة السنكرة ان يبرزها لدى الطلب الى الشخص المفوض بذلك من المجلس او الى مالك العقار

"٢" اذا كان من رأي المجلس ، في اي وقت من الأوقات ، ان شخصا يحمل رخصة لتعاطي مهنة السنكرة بمقتضى هذا النظام قد تخلف او قصر في القيام بالشغل على وجه يرضى به المجلس ، يجوز له ان يلغي رخصته ، ويحجزها وحينئذ لا يسمح لذلك السنكرى بتعاطي مهنة السنكرة بمقتضى احكام هذا النظام

استعمال المياه — المادة ٢٦ لا يجوز لأي مشترك أو لأي شخص يسكن في عقار مشترك ، او لأي شخص آخر ، ان يستعمل المياه الموردة بواسطة دورة المياه ، او ان يسمح باستعمالها لأية غاية خلاف الغايات المذكورة في العقد المعقود لتوريد المياه الى تلك الدورة

حظر نقل المياه — المادة ٢٧ لا يجوز لأي مشترك او لأي شخص يسكن في عقار مشترك مدت فيه المياه ، ان يسمح لأي شخص بنقل المياه من عقاره لاستعمالها لأية غاية من الغايات مهما كانت ، الا بعد الحصول على موافقة خطية بذلك من المجلس

حظر تلويث المياه — المادة ٢٨ لا يجوز لأي شخص ، :-

(أ) ان يستحم او يغسل في اي قسم من انشاآت مشروع المياه

(ب) ان يطرح او يتسبب او يسمح بطرح او دخول اي حيوان او ثياب او مواد او اشياء ، الى اي انشاء من انشاآت مشروع المياه

(ج) ان يفتح او يغلق بوجه غير مشروع اي زرفيل او حنفية او صمام او محبس او صنبور او منهل يخص انشاآت مشروع المياه

(د) ان يقوم بأي شيء من شأنه ان يسبب تلويث المياه او اعاقة مجراها

(هـ) ان ينشئ او يحفر ، او يقيم ، او يركب ضمن المنطقة ، اي خزان للمياه او حوض ، او بئر ، او صهريج ، او نفق ، او مسقاة او ماسورة رئيسية ، او انبوبة اضافية ، او حنفية او صمام ، او مضخة ، او آلة ، او اي انشاء او جهاز آخر من اجل خزن المياه ، او نقلها او توريدها ، او قياسها ، او تنظيمها ، الا بعد ان يكون قد استحصل مقدما على تصريح خطي من المجلس بشأن ذلك العمل

تبليغ المستندات — المادة ٢٩ ان كل قائمة حساب ، او مذكرة طلب ، او اشعار او اخطار ، او اي مستند من المستندات التي يقضي هذا النظام بوجوب تبليغها للمشترك ، يعتبر انه قد بلغ اليه تبليغا كافيا ، اذا ارسل اليه بالبريد العادي ، او سلم الى المحل الذي يتعاطى

فيه عمله ، او الى محل اقامته ، فاذا ارسل اليه بالبريد العادى ، يعتبرانه قد بلغ اليه في اليوم الثاني من تاريخ ارسله الى المشترك في البريد ، ويعتبر التبليغ الذ يتم بالتسليم في المحل الذى يتعاطى فيه المشترك عمله او في محل اقامته ، انه قد تم حسب الاصول ، اذا سلم المستند من قبل احد موظفي البلدية الى المشترك او الى اى شخص يشتغل في المحل الذى يتعاطى فيه المشترك عمله ، او الى اى فرد بالغ من افراد عائلة المشترك يقيم معه في مسكنه او اذا الصق على باب محل العمل او المسكن

احكام موقتة — المادة ٣٠ يقتضي على مالك او مشغل اى عقار تورد اليه المياه من قبل البلدية حين بدء العمل بهذا النظام ، أن يقدم خلال شهر من التاريخ المذكور ، طلبا الى المجلس وفقا لاحكام المادة الثامنة من هذا النظام . فاذا تخلف المالك او المشترك عن تقديم الطلب المذكور الى المجلس خلال المدة المذكورة ، يحق للمجلس ان يقطع المياه المورودة الى العقار المذكور

العقوبة — المادة ٣١ كل من خالف اى حكم من احكام هذا النظام يعاقب بغرامة لا تتجاوز عشرين جنيها عن كل مخالفة يرتكبها ، فاذا استمر ارتكاب المخالفة يعاقب بغرامة اضافية لا تزيد على جنيه واحد عن كل يوم يستمر فيه ارتكاب المخالفة بعد ابلاغه اخطارا كتابيا بتلك المخالفة من قبل رئيس البلدية ، او بعد ادانته ، ان لم يكن قد بلغ اخطارا كتابيا كهذا

بدء العمل بالنظام — المادة ٣٢ يعمل بهذا النظام اعتبارا من تاريخ نشره في الوقائع الفلسطينية

الـــــذيل

نموذج طلب لتوريد المياه من قبل بلدية طولكـــرم

(المادة ٨ من نظام (مشروع مياه) طولكرم لســـنة ١٩٤٤)

انا ....

اطلب تزويدى بالمياه . ـ (

" ا " من اجل استعمالها في الشؤون المنزلية في العقار الكائن ....
....(١)

الذى يسكن فيه ....(٢)

" ب " من اجل سقي بستان مساحته .... مترا مربع

" ج " من اجل كراج خصوصي

" د " من اجل سقي الحيوانات التالية ....

" هـ " من اجل العقارات التجارية التالية ....

" و " من اجل البناء

التاريخ .... التوقيع ....

(١) يجب ان تذكر اوصاف العقار بالتفصيل ، واذا لم يكن مقدم الطلب هو صاحب العقار يدرج اسم صاحب العقار

(٢) ينبغي ان تذكر التفاصيل الوافية عن عدد واسماء العائلات التي تسكن في العقار

رئيس بلدية طولكـرم

اقترن بموافقة فخامته

55

156

30 SEP 1944

P.16a

الرجاء ان تذكروا عند الاجابة
رقم ٢٩/٢

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

٢٠/٩/١٩٤٤

سعادة مساعد حاكم اللواء في طولكرم المحترم

أقدم طياً نظام (مشروع) مياه طولكرم لسنة ١٩٤٤ الذي وضعه مجلس بلدية طولكرم عوضاً عن نظام (مشروع مياه) جنين المنشور في الملحق رقم ٢ للعدد ١٣٤٨ من الوقائع الفلسطينية الصادر بتاريخ ٢٧/٧/١٩٤٤،
أرجو رفعه للموافقة عليه ونشره في الوقائع الفلسطينية بوقت قريب.
وتفضلوا بقبول فائق الاحترام

[signature]
رئيس لجنة بلدية طولكرم

A.D.C.

The by-laws is published in P.G. No. 1348 page 705 for Jenin Municipal Commission, D.C.'s letter No. 1402 of 29-8-44 para 2. (File No. 1290 page 8) refers. [initials]

I asked the municipality to submit the Arabic copy in ~~triplicate~~ quadruplicate x

x and the English copies will be typed at this office [initials]

[initials] 2.9.44.

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]
[illegible]
[illegible]
[illegible]

[illegible]

[illegible]

[illegible]

قانون البلديات لسنة ١٩٣٤

ق م ١ لسنة ١٩٣٤ ان لجنة بلدية طولكرم ، استناداً الى الصلاحية المخولة لها في المادة التاسعة والتسعين من قانون البلديات لسنة ١٩٣٤ ، قد اصدرت النظام التالي : —

اسم النظام — المادة ١ يطلق على هذا النظام اسم نظام (فروع مياه) طولكرم لسنة ١٩٤٤ .

تفسير اصطلاحات — المادة ٢ يكون للالفاظ والعبارات التالية الواردة في هذا النظام المعاني المخصصة لها أدناه ، الا اذا دلّت القرينة على غير ذلك : —

تعني عبارة (منطقة البلدية) منطقة بلدية طولكرم و « هيئة البلدية » هيئة بلدية طولكرم ، و« مجلس البلدية » مجلس بلدية طولكرم .

وتعرف لفظة « الوصلة » الى الانبوب الممتد من انابيب المياه الرئيسية العائدة لهيئة البلدية حتى دورة المياه ، وتشمل العداد وجميع المحابس والصمامات والصنابير والمضخة وعبوة عداد المياه ، المستعملة أو التي يراد استعمالها في توريد المياه من قبل هيئة البلدية أو فيما يتعلق بذلك .

وتفيد عبارة « رسم الوصل » الرسم الذي تقرره اللجنة ، بموافقة حاكم اللواء من أجل تركيب الوصلة

ويراد بلفظة « التأمين » المبلغ الذي يقرره المجلس ، بموافقة حاكم اللواء ، ويدفعه المشترك مقدماً ، لضمان دفع رسم المياه و/ أو اجرة العداد .

وتعني عبارة « الماء المخصص للشؤون المنزلية » الماء الذي يستهلكه الانسان ، أو يستعمل لغسل أدوات البيت وللتنظيف ، ولكنه لا يشمل المياه التي تستعمل للابقار أو الخيول أو غسل المركبات أو المحركات أو الآلات التجارية أو السكك الحديدية ، أو لتدفئة الابنية العمومية أو مهو سرح ، أو لتشغيل الماكنات والآلات ، أو لأية حرفة أو صناعة أو متجر مهما كان نوعه ، أو لسقي الحدائق بواسطة الحنفيات ، أو الخراطيم ، أو الانابيب ، أو ما شابه ذلك من الاجهزة ، أو للنوافير (الشادروانات) او الحمامات العمومية ، أو اماكن الغسيل أو لأي غرض من أغراض الزينة مهما كانت .

وتعرف لفظة « العداد » الى الجهاز الذي يركب في العقار لقياس وضبط كمية المياه التي تسحب من انشاءات فروع المياه الى ذلك العقار .

وتفيد عبارة « اجرة العداد » الاجرة التي يقررها المجلس ، بموافقة حاكم اللواء ، لاستعمال العداد الذي يخص البلدية .

وتعرف لفظة « المالك » فيما يتعلق بأي عقار ، الى الشخص الذي يتقاضى بدل ايجار أو ريع ذلك العقار ، سواء أكان ذلك لحسابه الخاص أم بصفته وكيلاً عن شخص آخر ، أو قيماً أو وصياً عليه ، أو الى الشخص الذي يتقاضى بدل الايجار او الريع المذكور فيما لو اجر العقار ، سواء أكان ذلك الشخص متصرفاً بالعقار او مالكه المعروف أم لم يكن ، وسواء أكان العقار مسجلاً باسمه أم لم يكن ، وتشمل الصفة الشريك ومتولي الوقف .

وتعني لفظة « العقار » الابنية والاراضي مهما كان نوعها ، مسورة كانت أم غير مسورة ،

مبنياً عليه أم خالية، عمومية أم خصوصية، وسواء أكانت محتفظاً بها أم تدار بموجب سلطة قانونية أم لم تكن.

وتعني عبارة «الحنفية العمومية» حنفية أو حنفية قائمة على أنبوب أو صمام أو صنبور أو جهاز مما تنشئه أو تركبه هيئة البلدية وتستعمل أو تنوي استعماله لتوريد المياه للجمهور أو فيما يتعلق بذلك ويكون ملك البلدية.

وتنصرف عبارة «دورة المياه» الى جميع ما يخص مالك العقار من أنابيب وصمامات وآبار (صهاريج) وحنفيات ووصلات وغير ذلك من الأدوات، ابتداءً من العداد (ان كان ثمة عداد) وان لم يكن هناك عداد، فابتداءً من نهاية وصلة البلدية الكائنة ضمن حدود العقار المحولة اليه المياه أو الذي يراد سحب المياه اليه من انشاءات مشروع المياه.

وتفيد عبارة «المشترك» أي شخص مسجل لدى المجلس كمشترك لأخذ المياه وفقاً لأحكام هذا النظام.

وتعني عبارة «رسم المياه» الرسم الذي يقرره المجلس، بموافقة حاكم اللواء، ويستوفى من مشترك مقابل المياه التي تورد اليه.

وتنصرف عبارة «انشاءات مشروع المياه» جميع الخزانات، والأحواض، والأقنية والآبار، والصهاريج، والأنفاق، والمصافي، والأنابيب الرئيسية، والأنابيب الفرعية، والحنفيات، والصمامات، والمضخات، والمحركات، والأجهزة، وسائر الانشاءات والأدوات الأخرى المستعملة أو المنشأة لخزن المياه، أو نقلها، أو توريدها، أو قياسها، أو تنظيمها، والتي تستعملها أو أنشأتها البلدية. أو أنشئت بالنيابة عنها وهي ملك لها، أو التي تستعملها أو تنشئها فيما بعد من أجل الغايات الآنفة الذكر.

انشاءات مشروع المياه وتوريد المياه

المادة ٣ يتولى المجلس العناية بانشاءات مشروع المياه والمياه الموجودة فيها وادارتها والاشراف على توريد وتوزيع المياه.

صلاحية الدخول الى العقار

المادة ٤ يجوز لأي موظف من موظفي البلدية، مفوض حسب الأصول من المجلس ان يدخل الى اي عقار لفحص أي أنبوب او وصلة او جهاز آخر من أجهزة المياه، او لاصلاحه أو ازالته، وذلك في اي وقت بين الساعة الثامنة صباحاً والسادسة مساءً، وبعد اعطاء اشعار معقول بذلك، وكل شخص يعترضه أو يعيق الموظف المذكور عن القيام بهذا الواجب يعرض نفسه للعقوبات المنصوص عليها في هذا النظام.

مد الأنابيب

المادة ٥ يجوز للمجلس ان يمد أي أنبوب من أنابيب المياه في اي طريق عام أو مكان مخطط كطريق عام أو يراد استعماله كذلك، أو ان يمده من الجانب الواحد منه الى الآخر أو تحته.

الحنفيات العمومية

المادة ٦ يحق للمجلس ان ينشئ حنفيات عمومية في اي طريق عام أو مكان عام.

قطع المياه

المادة ٧ يحق للمجلس، في اية حالة طارئة، ان يقطع المياه المورّدة من قبله بواسطة اي جهاز من أجهزة المياه أو اية حنفية عمومية، او ان يمتنع عن توريد المياه او ان يوقفها او يغير مجراها، كلياً او جزئياً، كلما رأى المجلس ذلك ضرورياً أو ملائماً، دون ان يخفف ذلك في المبالغ المستحقة او التي تستحق بمقتضى هذا النظام.

تقديم الطلبات لتوريد المياه

المادة ٨ – (١) يترتب على كل شخص يرغب في توريد المياه اليه، ان يقدم بادئ ذي بدء طلباً كتابياً بذلك الى المجلس على النموذج المعين في ذيل هذا النظام.

(٢) يعين المجلس عندئذ الشروط التي يمنح الطلب بموجبها بما في ذلك مقدار التأمينات ورسم المياه، ويجوز له ان يرفض توريد المياه الى ان يتم تنفيذ الشروط ودفع التأمينات.

(٣) حينما يستلم المجلس موافقة الطالب خطياً على الشروط المذكورة، يصبح الطالب مشتركاً.

العقود

المادة ٩ يترتب على المشترك ان يعقد عقداً مع المجلس، يشتمل على الشروط التي يفرضها المجلس لتوريد المياه اليه وفقاً للفقرة (٢) من المادة الثامنة من هذا النظام وان يدفع جميع الرسوم والمصاريف المتعلقة بذلك العقد.

وصل أجهزة المياه

المادة ١٠ حينما يصبح المجلس مشتركاً، يتولى المالك على نفقته اقامة دورة المياه وتركيبها وصيانتها في حالة جيدة، وفقاً للشروط المعينة وباشراف موظف من موظفي البلدية مفوض بذلك الشأن من المجلس.

ربط أجهزة المياه

المادة ١١ يقوم المجلس بوصل دورة المياه بالمواسير الرئيسية، ويدفع المالك رسم الوصل وجميع المصاريف الناشئة عن عملية الوصل، ولا يجوز لأي شخص ان يفتح أو يقفل انابيب أو حنفيات أو أدوات الوصل، أو ان يعبث بها على أي وجه آخر، مهما كان السبب الذي يتذرع به، الا بتفويض من المجلس.

التأمين

المادة ١٢ يترتب على المشترك، حالما يسجل لدى المجلس، ان يدفع التأمين المقرر، الى امين صندوق البلدية، ويحق للمجلس ان يستوفي من التأمين المذكور اية رسوم او عوائد او تكاليف قد تستحق على المشترك بمقتضى هذا النظام

تعيين حجم ونوع الانابيب

المادة ١٣ يقرر المجلس حجم ونوع الأنابيب التي ستستعمل في دورة المياه والوصلة والمكان الملائم لايصال المياه منه الى العقار.

تركيب العداد

المادة ١٤ – (١) يجوز للمجلس، في اي وقت من الاوقات، ان يركب عداداً او اكثر في اي عقار تورد اليه المياه

(٢) في الأحوال التي يركب فيها عداد، يلزم المشترك بدفع اجرة العداد مقابل استعماله.

(٣) يكون العداد ملكاً للبلدية، ويتولى المجلس حفظه في حالة جيدة.

صيانة العداد

المادة ١٥ اذا ركب المجلس عداداً، يقتضي ان يحفظ ذلك العداد في خزانة من الاسمنت وان يكون لباب الخزانة مفتاحان يحتفظ المشترك بأحدهما ويبقى الثاني لدى الموظف المعين من قبل المجلس لتفتيش المياه، ولا يحق للمشترك بأية حالة من الحالات ان يعبث بالعداد او ان ينقله من مكانه او يزيله، ولا يجوز اجراء ذلك الا من قبل موظف مفوض معين من المجلس.

العبث بالعداد

المادة ١٦ ان أي عبث يلحق بالعداد يعرض المشترك لقطع المياه عنه.

الرسوم الخ

المادة ١٧ يعين المجلس بقرار يتخذه يقترن بموافقة حاكم اللواء، رسم المياه، واجرة العداد ومبلغ التأمين، ورسم الوصل، وغير ذلك من الرسوم والمصاريف، ويجوز تغيير هذه الرسوم والأجور والمبالغ من وقت لآخر بالصورة الآنفة الذكر.

حساب رسم المياه

المادة ١٨ – (١) حينما يركب عداد، تكون كمية المياه التي يطالب المشترك بدفع رسم عنها، هي الكمية التي يسجلها العداد.

(٢) اذا اقتنع المجلس بأن في عداد المياه خللاً، او بأنه لم يسجل او قد لا يسجل الكمية الصحيحة للمياه المستهلكة، او بأنه مكسور أو مقطوع، تقدر رسوم المياه عن المدة التي كان العداد فيها معطوباً على اساس الكمية التي استهلكها المشترك خلال مدة تساوي تلك المدة من الفصل ذاته في السنة الماضية، واذا كانت كمية المياه التي وردت خلال الفصل ذاته من السنة الماضية لم تحسب بواسطة عداد، فتحسب كمية المياه الموردة وفقاً لما يراه المجلس، ويكون قراره بهذا الشأن نهائياً مبرماً.

(٣) في الأحوال التي لم يركب فيها عداد، تستوفى قيمة مقطوعة.

موعد الدفع

المادة ١٩ – (١) اذا لم يركب عداد في اي عقار، يترتب على المشترك ان يدفع مقدماً رسم المياه المستحق عن نصف السنة التالية، ويستحق دفع القسط نصف السنوي في نيسان وايلول. واذا كانت المياه الموردة الى المشترك تحسب بواسطة العداد، فيقتضي عليه ان يدفع في آخر كل شهر رسم المياه التي استهلكها في ذلك الشهر مع اجرة العداد.

(٢) ان المبلغ الواجب دفعه عن المياه التي تستعمل في اثناء بناية او في اية عملية من عمليات البناء، يدفع بكامله الى البلدية حين اصدار رخصة البناء المتعلقة بتلك الانشاءات او عملية البناء المذكورة، الا اذا كانت المياه المجلوبة عندئذ تورد بواسطة عداد.

قطع المياه للتخلف عن الدفع او تبذير المياه او العبث بها

المادة ٢٠ اذا حدث ان تخلف مشترك عن تسديد حسابه خلال ثمانية ايام من تاريخ تبلغه بياناً بالحساب، او تخلف عن منع تبذير المياه او سوء استعمالها او عن ازالة اية كراهة ناشئة عنها، بعد تبليغه اخطاراً كتابياً بذلك من رئيس البلدية، يتعرض ذلك المشترك لقطع المياه عن عقاره، ولا يجوز له ان يعاد وصل المياه بعقاره الا بعد ان يسدد كافة المبالغ المستحقة عليه او اصلاح الخلل المشار اليه. ويقتضي عليه، بالاضافة الى ذلك، ان يدفع الرسم الذي يقرره المجلس بموافقة حاكم اللواء، مقابل اعادة توريد المياه اليه، مع نفقات اعادة الوصل. ويجوز لاي شخص معين من قبل المجلس ان يدخل الى اي عقار كان في اي وقت من الاوقات بين الساعة الثامنة صباحاً والسادسة مساءً، دون عائق، من اجل توقيف توريد المياه، او قطعها، او تحويلها.

الاعفاء من الرسوم

المادة ٢١ يجوز للمجلس ان يعفي من رسم المياه، المدارس، والمساجد، والكنائس، كما يجوز له ايضاً ان يعفي من رسم المياه، مؤسسات البر والاحسان، كالمياتم (الهوسبيس) والمستشفيات، والتكايا، بشرط ان تكون مستعملة كلياً لاقامة المحتاجين او قبول المرضى مجاناً.

حظر التركيب او التغيير دون اذن

المادة ٢٢ لا يجوز لاي مشترك، او لاي شخص يسكن في عقار المشترك، او لاي شخص آخر ان يركب دورة للمياه، او ان يغير او يوسع او يعبث باية دورة مياه وضعت او ركبت من قبل المجلس او بترخيص منه، الا بعد الحصول على اذن خطي بذلك من المجلس.

حظر مجاورة حفر المراحيض للانابيب

المادة ٢٣ – (١) لا يجوز لاي شخص ان يسمح بوجود حفرة للرماد، او للقاذورات، او بجورة مرحاض او حفرة ارشح او مطابخ او وعاء او شيء غير نظيف بالقرب من دورة المياه.

(ج) يكون المالك مسؤولاً عن إزالة أو إصلاح أو تغيير أية حفرة مياه أو حفرة فاذورات أو حفرة فحص أو حفرة رشح أو مكانه أو وعاء أو شيء غير نظيف، إذا كلفه رئيس البلدية بذلك بإشعار كتابي، فإذا تخلف المالك عن إجراء ما كلف به في الإشعار، من نقل أو إصلاح أو تغيير ضمن المدة المعينة في الإشعار وعلى الوجه المشار فيه، يحق للمجلس أن يقوم بعملية الإزالة أو الإصلاح أو التغيير وأن يحصل النفقات من المالك.

حظر تبذير المياه

المادة ٢٤ لا يجوز لأي مشترك أو شخص يسكن في عقار مشترك بورد إليه المياه، أن يسمح بتبذير المياه بسبب وجود خلل في أية وصلة، أو بترك أية وصلة أو حنفية مفتوحة، ويترتب على المشترك أن يبلغ اللجنة فوراً عن أي خلل كهذا، كما يترتب على مالك العقار أن يتخذ التدابير الضرورية في الحال لإصلاح ذلك الخلل.

السنكريون المفوضون

المادة ٢٥ – (١) لا يجوز لأي شخص أن يركب مجاري مياه، أو يغيرها أو يصلحها، كما لا يجوز السماح لأي شخص القيام بما سبق ذكره، إلا إذا كان ذلك الشخص يحمل شهادة سنكري صادرة من المجلس تصرح له بالقيام بالعمليات المذكورة، ويقتضي على حامل رخصة السنكرة أن يبرزها لدى الطلب إلى الشخص المفوض بذلك من المجلس أو إلى مالك العقار.

(٢) إذا كان من رأي المجلس، في أي وقت من الأوقات، أن شخصاً يحمل رخصة لتعاطي مهنة السنكرة بمقتضى هذا النظام، قد تخلف أو قصر في القيام بالشغل على وجه يرضى به المجلس، يجوز له أن يلغي رخصته، وحينئذ لا يسمح لذلك السنكري بتعاطي مهنة السنكرة بمقتضى أحكام هذا النظام.

استعمال المياه

المادة ٢٦ لا يجوز لأي مشترك أو لأي شخص يسكن في عقار مشترك، أو لأي شخص آخر، أن يستعمل المياه الموردة بواسطة دورة المياه، أو أن يسمح باستعمالها لأية غاية خلاف الغايات المذكورة في العقد المعقود لتوريد المياه إلى تلك الدورة.

حظر نقل المياه

المادة ٢٧ لا يجوز لأي مشترك، أو لأي شخص يسكن في عقار مشترك، مدت فيه المياه، أن يسمح لأي شخص بنقل المياه من عقاره لاستعمالها لأية غاية من الغايات مهما كانت، إلا بعد الحصول على موافقة خطية بذلك من المجلس.

حظر تلويث المياه

المادة ٢٨ لا يجوز لأي شخص :—

(أ) أن يستحم أو يغسل في أي قسم من انشاءات مشروع المياه

(ب) أن يطرح أو يتسبب أو يسمح بطرح أو دخول أي حيوان أو ثياب أو مواد أو أشياء، إلى أي انشاء من انشاءات مشروع المياه.

(ج) أن يفتح أو يعالج بوجه غير مشروع أي دفيل أو حنفية أو صمام أو محبس أو صنبور أو سبيل يخص انشاءات مشروع المياه.

(د) أن يقوم بأي شيء من شأنه أن يسبب تلويث المياه أو إعاقة مجراها.

(هـ) أن ينشئ ، أو يحفر ، أو يقيم ، أو يركب ضمن المنطقة ، أي خزان للمياه ، أو حوض ، أو بئر ، أو صهريج ، أو نفق ، أو مصفاة ، أو ماسورة رئيسية ، أو أنبوبة اضافية ، أو حنفية ، أو صمام ، أو مضخة ، أو آلة ، أو أي انشاء أو جهاز آخر من أجل خزن المياه ، أو نقلها ، أو توريدها ، أو قياسها ، أو تنظيمها ، الا بعد ان يكون قد حصل مقدماً على تصريح خطي من المجلس بشأن ذلك العمل .

تبليغ المستندات

المادة ٢٩ ان كل لائحة حساب ، أو مذكرة طلب ، أو اشعار ، أو اخطار ، أو أي مستند من المستندات التي يقضي هذا النظام بوجوب تبليغه للمشترك ، يعتبر انه قد بلغ اليه تبليغاً قانونياً ، اذا ارسل اليه بالبريد العادي ، أو سلم الى المحل الذي يتعاطى فيه عمله ، او الى محل اقامته ، فاذا ارسل اليه بالبريد العادي ، يعتبر انه قد بلغ اليه في اليوم التالي من تاريخ ارساله الى المشترك في البريد ، ويعتبر التبليغ الذي يتم بالتسليم في المحل الذي يتعاطى فيه المشترك عمله أو في محل اقامته ، انه قد تم حسب الأصول ، اذا سلم المستند من قبل أحد موظفي البلدية الى المشترك أو الى أي شخص يشتغل في المحل الذي يتعاطى فيه المشترك عمله ، أو الى أي فرد بالغ من افراد عائلة المشترك ، يقيم معه في مسكنه ، او اذا الصق على باب محل العمل أو المسكن .

أحكام مؤقتة

المادة ٣٠ يقتضي على مالك أو مشغل أي عقار تورد اليه المياه من قبل البلدية حين بدء العمل بهذا النظام ، ان يقدم خلال شهر من التاريخ المذكور ، طلباً الى المجلس وفقاً لأحكام المادة الثامنة من هذا النظام . فاذا تخلف المالك أو المشترك عن تقديم الطلب المذكور الى المجلس خلال المدة المذكورة ، يحق للمجلس ان يقطع المياه المورّدة الى العقار المذكور .

العقوبة

المادة ٣١ كل من خالف أي حكم من احكام هذا النظام يعاقب بغرامة لا تتجاوز عشرة جنيهات عن كل مخالفة يرتكبها ، فاذا استمر ارتكاب المخالفة يعاقب بغرامة اضافية لا تزيد على جنيه واحد عن كل يوم يستمر فيه ارتكاب المخالفة بعد ابلاغه اخطاراً كتابياً بتلك المخالفة من قبل رئيس البلدية ، او بعد ادانته ، ان لم يكن قد بلغ اخطاراً كتابياً كهذا .

بدء العمل بالنظام

المادة ٣٢ يعمل بهذا النظام اعتباراً من تاريخ نشره في الوقائع الفلسطينية .

الذيل

نموذج طلب لتوريد المياه من قبل بلدية طولكرم

(المادة ٨ من نظام (مشروع مياه) طولكرم لسنة ١٩٤٤)

انا .... اطلب تزويدي بالمياه :ـ

(أ) من اجل استعمالها في الشؤون المنزلية في العقار الكائن ....
.... (١) الذي يسكن فيه ....(٢)

(ب) من اجل سقي بستان مساحته .... متر مربع

(ج) من اجل كراج خصوصي

(د) من اجل سقي الحيوانات التالية ....

(هـ) من اجل العقارات التجارية التالية ....

(و) من اجل البناء

التاريخ .... التوقيع ....

(١) يجب ان تذكر اوصاف العقار بالتفصيل ، واذا لم يكن مقدم الطلب هو صاحب العقار يدرج اسم صاحب العقار.

(٢) ينبغي ان تذكر التفاصيل الوافية عن عدد واسماء العائلات التي تسكن في العقار.

[توقيع]
رئيس بلدية طولكرم

اقترن بموافقة فخامته

NO.TUL.136/34. 54

Assistant District Commissioner's Office,
Tulkarm.

26th September, 1944.

The Chairman,
Municipal Council,
Tulkarm.

Sir,

Subject :- Use of Municipal Water Sprinkling Cart to transport water to Anabta.

Ref'nce :- Our conversation.

The Controller of Road Transport, Jerusalem, has agreed to the use of your water sprinkler to transport water to Anabta during the period in which the water pump of that village is under repair.

2. The Local Council at Anabta are prepared to pay all expenses connected with this service.

3. Please arrange that a careful record be kept of all journeys made so that I can supply you later with a certificate that this additional work has been imposed upon the sprinkler in an emergency and that, when the matter of replacement of tyres arises, you can use this certificate in support of your claim.

4. Please also inform me what additional petrol coupons you will need so that I can apply for such on your behalf.

I have the honour to be,
Sir,
Your obedient servant.

J. S.

Assistant District Commissioner,
Tulkarm.

sup 86

Copy to District Commissioner,
Samaria District.

" " President, Local Council, Anabta,

" " Anabta Local Council File. No 15

Replied see file No. 15

C.C

Ask Mayor what is the position with regard to the purchase of a new engine for water supply.

V. G.
29/7

A. D.C.

His Worship the Mayor informed that a notice was published to the effect that Municipality desires to purchase a new engine, but no reply was received from any body. However, the Mayor is now enquiring from another two Companies whose addresses are known to him and hopes that the result will be communicated to you within the next fortnight. [illegible]

~~[illegible] 30-7.44~~ [illegible] 29.7.

P. A. in [illegible].
V. G.
31/7

C.L. 4.

URBAN PROPERTY TAX ORDINANCES, 1928—32

قانون ضريبة الاملاك في المدن لسنة ١٩٢٨—٣٢ פקודת מס הרכוש העירוני 32—1928

Notice of Valuation. اعلان التخمين

הודעה בנידון שומא

النمرة
המספר 167786

Urban Area of طولكرم منطقة مدينة
האזור העירוני של

TO عبد الرحمن افندي الحاج ابراهيم حضرة

Take Notice

that the property described hereunder, of which you are stated to be the reputed, owner, has been assessed in respect of Urban Property Tax as follows:

ليكن معلوماً لديك بان الملك المبينة اوصافه وتفاصيله ادناه الذي يقال انك مالكه المعروف قد جرى تخمينه لاستيفاء ضريبة الاملاك عنه على الوجه التالي :

ליהוי ידוע לך שהרכוש המפורש לקמן שאתה הנך מתואר כבעל הידוע שלו הוערך לצורך מס רכוש עירוני כדלקמן:

23917—1500 Books 6/7/33 A.P.

Name of Street اسم الشارع שם הרחוב	Name and Number of Block اسم القطعة ونمرتها שם הגוש ומספרו		No. of Parcel نمرة القسيمة מספר החלקה	Description of Property اوصاف الملك תאור הרכוש	Category for Taxation نوع الملك من حيث الضريبة סוג לצרכי מסים	Net Annual Value قيمة الايجار السنوي الصافي חשוי השנתי הנקי (נטו) ج.ف. P. £. פ"פ (א"י)
الحل المعزيم	٨٠٠٢		٨٦	دار	A	٢١

52

C.C.

Tell Mayo that they should avoid spending money on repairs (L.P. 200) & should start negotiations for purchase of new engine but that they should NOT commit themselves financially.

v. glm

Fin. Jomed

[initials]
15/3/44

F. 54.

GOVERNMENT OF PALESTINE.

حكومة فلسطين ממשלת פלשתינה (א"י).

№ 167159

Werko Officer's Certificate for Transaction in Immovable Property.

شهادة مأمور الويركو بمعاملات الاملاك الغير منقولة
תעודת פקיד הורקו להעברת נכסי דלא ניידי

File No. نمرة الدوسية 20/491
מספר המעטפה

PARTICULARS OF EXISTING REGISTRATION IN WERKO OFFICE
التفصيلات عن القيود الحالية في دائرة الويركو
פרטי הרשומים הקימים במשרד הורקו

District القضاء מחוז طولكرم — Town or Village البلدة او القرية עיר או כפר شابا

Quarter or Locality الموقع او المحلة סביבה או שכונה الويد — No. on Door النمرة على الباب מספר הבית — Street الشارع רחוב

Nature of Property نوع الملك מין הנכסים ٧٧٢ — Extent المساحة שטח ٩٧٥

Werko Registration No. (Umum) نمرة عموم قيد الويركو רשום הורקו מספר — Value L.P. القيمة ج. ف ערך לי"פ — Mils مل מיל

Boundaries الحدود הגבולות
الحدود خارج

Transferor البائع המעביר
[illegible]

of في ב — Werko Khulasa page صحيفة خلاصة الويركو דף הורקו (חולסה) ٢ / ٩٠

Transferee المشتري המעבר אליו
يعقوب [illegible]

of في ב شابا — Werko Khulasa page صحيفة خلاصة الويركو דף הורקו (חולסה)

I hereby certify that all the Taxes assessed on the above property from the 1st March, 1918, up to date have been collected

اصدق بان كل الرسوم المفروضة على الملك المذكور اعلاه من ١ مارت سنة ١٩١٨ لهذا التاريخ قد تحصل

הנני מאשר בזה שנאספו כל המסים המוטלים על הנכסים הנ"ל מהראשון לחרש מרס 1918 עד היום הזה

Place المحل מקום طولكرم — Signature الامضاء חתימה [signature]

Date التاريخ תאריך 20/1/28 — Werko Officer of the District of مأمور الويركو في منطقة פקיד משרד הורקו של מחוז طولكرم

Additional remarks (if any) by Werko officer:- ملاحظات مأمور الويركو الخصوصية
הערות פקיד משרד הורקו

28284—800 Bks.—1.6.35—S.O.P.

85/2.

(Translation).

57

Municipality of Tulkamm.
26-2-1944.

Asst. Dist. Commissioner,
Tulkarm.

Through Dist. Officer ,
Tulkarm.

Last week I have been informed by the Municipal Mechanic that the quantity of water in the municipal well has exceeded its normal level and it is apprehended that water will flood the electrical motor and cause damage to it.

We immediately got in touch with "AWAD COMPANY" now superintending the "WAGNER FACTORIES" at Jaffa, with a view to sending labourers to Tulkarm for the purpose of removing the motor and pump and erecting them again on a higher spot.

Awad Company considered it more wise to send an engineer to Tulkarm to inspect the well and ascertain whether work could be started. The engineer, after inspecting the well, made a report to the company to the effect that work cannot be started unless the municipality improves means of ventilation and effect other repairs. Such repairs, subject to execution, will cost the municipality about LP 200 for which there is no allocation in the Estimates.

Add to that many repairs have been entered in previous years and electrical van has been installed inside the well to improve ventilation and labourers carry on their work without difficulty whenever necessary.

I am also informed that the water level is likely to descend and I have therefore decided not to carry out any repair in the motor and pump unless it is observed that water is likely to rise.

In this occasion I should like to stress the extreme importance of installing another motor and pump for water supply scheme in Tulkarm because water is always subject to stoppage whenever any damage occurs to the motor or pump.

I have allocated LP 2000 in the next year's estimate for the water supply scheme and I think, it is necessary to negotiate with companies and take necessary steps to prepare works in order that new machinery be constructed at an early time.

I shall be grateful to receive your comments on this subject.

(sgd) H. Jayousi,
Chairman, Mun. Commission,
Tulkarm

[illegible]

[illegible] 11, [illegible]

[illegible]

[illegible]

[illegible]

[illegible] will [illegible].

[illegible] now [illegible] view to [illegible].

[illegible] for which [illegible] in the [illegible].

[illegible] of previous [illegible].

[illegible] it is [illegible] rise.

[illegible]

[illegible]

[illegible] help me [illegible].

51

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٨٥/٢

ASSISTANT DISTRICT COMMISSIONER
156
28 FEB 1944

طولكرم في ٢٦/٢/٩٤٤

سعادة مساعد حاكم اللواء في طولكرم المحترم
بواسطة سعادة قائمقام طولكرم المحترم

الموضوع :- مشروع الماء في طولكرم

فهمت في الاسبوع الماضي من ماكينست البلدية بأن الماء في بئر البلدية قد ارتفع عن معدله الاعتيادي واصبح يخشى ان يصل الى الموتور الكهربائي فيتلفه . لذلك فقد اتصلنا حالاً مع شركة عوض المشرفة على معامل واكنز في يافا وطلبت منها ان تبعث عمالاً لاجل نقل الموتور والطلمبة من محلها وتركيبها في محل أعلى من الحالي . على ان الشركة رأت ان تبعث مهندساً ليكشف عن البئر قبل المباشرة بالعمل . وقد حضر المهندس يوم ٢٢/٢/٤٤ وبعد الكشف قدم تقريراً للشركة بأنه يتعذر الشغل في بئر بلدية طولكرم قبل ادخال اصلاحات ضرورية عليه مثل تحسين التهوية وغير ذلك . وتقدر تكاليف هذه الاصلاحات بنحو (٢٠٠) جنيه وبعدها يستطاع المباشرة بالعمل . لا توجد مخصصات لمثل هذا العمل في ميزانية البلدية ولا اعتقد لضرورته ، فقد أدخلت تحسينات كثيرة على البئر في السنوات الأخيرة وركبت فيه مروحة كهربائية للتهوية . والعمال يشتغلون فيه كلما دعت الحاجة بدون اية صعوبة . هذا وقد علمت الآن ان الماء لم يرتفع خلال الاسبوع عما وصل اليه في الاسبوع الماضي بل يلاحظ فيه ميل للانخفاض . ولهذا رأينا أن لا نقدم على اي تغيير في تركيب الآلات الآن الا اذا لاحظنا ميلاً جديداً لارتفاع الماء .

ولا بد لي بهذه المناسبة ان اكرر بيان حاجتنا الشديدة الى موتور وطلمبة أخرى لمشروع الماء . اذ اننا في الوضع الحاضر معرضون لانقطاع الماء عن البلدة عند حصول اي عطل في الآلات الموجودة . لقد خصصنا في ميزانية السنة المقبلة مبلغ (٢٠٠٠) جنيه لهذا الغرض . وأرى ان نباشر من الآن في مفاوضة الشركات وتحضير الاعمال التمهيدية حتى اذا دخلت السنة الجديدة نستطيع عقد المقاولات والمباشرة في تركيب الآلات الجديدة بوقت مبكر . اكون ممتناً اذا تفضلتم علينا برأيكم في هذا الخصوص .

وتفضلوا بقبول فائق الاحترام

هاشم الجيوسي
رئيس لجنة بلدية طولكرم

S.D.C.
[illegible]
SC
2/3/44

GOVERNMENT OF PALESTINE

PUBLIC WORKS DEPARTMENT,
NABLUS.

No. 3/1/8. 14th October, 1943.

Asst. Dist. Commissioner,
Tulkarm.

Sub:-Tulkarm Water Supply.
Ref:-Your TUL/156/49 dated
10th September, 1943.

The girder is
accepted, please.

DISTRICT ENGINEER
NABLUS DISTRICT

Copy to:- Foreman, P.W.D.,
Tulkarm, who is
requested to issue
the necessary
Receipt Voucher.

49/HZ.

No. TUL. 156/49.

Assistant District Commissioner's Office,
Tulkarm.

10th Sept., 1943.

District Engineer,
Nablus.

Subject :- Tulkarm - Water Supply.
Ref'nce :- Your 3/1/2 of 6.9.43.

The Chairman, Municipal Commission, Tulkarm, informed me that the measurment of the girder quoted in the permit was 3.2 x 0.32x0.14 but when they produced the permit to Messrs Iron Stores, Tel-Aviv to purchase it, they were supplied the girder which has been handed over to the Foreman i/c P.W.D., Tulkarm on the assumption that this is required measurement.

2. In the circumstances I suggest you accept it.

(Sgd.) A. C. [illegible]

Assistant District Commissioner,
Tulkarm.

GOVERNMENT OF PALESTINE

156

PUBLIC WORKS DEPARTMENT,
NABLUS.

No. 3/1/2

6th September, 1943.

Asst. District Commissioner,
Tulkarm.

Subject :- Tulkarm-Water Supply.
Reference:- Your 156/46 of 17.8.43.

It is reported that the girder returned to P.W.D. Tulkarm has the following measurements 3.3 x 0.32 x 0.13 while it was agreed that the girder to be returned would be 3.2 x 0.32 x 0.14.

2. If it is impossible to obtain the girder the one promised the girder you have returnwd will be accepted. Please advise me of the position.

DISTRICT ENGINEER
NABLUS DISTRICT

Copy to:- Foreman, Tulkarm, ref. his T/1 of 2.9.43.

65/BS.

GOVERNMENT OF PALESTINE

PUBLIC WORKS DEPARTMENT,
NABLUS.

Ref. 2/1/2

6th September, 1943.

Asst. District Commissioner,
Tulkarm.

Subject :- Tulkarm-Water Supply.

Reference:- Your 156/43 of 17.8.43.

It is reported that the girder returned to P.W.D. Tulkarm has the following measurements 5.3 x 0.33 x 0.13 while it was agreed that the girder to be returned would be 5.8 x 0.33 x 0.14.

2. If it is impossible to obtain the girder the one provided the girder you have returned will be accepted. Please advise me of the position.

Divisional Engineer,
Samaria Division.

Copy to:- Foreman, Tulkarm, re his 2/1 of 3.9.43.

GG/AE.

No. TUL.156/47.

Assistant District Commissioner's Office,
Tulkarm.

7th September, 1943.

District Engineer,
Nablus.

Subject :- Tulkarm Water Supply.

Ref'nce :- Your 3/1/2 of 1st September, 1943.

The Chairman, Municipal Commission, Tulkarm, informed that the steel girder has been handed over to the Foreman i/c P.W.D. Tulkarm on 2nd September, 1943.

(Sgd.) A. S. KHAYR

Assistnt District Commissioner,
Tulkarm.

GOVERNMENT OF PALESTINE

156/46

PUBLIC WORKS DEPARTMENT,
NABLUS.

No. 3/1/2

1st September, 1943.

Asst. District Commissioner,
Tulkarm.

Subject :- Tulkarm Water Supply.

Reference:- Your 156/46 of 17th August, 1943.

When may I expedt the return of the steel ~~pipe~~ girder please.

DISTRICT ENGINEER
NABLUS DISTRICT

85/BS.

R/B

No.TUL.156/46.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE,
TULKARM.

17TH AUGUST,1943.

P39

Sir,

With reference to your letter No.85/5 of 6.7.43, the District Engineer Nablus has now agreed to accept the iron girder measuring 3.20 x 32 x 14 cms stocked by Messrs. Iron Stores, Tel-Aviv, in lieu of that borrowed by you from the Public Works Department.

2. I enclose a release permit for this girder issued by the Controller of Heavy Industries and will be grateful if you will arrange to purchase it and have it delivered to the District Engineer Nablus at your earliest convenience.

3. The permit has been issued in my name, but I take it that this letter will be sufficient authority for you to collect the girder on my behalf.

I am,
Sir,
Your obedient servant.

(Sgd.) J. M. MONTGOMERY
Assistant District Commissioner,
T u l k a r m.

P44

The Chairman,
Municipal Commission of Tulkarm.

Copy to District Engineer, P.W.D.Nablus.
Ref.my TUL/156/44 of 31.7.43.

5-1292

Per /No. SE 1326/D

GOVERNMENT OF PALESTINE

DUPLICATE

ASSISTANT DISTRICT COMMISSIONER'S OFFICE

14 AUG. 1943

TULKAREM

252

CONTROLLER OF HEAVY INDUSTRIES
P. O. B. 661
JERUSALEM.

Date 10th Aug., 1943.

To: Messrs. Iron Stores,
Tel Aviv.

Defence Regulations, 1939.

In accordance with Order/s of a Competent Authority dated 22.2.42.

you are hereby authorised to dispose of the undermentioned materials to Asst. District Commissioner, Tulkarem.

This permit is not valid after 11 SEP 1943 on which date it must be returned to the Competent Authority if the authorised sale has not been effected. If part only of the materials are sold the permit must be returned for amendment. If and when any sale has been effected a certified invoice shall be forwarded to the Competent Authority in accordance with Order dated 22-2-1942. Failure to comply with these instructions will constitute an offence under the Defence Regulations, 1939.

IMPORTANT: PLEASE READ INSTRUCTIONS CAREFULLY!

joist 3.20 x 32 x 14 cms.

PERMIT MUST BE USED WITHIN 30 DAYS.
NO EXTENSION OF VALIDITY WILL BE GRANTED

P44

R T
14/8.

Copy to: Asst. District Commissioner,
Tulkarem.
Ref: letter TUL.156/44 of 31.7.43.

(Sgd.) E. KEMPINSKI.
CONTROLLER OF HEAVY INDUSTRIES.
COMPETENT AUTHORITY.

8.

GPP 16501—50,000 23.11.42—2178 A/S.

No.TUL.156/44.

Assistant District Commissioner's Office,
Tulkarm.

31st July, 1943.

Controller of Heavy Industries,
Jerusalem.

Subject :- Repairs to Tulkarm Water Supply.
Ref'nce :- Your 46/10 of 26th July, 1943.

The District Engineer, Nablus, has agreed to accept the joist measuring 3.20 x 32 x 14 cms. stocked by Messrs Iron Stores, Tel-Aviv.

2. I thank you for your assistance in this matter and will be grateful if you will now issue the Tulkarm Municipality with a permit for the release of the joist in question to enable them to carry out the necessary transaction.

P.113

(Sgd.) J. M. MONTGOMERY
Assistant District Commissioner,
T u l k a r m.

1.1030
K 5

Copy to :-
District Engineer, Nablus.
ref. telephone conversation of 30.7.43.
Chairman, Municipal Commission, Tulkarm,
ref. his 85/5 of 6th July, 1943.

P.39

156

GOVERNMENT OF PALESTINE.

IN REPLY PLEASE QUOTE

No. 46410

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
28 JULY 1943
TULKARM

CONTROLLER OF HEAVY INDUSTRIES
AND
DIRECTOR OF WAR PRODUCTION
P. O. B. 661 – TELS. 4427 & 4452
JERUSALEM.

26th July, 1943.

Assistant District Commissioner,
Tulkarm.

P. 42

Subject: Repairs to Tulkarm Water Supply.

Reference: Your TUL.156/42 of 14.7.43.

I regret that I have no supplier in my records for a joist of identical dimensions with that obtained from District Engineer, Nablus.

The nearest size available is of 30 cm. from Mr. Antoine Bost, Bost Street, Jaffa, or of 32 cm. from Messrs. Iron Stores, Jaffa-Tel Aviv Road, Tel Aviv.

H [signature]

f. CONTROLLER OF HEAVY INDUSTRIES/
COMPETENT AUTHORITY.

R
R
[initials]
28/7.

12.

See P44

٢٧ اضيف البندان الجديدان التاليان كبندين ١٥٠ و١٥١:—

الاعلان المؤرخ في ١ آب سنة ١٩٣٤ والمنشور في الوقائع الفلسطينية بعددها المؤرخ في ٩ آب سنة ١٩٣٤

«١٥٠ السدادات الزجاجية لمرتبانات الفواكه

١٥١ الآلات والاجهزة والمواد الاساسية لمعامل المواد المحسنة للطعم والارواح ، المعدة للتصدير فقط»

٢٨ اضيف البندان الجديدان التاليان كبندين ١٥٢ و١٥٣:—

الاعلان المؤرخ في ٢٢ آب سنة ١٩٣٤ والمنشور في الوقائع الفلسطينية بعددها المؤرخ في ٣٠ آب سنة ١٩٣٤

«١٥٢ برونز الفوسفور

١٥٣ تيتانيوم»

٢٩ اضيف البند الجديد التالي كبند ١٥٤:—

الاعلان المؤرخ في ٣٠ آب سنة ١٩٣٤ والمنشور في الوقائع الفلسطينية بعددها المؤرخ في ٣١ آب سنة ١٩٣٤

«١٥٤ الورق الرقيق (كريب) المستورد في لفافات للصناعة على ان لا يقل طول اللفافة الواحدة عن ٥٠٠ متر»

٣٠ اضيفت البنود التالية كبنود ١٥٥ لغاية ١٦٤:—

الاعلان المؤرخ في ١٣ تشرين الثاني سنة ١٩٣٤ والمنشور في الوقائع الفلسطينية بعددها المؤرخ في ١٥ تشرين الثاني سنة ١٩٣٤

«١٥٥ الفحم الحجري

١٥٦ الصلصال

١٥٧ الريش

١٥٨ الحطب

١٥٩ الشعر ، ما عدا شعر الحيوانات

١٦٠ حشيشة الدينار

١٦١ اشرطة الفانوس السحري

No.TUL.156/4

Assistant District Commissioner's Office,
Tulkarm.
14th July,1943.

Controller of Heavy Industries,
Jerusalem.

P31 / P29

Subject:- Repairs to Tulkarm Water Supply.
Reference:-My TUL.156/29 of 8/5/43, and your letter No.46/10 of 17th May,1943.

It has unfortunately been impossible to carry out the promise of repayment in kind referred to in my above letter as no girder of these exact measurements is obtainable.

2. As the District Engineer,Nablus insists upon the replacement of the joist lent by him by one of identical dimensions (i.e.3.20 m x- 35 x 14 cms) I shall be very grateful for any assistance you can give in locating such a joist anywhere in Palestine or adjacent territories.

3. The promise of replacement was made in good faith by the Municipality of Tulkarm who did not realise the difficulties involved and who are prepared to purchase the required girder at any price if one is to be found.

(Sgd.) J. M. MONTGOMERY
Assistant District Commissioner,
T u l k a r m.

5-331

See P.43

BF 31/7/43

No.TUL.156/41.

Assistant District Commissioner's Office,
Tulkarm.
14th July,1943.

(41)

District Engineer,
Nablus.

P.38

Subject:- Loan of P.W.D.materials.
Reference:-Your 3/1/1. of 24th June,1943.

I much regret that it has been impossible hitherto to carry out the promise made in good faith by the District Officer,Tulkarm, to return to you an iron girder exactly the same size as that lent by you for the repair of the Tulkarm water supply. It was not realised at the time that there would be such difficulty in procuring a girder of the required dimensions.

2. I enclose a copy of a letter received from the Chairman of the Municipal Commission of Tulkarm on the subject, in pursuance of which I am seeking the advice of the Controller of Heavy Industries with regard to the possibility of finding such a joist (for which the necessary release permit is already in the possession of the Municipality) anywhere in Palestine or adjacent territories.

(Sgd.) J. M. MONTGOMERY
Assistant District Commissioner,
T u l k a r m.

5-832

12 JULY 1943

GOVERNMENT OF PALESTINE

PUBLIC WORKS DEPARTMENT,
NABLUS.

No. 3/1/1.

7th July, 1943.

Asst. Dist. Commissioner,
Tulkarm.

Subject :- Loan of P.W.D. Materials.

Ref'nce :- My 3/1/1 dated 24th June, 1943.

May a reply to my above be given, please.

DISTRICT ENGINEER
NABLUS DISTRICT

49/HZ.

12 JULY 1945

GOVERNMENT OF PALESTINE

PUBLIC WORKS DEPARTMENT,
NABLUS.

No. 8/1/1.

7th July, 1945.

Asst. Dist. Commissioner,
Tulkarm.

Subject :- Loan of P.W.D. Materials.
Reference :- My 8/1/1 dated 24th June, 1945.

May a reply to my above be given, please.

DISTRICT ENGINEER
NABLUS DISTRICT

AB/NA.

No 85/5 39
6.7.43

Translation.

A. D. C. Tulkarm.

P.38

Subject:- Iron girder for water supply scheme.
Ref'nce:- Your No. 156/38/of 2.7.43.

When we took the iron girder from the P.W.D. the town was not provided with water, and it is our duty to follow the shorter way to repair the water supply scheme as soon as possible, however, we never thought that the iron girder of the same size could not be found in Palestine in order to purchase it and to return it back to the P.W.D.

2. We promised the D.O. to return an iron girder of the same size to the P.W.D., and our promise was given in good faith. All endeovers were made to trace an iron girder of the same size , and, however, when we'll trace one, we'll not delay in purchasing it, even if we found it outside Palestine, if that is allowed.

We shall be much grateful if any information is given to us about where such a girder could be found in any place in Palestine or in the adjacent territories , so that we may be able to purchase it by any price.


With Respects.


(Sgd) H. Jayyousi

CHAIRMAN,
MUNICIPAL COMMISSION TULKARM.

See P44

39





سعادة مساعد حاكم اللواء في طولكرم المحترم

P38

الموضوع :- جر الحديد لمشروع الماء

الاشارة :- كتابكم رقم ٤٢/١٥٦ تاريخ ٢/٧/٩٤٣

اخذنا جر الحديد من دائرة الاشغال العمومية في وقت كانت المدينة فيه خلواً من الماء وكان واجبنا المحتوم ان نتبع اقرب الطرق لاصلاح مشروع الماء باقصى سرعة مستطاعة . ولم يخطر لنا ببال اننا لن نجد جراً حديدياً من نفس القياس في فلسطين نشتريه ونعيده لدائرة الاشغال العامة .

قطعنا وعداً مع القائمقام باعادة جر من نفس القياس لدائرة الاشغال العامة . وكان وعدنا عن نية صادقة ، ونحن نسعى بكل جهدنا للعثور على جر من ذلك القياس ومتى وجدناه لن نتأخر عن شرائه لحظة ، حتى ولو استدعى الأمر الى جلبه من خارج فلسطين اذا تيسر ذلك . ونكون ممتنين جداً اذا اعطيت لنا معلومات عن وجود مثل هذا الجر في اي مكان في فلسطين او البلاد المجاورة حتى نستحصل عليه باي ثمن كان .

وتفضلوا بقبول فائق الاحترام

هاني الجوهري

رئيس لجنة بلدية طولكرم

See P44

38

GOVERNMENT OF PALESTINE

No. 3/1/1.

PUBLIC WORKS DEPARTMENT,
NABLUS.

Assistant District Commissioner, ~~18th~~ 24th June, 1943.
Tulkarm.

P. 37-156.

23 JUNE 1943

Subject :- Loan of P.W.D. materials.
Reference:- Your Tul 156/37 of 10.6.43.

The District Officer on 27.4.43 asked for the loan of the joist and promised to return one exactly similar. According to the promise I issued it, to oblige, and regret to note the promise given has not been kept.

2. Under the circumstances I cannot accept an alternative but must insist on the return of a piece the same size as lent. I have no authority to issue stores on loan and did so at my own personal risk, relying on the promise of the District Officer.

3. I would therefore be glad if you would hand over, against receipt, joist of the same size as borrowed to Foreman, Tulkarm and inform this office when the transaction is completed.

C.C. Copy to H.W. for information and necessary action.

See P. 39.

[signature]
DISTRICT ENGINEER
NABLUS DISTRICT

No. TUL.156/38.

Assistant District Commissioner's Office
Tulkarm.
2nd July, 1943.

His Worship,
The Mayor of Tulkarm.

For information and necessary action.

(Sgd.) L. M.

Assistant District Commissioner.
T u l k a r m.

./JK.

5-686

B.F. 14/7/4

No.TUL.156/37.

37

Assistant District Commissioner's Office,
Tulkarm.

10th June, 1943.

District Engineer,
Nablus.

P36

Subject :- Loan of P.W.D. materials.
Ref'nce :- Your No.3/1/1 of 5th June, 1943.

A permit No.SE/1105/D was issued by the Controller of Heavy Industries to Tulkarm Municipality to purchase "one iron girder 3.20 mx35x 14 cms from Messrs Iron Stores, Tel-Aviv." Messrs Iron Stores have informed the Mayor that it is regretted that they have not the same measurement in stock but they have the size of 30 cms x 3.30 m.

2. I shall be grateful if you will inform me whether you are prepared to accept the girder of 30 cms x 3.30 m instead of the girder which you kindly issued to the Tulkarm Municipality for urgent repairs to the water supply, or alternatively whether you would accept payment in cash.

See P.38 - B.F. 30/6/43

(Sgd.) J. M. MONTGOMERY

Assistant District Commissioner,
T u l k a r m.

Copy to His Worship,
The Mayor of
Tulkarm.

S - 366

36

GOVERNMENT OF PALESTINE

PUBLIC WORKS DEPARTMENT,
No. 3/1/1. NABLUS.
5th June, 1943.

District Officer,
Tulkarm.

Subject :- Loan of P.W.D. materials.
Reference:- My 3/1/1 of 21st May, 1943.

Please inform me when I may expect the return of the Steel Joists.

R.A.R. C.C.

(signed)
DISTRICT ENGINEER
NABLUS DISTRICT

85/BS.

D.O. A copy of P.33 was sent as directed, and reply to it is returned

GOVERNMENT OF [illegible]

PUBLIC WORKS DEPARTMENT.
NAIROBI.

No. 3/1/1.

5th June, 1949.

District Officer,
[illegible].

Subject :- Loan of P.W.D. materials.

Reference:- My 3/1/1 of 21st Feb., 1949.

Please inform me when I may expect the return of the Steel plate.

DISTRICT ENGINEER
NAIROBI DISTRICT

SK/SS.

[illegible]

35

٥/٨٥
٧/٦/٩٤٤

156
7 JUNE 43

سعادة قائمقام طولكرم المحترم

P.33

الموضوع :- جسر الحديد لمشروع الماء

الاشارة :- كتابكم رقم ٧٧٢ تاريخ ٢٢/٥/٩٤٤

X بعد اعطاء سعادتكم تصريح شراء جسر الحديد من قياس ٢٥ سنتمتر لأية شركة مخازن الحديد المحدودة اجابت بان ليس لديها جسورة حديد من هذا القياس وان لديها جسراً من قياس ٢٠ سنتمتر لطول ثلاثة امتار و٥٠ سنتمتر.

ارجو الاستفسار من دائرة الاشغال العمومية عما اذا كانت توافق على اخذ جسر من قياس ٢٠ سنتمتر بدلاً عن الجسر المأخوذ منهم وفي حالة عدم موافقتهم ان يعلمونا عن ثمن الجسر حتى ندفعه او يبينوا لنا اية طريقة نستطيع بها مقابلتهم عن الجميل الذي صنعوه معنا في وقت حرج من حيث انقطاع الماء عن المدينة.

اعيد ضمناً اذا احتجتم التصريح المرفوع لدائرة مراقب الصناعات الثقيلة وعندما نجد جسراً توافق عليه دائرة الاشغال نتقدم بطلب تصريح جديد لشرائه

وتفضلوا بقبول فائق الاحترام

[signature]

رئيس لجنة بلدية طولكرم

c.c.

Pl. draft letter to P.W.D.

9/6

X بعد التصريح للبلدية طلبنا بالتلفون

[signature]

٢٢/٧/٩٤٤

See P 37

Folio 31 refer please

34

156

No.515

2 8 MAY 1943

GOVERNMENT OF PALESTINE

DISTRICT COMMISSIONER'S OFFICES
SAMARIA DISTRICT, NABLUS

27th May, 1943

Asst.Dist.Commissioner,
Tulkarm

P.30

Subject:- Tulkarm Water Supply
Reference: Your TUL.156/30 of 19-5-43.

I refer to our meeting with the Mayor of Tulkarm on 25-5-43. I understood from him that he would make the next move about the purchase of a diesel engine by sending in plans and costs. I will take no action till I hear from you again.

R Chinnel

ACTING DISTRICT COMMISSIONER

Copy to H.W. for info. and necessary action.
28/5.

J. No. 240

B.F. on 30/7
25/6
BE.

No. TUL. 156/34.

Tulkarm.
28th May, 1943.

His Worship,
Mayor of Tulkarm.

For information and necessary action.

(Sgd.) J. M. MONTGOMERY

Assistant District Commissioner,
T u l k a r m.

GOVERNMENT OF PALESTINE

---

156 MR.

PUBLIC WORKS DEPARTMENT,
NABLUS.

No. 3/41

21st May, 1943.

District Officer,
Tulkarm.

Subject :- Loan of P.W.D. materials.

I shall be glad to be informed as to when it is proposed to return the Steel joist loaned to you for work on the Tulkarm Municipal Water Supply on 27.4.43.

c.c.

H.E. send copy
H.W. for report

DISTRICT ENGINEER
NABLUS DISTRICT

58/BS.

5-No-219

No. 85-5

(Translation). 23.5.43.

Foreman i/c

P.W.D., Tulkarm.

On 22.5.43 the labourers of your Department have drawn water from the pipe which is used only for filling up of street watering car without obtaining a permission from this office. Consequently they have broken the pipe and damaged the top of 2 inches. This is the second time that your labourers have tresspassed on the water supply scheme.

2. I hope you will take the necessary action against the person who caused this tresspass and such action should not be occurred in future, as the municipality shall not forgive if such act is repeated.

(sgd) Hashem Jayoussi
Chairman,
Municipal Commission, Tulkarm.

Copy to A.D.C. for info.

585



حضرة مهندس دائرة الاشغال العمومية بطولكرم المحترم

ان عمالاً من دائرتكم أقدموا يوم ٢٢/٥/١٩٤٢ على أخذ البلاط من الانابيب التي تمر من ساحة السيارات في الشوارع دون ان يأخذوا اذناً من البلدية فكسروا الماسورة واتلفوا حنفية من قياس انش ونصف. وهذه هي المرة الثانية التي يعتدي بها عمال دائرتكم على مشروع ماء البلدية. آمل ان تتخذوا الاجراءات اللازمة ضد المسبب لهذا الاعتداء وان تعملوا لعدم وقوعه في المستقبل، لأن البلدية سوف لا تتسامح مرة اخرى اذا تكرر مثل ذلك العمل.

وتفضلوا بقبول فائق الاحترام

[signature]

رئيس لجنة بلدية طولكرم

٢٢/٥/١٩٤٢

نسخة لسعادة ساعد حاكم اللواء في طولكرم المحترم

31

GOVERNMENT OF PALESTINE.

IN REPLY PLEASE QUOTE

N. 46/10

CONTROLLER OF HEAVY INDUSTRIES
AND
DIRECTOR OF WAR PRODUCTION
P.O.B. 661 - TELS 4427 & 4452.
JERUSALEM.

22 MAY 1943
TULKARM

17th May, 1943.

Assistant District
Commissioner's Office,
Tulkarm.

Subject :- Defence Regulations, 1939 -
Reference:- Your letter No. TUL.156/29 of 8-5-43.

(P. 29

The amended permit SE 1105/D is returned to you --- herewith.

P. M. Ward

f. CONTROLLER OF HEAVY INDUSTRIES
COMPETENT AUTHORITY.

15.

F. (of last line + original to H.W. myself). 22/5

בזה) וסומן בסעיף 27 א:—

„רישום העברות של שעבודים לפני יום עשרים וששה בפברואר, 1935.

27 א. כל העברה של שעבוד שבידי אגודה רשומה עפ״י סעיף 26 (1) מפקודה זו, ואשר נרשמה אצל פקיד המחוז של הנפה אשר בה מצוי הנכס הכלול בשעבוד, מיום עשרים ושבעה בדצמבר, 1933, ואילך, אך לפני עשרים וששה בפברואר, 1935, דינה כדין העברה בת תוקף מלא, ואפילו אם לא נרשמה אותה העברה אצל הרושם".

סעיף 28 הוחלף בסעיף הבא:—

„שעבודים שהטילו אגודות על נכסיהן הן.

28.—(1) אגודה רשומה תהא זכאית, מתוך התחשבות בכל הגבלה או הוראה מצמצמת שבתקנותיה, לעבוט את נכסי המטלטלין שלה ולמשכן או לשעבד את נכסיה, כולם או מקצתם, בין מטלטלין ובין מקרקעין, בין שהיא מחזיקה בהם ובין שהיא תובעת זכות עליהם, בין בהווה ובין בעתיד, לרבות הון מניותיה שעדיין לא נפרע, אם יש הון כזה, ואת שם העסק שלה, בתורת בטחון לחובותיה, בין שבהווה ובין שבעתיד ובין שיהיו קיימים על תנאי, ע״י הוצאת אובליגציות בודדות או בסריות".

No.TUL.156/30. 30

Assistant District Commissioner's Office,
Tulkarm.

19th May, 1943.

District Commissioner,
Samaria District.

Subject :- Tulkarm Water Supply.

The recent partial stoppage of the Tulkarm water supply lasting for more than a week has not been an isolated occurrence and although emergency repairs have now been successfully completed they have acted only as a palliative, not as a radical cure. Such trouble will inevitably recur every rainy season until another motor and horizontal pump are fixed at the head of the Municipal well to replace the present electric motor at water level.

2. The present difficulty is that any sudden rise in the level of the water in the well is liable to flood the motor and cause a short circuit, incidentally causing serious damage to the motor itself which had recently to be sent to Jaffa for four days to be dried in an electric oven. By the insertion of an iron girder underneath it the motor has now been raised 36 cms but this is not sufficient to insure it against similar damage in the future.

3. The Civil Defence Adviser in his report of the 30th September, 1942, stated that "The purchase of a diesel engine and generator to provide an alternative to electric power has been proposed, and the Municipality is prepared to contribute LP 400 towards the estimated cost of LP 1,500." I am afraid that if the project is to go through, the Municipality will have to be prepared to make a bigger contribution than this. Nevertheless, in view of the Civil Defence Adviser's above quoted report and of the importance of ensuring a safe and adequate water supply for Tulkarm not only in an emergency but at all times, I recommend that Government be asked to assist to the fullest possible extent.

? Ask Ashbourne about it.

4. The Chairman of the Municipal Commission is so much alive to the importance of completing the new installation before next winter that he is prepared if necessary to meet the entire capital expenditure from Municipal Revenue (which will show an estimated surplus balance of LP 5975 as at 31.3.44.) but in view of the fact that many Government institutions, including the Wilson Brown Building and Civil Defence Services, not to mention the Army, stand to derive great benefit from the scheme I am inclined to think that this would be an unfair drain upon the Municipal resources especially in wartime when they may always be called upon to deal with a sudden emergency. Further, I should find it difficult, if the Municipal Commission were required to spend so large a sum on the improvement of the town water supply, to sustain the recommendation in my TUL.1210/5 of 15th May, 1943, that they be permitted the further heavy outlay involved in purchasing the building known as the Old Seraya for use as Municipal Offices.

(P. 5 of file No. 1210)

5. It is noteworthy that the present municipal water rate of 30 mils per cubic metre is a piastre lower than that of Nablus and Jenin. I have pointed out to Hashim Eff. that he can recoup to some extent on any capital outlay by raising the rate to 40 mils. He is very reluctant to apply such an increase to the whole municipal area but he feels (and I agree) that unless the Military are prepared to make a substantial capital contribution towards the installation he would be justified in asking them to pay four (as in Jenin) or even five piastres. The army are responsible for nearly one quarter of the monthly average water consumption. A further one eighth of the consumption is attributable to Government owned houses and offices.

The position may be simply stated in tabular form as follows :-

HB
[illegible]

5 No. 183

Consumer.	Average monthly consumption.	Cost at present rate of 30 mils	Cost at increased rate of 40 mils	Net increase in revenue to Municipality.
1. Whole Town (including 2 & 3).	4000 M 3	LP. 120	LP. 160	LP. 40
2. Army	800 M 3	" 24	" 32	" 8
3. Govt.	500 M 3	" 15	" 20	" 5

6. In the light of His Worship's representations I think that it will be better if possible to carry out the necessary works without any increase in consumers' rates and that Government and the Military should each assist the Municipality by making an equitable contribution to the capital outlay required. Failing the grant of such assistance I consider that the Municipality must be left to work out its own salvation by such increase in rates or other financial measures as it may think fit, but I shall be grateful if early approval may be given in principle to the acquisition by the Municipality of this urgently required machinery either with or without financial assistance.

[signature]

Assistant District Commissioner,
T u l k a r m.

B. ~~F. on 20/5/43~~ ✓ Discussed orally ~~[illegible]~~ by D.C., A.D.C. & H.W.

Purchase of new motor &c. will be recommended by D.C. but as an exclusive charge against Municipality. Plans now being drawn up by H.W. Water rate will be raised from 30 to 40 mils per M3 bringing in increased revenue of at least LP 500-600 p.a.

[initials] 25/5.

See P 34.

GOVERNMENT OF PALESTINE

[Per]mit No: SE 1105/D

To Messrs. Iron Stores,
Tel Aviv.

CONTROLLER OF HEAVY INDUSTRIES
P. O. B. 661
JERUSALEM.

Date 30th April, 1943.

- 6 MAY 43

Defence Regulations, 1939.

In accordance with Order/s of a Competent Authority dated 22.2.42.

you are hereby authorised to dispose of the undermentioned materials to Tulkarm Municipality.

This permit is not valid after 31 MAY 43 on which date it must be returned to the Competent Authority if the authorised sale has not been effected. If part only of the materials are sold the permit must be returned for amendment. If and when any sale has been effected a certified invoice shall be forwarded to the Competent Authority in accordance with Order dated 22-2-1942. Failure to comply with these instructions will constitute an offence under the Defence Regulations, 1939.

3.20 m x 35 X 14 cm

2 Iron Girders each ~~30 cms. x 1 m.~~

B 6/5

Covering permit for release by telegrams
Nos. 981 & 983 of 25.4.43.

CANCELLED

Copy to: Tulkarm Municipality.
" " A/District Commissioner,
Tulkarm.
Ref: telegram of 22.4.43. P-23

(Sgd.) [illegible]

CONTROLLER OF HEAVY INDUSTRIES.
COMPETENT AUTHORITY.

GPP.16601—20.000—28.11.42
S.

No.TUL.156/29. 29

Assistant District Commissioner's Office,
Tulkarm.

8th May, 1943.

Controller of Heavy Industries,
Jerusalem.

Subject :- Repairs to Tulkarm Water Supply.

Ref'nce :- Your Permit No.SE.1105/D of 30.4.43 authorising the release of 2 iron girders each 30 cms x 1 m. to Tulkarm Municipality by Messrs Iron Stores, Tel-Aviv.

Owing to some misunderstanding, the girders applied for should have been of 1½ metres length and in view of the urgency of the repairs to be carried out, a girder measuring 3.20 m x 35 x 14 cms was borrowed from the Public Works Department, on promise of repayment in kind, in order to save time.

2. I shall therefore be grateful if the above permit may be amended to read "Iron Girder 3.20 m x 35 x 14 cms" thus enabling the Municipality to fulfil their promise of replacement.

3. I return, in triplicate, the permit referred to above.

(Sgd.) J. M. MONTGOMERY

Assistant District Commissioner,
Tulkarm.

Copy to Chairman,
Municipal Commission,
Tulkarm.

S. No. 373

27

DUPLICATE

Permit No. PA 1789/D

GOVERNMENT OF PALESTINE

CONTROLLER OF HEAVY INDUSTRIES
P. O. B. 661
JERUSALEM.

- 6 MAY 1943

To: Mr. M. Burger,
Tel Aviv.

Date 30th April, 1943

Defence Regulations, 1939.

In accordance with Order/s of a Competent Authority dated 22.2.42.

you are hereby authorised to dispose of the undermentioned materials to Tulkarm Municipality.

This permit is not valid after 31 MAY 1943 on which date it must be returned to the Competent Authority if the authorised sale has not been effected. If part only of the materials are sold the permit must be returned for amendment. If and when any sale has been effected a certified invoice shall be forwarded to the Competent Authority in accordance with Order dated 22-2-1942. Failure to comply with these instructions will constitute an offence under the Defence Regulations, 1939.

3 kgs. Insulating Varnish.

6/5.

Covering permit for release by telegrams
Nos. 983 & 982 of 25.4.43.

Copy to: Tulkarm Municipality.
" " A/District Commissioner,
Tulkarm.
Ref: telegram of 22.4.43.

(-) W. A. Kirk
Sgd.
6 CONTROLLER OF HEAVY INDUSTRIES,
COMPETENT AUTHORITY.

GPP 16601—50,000—23.11.42

8.

Extract from Civil Defence Adviser's Report of the 3rd September, 1942.
(Page 41 of File No.124)

WATER SUPPLIES.

There are two reservoirs. "The purchase of a Deisel Engine and generator to provide an alternative to electric power has been proposed, and the Municipality is prepared to contribute LP 400 towards the estimated cost of LP 1,500."

There is a separate water supply at the Kadouri School, about one mile from the town centre, where there is also a swimming bath: though the level of the water in this is usually very low.

No. 81/5.

Municipality of Tulkarm.
25th April, 1943.

Asst.Dist.Commissioner, Tulkarm
Thro' District Officer, Tulkarm

Subject :- Water Supply Scheme - Tulkarm.

As a result of heavy rain fallen this year caused an increase of water in the municipal well, so that the water has reached the motor, and if the water entered into the internal wires of the motor no doubt it will be burnt.

2. Electrician Engineer has inspected the well and advised us that we should erect a new iron bridge over the present one at a height of 30 cms and the motor should be sent to Jaffa and be placed in the electric oven for a period of 3 days in order to efface the moistness. We have applied for a permit through you to purchase two iron gerders and paints and we hope that the erection of gerders and the motor will be completed within a week if all the required materials are available. The inhabitants of Tulkarm will suffer from the scarcity of water because there is no other spring in Tulkarm except the Municipal Well. The Govt. Depts. shall use the water now kept in reservoir.

x 3. I consider that the present water supply scheme to work on one motor will threat the town by continuous stoppage of water and will cause a great suffer in case of any damages occurred to the motor. It is necessary to fix another motor and horizontal pump as such pump will not be effected by the rising of the water from time to time. I have discussed this scheme with your predecessor to do an alternative scheme by fixing a deisel engine and generator the cost of which was estimated at LP 1500 and the Municipality should pay LP 400 and the remaining balance to be paid by the Army. (Pl. see F. No. 124 P. 41(ii) Water Supply) Sd. 3/5

I therefore beg to request that you may communicate with the authorities concerned to give a final decision in this respect as soon as possible and if ~~they~~ the authorities concerned agree, ~~to~~ work will be commenced forthwith or the municipality will be obliged to carry out a work to maintain the water problem to the interest of the inhabitants according to the funds which could be used from municipal revenue." x

With respects.

(sgd) Hashem Hayyousi,
Chairman,

Municipal Commission,
Tulkarm.

A.D.C.

I agree with the ~~proposal~~ of the chairman as at x. The present pump is liable to be damaged at any time. The purchase and existence of a deisal engine will help a great deal especially when both present engines go out of order as at present. We are liable to run out of water every winter with the present pumping system Sd. 3/5

? Not in summer.

بلدية طولكرم

صندوق البريد رقم ٩

التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة

رقم ٨١/٥

156

26/4

طولكرم في ٢٥/٤/١٩٤٢

سعادة مساعد حاكم اللواء في طولكرم المحترم

بواسطة سعادة قائمقام طولكرم المحترم

الموضوع :- مشروع الماء في طولكرم

يظهر بان كثرة الامطار التي هطلت هذه السنة ادت الى ارتفاع الماء في بئر البلدية الى علو لم يسبق له مثيل حتى صار الماء يلامس الموتور الكهربائي الذي يحترق حتماً اذا وصل الماء الى اسلاكه الداخلية. طلبنا خبيراً كهربائياً فنياً بالاشتراك مع مأمور صيانة البلدية الموتور من البئر وتم الرأي على وضع جسورة حديد بارتفاع ٧٠ سنتمتراً فوق قاعدة الموتور الحالية وتركيب الموتور فوق الجسورة الجديدة وان يوضع الموتور لمدة ثلاثة ايام بالفرن الكهربائي لازالة الرطوبة منه. وقد أرسل الموتور للفرن وطلبنا تصريحاً لشراء جسورة الحديد والدهان اللازم للموتور بواسطة سعادتكم. والأمل ان يتم تركيب الجسورة واعادة الموتور للبئر والمباشرة بسحب الماء خلال اسبوع اذا سارت الامور مجراها الطبيعي وبدون تأخير في التصريح بالمواد المطلوبة. ونظراً لعدم وجود مورد للمياه في طولكرم غير بئر البلدية فان السكان يعانون أزمة شديدة من قلة المياه ريثما يعود سير المشروع الى العادة. اما دوائر الحكومة فانها ستعتمد خلال هذه المدة على الكمية الموجودة في خزان الماء.

أرى بان بقاء مشروع الماء على حالته الحاضرة مقتصراً على موتور واحد يهدد البلدة دوماً بانقطاع الماء ومعاناة أزمات خانقة من جراء اي خلل يطرأ على الموتور، وانه من الضروري تركيب موتور آخر طلمبة عمودية لان هذا النوع من الطلمبات يلائم حالة البئر الموجودة ولا يتأثر من ارتفاع المياه في البئر بحجم واخر. ولقد بحثنا هذا الموضوع مع جناب مساعد الحاكم السابق وكان الاقتراح ان تركب على البئر طلمبة من هذا النوع تشتغل على الكهرباء ومع الديزل وقدرت التكاليف بمبلغ ٥٠٠ جنيه تدفع البلدية منها ٤٠٠ جنيه ويدفع الجيش باقي المبلغ.

وعليه ارجوكم ان تتصلوا مرة اخرى بالمراجع المختصة لاعطاء القرار النهائي بهذا الموضوع باقرب فرصة ممكنة فاذا تمت الموافقة عليه يباشر في العمل حالاً والا فان البلدية تكون مضطرة للقيام بعمل يؤمن حركة المياه لسكان المدينة بالدرجة التي تسمح بها حالتها المالية.

وتفضلوا بقبول فائق الاحترام

رئيس لجنة بلدية طولكرم

[signature]

25. APR 1943

מברק TELEGR[...]

This form must accompany any enquiry respecting this Telegram

يجب ان يرسل هذا النموذج مع كل استعلام بخصوص هذا التلغراف

יש לצרף את הטופס הזה לכל חקירה הנערכת בנידון המברק הזה.

Service Instructions	Govt	عمليات ادارية הוראות משרדיות
Handed in at	Jerusalem	سلم في נמסר ב
Time 11 30 الوقت הזמן	on 24/4	التاريخ ביום
Received at	12 11	وصل في נתקבל ב



TO Assistant District Commissioner Tulkarm — الى אל

983 your telegram 22nd released two T sections from iron stores 3 kilos insulating varnish from Burgess as requested inform municipality permit sc 1101/pa 1789/D follows

Competent Authority

Use the Express Delivery Services—

The undermentioned services are available:—

I. By special messenger all the way.

II. By special messenger after receipt at office of delivery, at request of sender.

III. By special messenger after receipt at office of delivery, at request of addressee.

Charges and further particulars may be ascertained at any Post Office.

استعمل خدمات التوزيع السريع —

تتوفر التسهيلات الاتية :—

١) بواسطة موزع خاص على طول الطريق

٢) بواسطة موزع خاص بعد الاستلام في مكتب التوزيع بناء على طلب المرسل

٣) بواسطة موزع خاص بعد الاستلام في مكتب التوزيع بناء على طلب المرسل اليه :

يمكن الاستعلام عن الاجور او عن اية تفاصيل اخرى من اي مكتب بريد

השתמש בשרותי הדואר למסירה מהירה (אקספרס).

השרותים דלהלן קימים:—

(א) על ידי שליח מיוחד לאורך כל הדרך.

(ב) על ידי שליח מיוחד, לאחר שנתקבל במשרד המסירה, לפי דרי[illegible]
השולח.

(ג) על ידי שליח מיוחד, לאחר שנתקבל במשרד המסירה, לפי דר[illegible]
המקבל.

פרטים נוספים בדבר המחירים וכו', אפשר להודע בכל משרד דו[illegible]

24

2 Iron guirders 30 cm.

I or]

length 1 metre each

---

3 Kilog. paint for

Dynamos

For raising the motor above

the water level.

—

[illegible]20
74
114
———
208

23

P.T. 4

Counter No.

Prefix | No. 6
Time | Words

PALESTINE POSTS; TELEGRAPHS & TELEPHONES.

A

دائرة البريد والبرق والتلفون في فلسطين

הדאר המברקה והשח־רחוק של פלשתינה (א״י).

Office Date Stamp

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
22 APR 1943
TULKARM

Sent to

at 12

by

THIS SPACE FOR USE IN THE CASE OF AN OFFICIAL TELEGRAM

I certify that this telegram is on the service of D. A. Dept.

Office of Origin and Service Instructions

(Sgd.) J. M. MONTGOMERY
A. D. C. Tulkarm.
Signature

Charges Paid

mils

To Heavy Industries , Jerusalem. الى אל

Reference telephone conversation with Chief Clerk please permit release to Tulkarm Municipality of two iron girders each thirty centimetres by one metre and three kilogrammes paint for urgent repairs to water supply. Please inform me earliest name of supplier and instruct him to supply goods on demand to representative of Tulkarm Municipality.

29193—6000 Pads—2/5/35—Com P.

Where is the reply? [initials] B.U. 4/5.

A.D.C. Tulkarm.

CONDITION.

This telegram shall be forwarded in accordance with the provisions of the Regulations with reference to Inland Telegrams made pursuant to the Post Office Ordinance No. 20 of 1930. and the provisions of such Regulations* shall be deemed to be binding between the Sender and the Postmaster-General.

* The substance of these Regulations will be found in the Post Office Guide.

شرط.

ترسل هذه البرقية طبقاً لنصوص قانون البرقيات الداخلية المندرجة في قانون البريد رقم ٢٠ لسنة ١٩٣٠ ونصوص هذا القانون* تنطبق على المرسل ومدير البريد العام.

*توجد خلاصة هذه القوانين في دليل البريد.

תנאי.

הטלגרמה הזאת תשלח בהתאם לתקנות בנוגע לטלגרמות הנשלחות בפנים הארץ לפי חקת הדאר מס׳ 20 מ־1930, והתנאים של התקנות הללו* יחשבו כמחייבים בין השולח והמנהל הכללי של בתי הדאר.

* תכן התקנות הללו אפשר למצא במדריך הדאר.

Name and address of Sender .... اسم المرسل وعنوانه
השם והכתבת של השולח

(Not to be telegraphed)
(לא לשלח ע״י הטלגרף) (لا يرسل كجزء من البرقية)

22

حكـــومة فلســطين .

دائرة قائمـقام طولكـرم .

رقم ـ ١٥٦

٣٠/١١/١٩٤٢

P. 18

سعادة رئيس بلدية طولكـرم المحترم .

الموضوع ـ تكرير المــاء .

بالاشارة الى كتابكم رقم ٨٥/٥ تاريخ ١٠/١١/١٩٤٢ المتعلق بطلب شراء المحلول لتكرار الماء . كلفت بان ارسل اليكم ثلاثة نسخ من النموذج المخصص للحصول على المواد المراقبة .

الرجاء بعد تعبئة المعلومات المطلوبة ارسالها بواسطة حضرة رئيس الصحة بنابلس من نسختين وتفضلوا بقبول فائق الاحترام .

(Sgd.) S. DEJANI

قائمـقام قضاء طولكـرم .

7/6.

21

DEPARTMENT OF HEALTH
GOVERNMENT OF PALESTINE
JERUSALEM.

Assistant District Commissioner,
Tulkarm. 28 NOV 1942

25 NOV 1942

P. 20

Subject :- Water Supply - Tulkarm.
Reference:- Your TUL.156/20 dated 17.11.42.

It would facilitate the procedure recommending release of the item required if the enclosed forms were completed by the Municipal Authorities and forwarded through the usual channels.

P 21A

Ask M.W. to forward thro' M.O.H.

28/11

DIRECTOR
MEDICAL SERVICES.

LE/V.

See P. 22

Encl. 3

TO BE SUBMITTED IN DUPLICATE THROUGH THE S.M.O.

APPLICATION FOR THE RELEASE OF CONTROLLED MATERIAL.

Requiring the endorsement of the Director of Medical Services.

NAME OF APPLICANT ______________________________

(Block letters)

TOWN ______________________________

MATERIAL	QUANTITY.	NAME AND ADDRESS OF FIRM FROM WHOM PURCHASED WILL BE MADE.
1		
2		
3		
4		
5		

PURPOSE for which REQUIRED.

I declare that the above controlled materials are essential for the purpose stated, that it is the minimum required and no other material can be substituted.

Date ________________ ________________ Signature of Applicant.

Endorsement of Senior Medical Officer, ____________ District.

(Recommended
(NOT recommended.

STATE REASON

Date ________________ ________________ Signature Senior Medic

FOR USE BY DIRECTOR OF MEDICAL SERVICES

NO ________

Controller of Heavy/Light
Industries, Jerusalem.

The above application is transmitted for considerati
Release of controlled material as indicated above is
recommended.

I hereby certify that the purpose for which the mater
is required is essential for the safeguarding of the health
of the population.

DIRECTOR
MEDICAL SERVICES.

Date ________________

No. TUL. 156/20. 20

Assistant District Commissioner's Office,
Tulkarm.

17th November, 1942. P. 18

Director of Medical Services,
Jerusalem.

P. 19

Water Supply - Tulkarm.

I forward an application received from the Chairman, Municipal Commission, Tulkarm, together with a certificate from the Medical Officer of Health, Tulkarm, applying for permission to purchase 120 litres of sodium Hypochlorite monthly from Dr. Weigert.

2. The requirements appear necessary for safeguarding the health of the population, and if you agree, I should be grateful if you could forward the application with a certificate to that effect to the competent authority in accordance with the provision of paragraph III (b) of the General Rules for control of materials issued with Chief Secretary's Circular No. WSB/243/41 of the 16th of January, 1942.

(SGD.) ROWAN REEVES

Assistant District Commissioner,
T u l k a r m.

See P. 21

This is to certify that "Sodium Hypochlorite" is required for the chlorination of the Water Supply of Tulkarm town.

The water has proved on many repeated examination to be contaminated and far below the standard; Hence a chloronance for chlorination has been installed for the purpose by the municipality of Tulkarm.

(sgd) A. Khartabil.

M.O.H.,
Tulkarm.

14.11.42.

18

بلدية طولكرم ٠

صندوق البريد ـــ ٦

التلفون رقم ـــ ١٥

رقم ـــ ٥/٨٥

طولكرم في ١٠/١١/١٩٤٢

سعادة مساعد حاكم اللواء في طولكرم المحترم ٠

الموضوع ـــ تكرير الماء ٠

بما ان المحلول الذى نستعمله لتكرير الماء وهو (هايبوكلورايت الصوديوم)

قد اصبح مراقبا لا يمكننا ان نحصل عليه الا بتصريح من مراقب الصناعات الثقيلة وحيث ان الاستهلاك الشهرى من هذا المحلول لتكرير الماء في طولكرم يبلغ (١٢٠) لترا فاني اكون ممتنا جدا اذا استحصلتم لنا على تصريح بشراء (١٢٠) لترا كل شهر من الدكتور ويكرت في تل ابيب وتفضلوا بقبول فائق الاحترام ٤

رئيس لجنة بلدية طولكرم
(امضاء) هاشم الجيوسي ٠

(Translation).

Tulkarm Municipality.
10.11.42.

A. D. C., Tulkarm.

Subject :- Chlorination Plant.

The sodium Hypochlorite which is used for chlorination plant is becoming controlled and we are unable to obtain unless a permit from the Controller of Heavy Industries is issued.

As the monthly requirements are 120 litres I shall be grateful if you will arrange for a permit for the purchase of 120 litres every month from Dr. Weigert of Tel-Aviv.

With respects.

(sgd) Hashem Jayousi.
Chairman,
Municipal Commission,
Tulkarm.

See P. 22

259

DISTRICT OFFICES, JENIN.
24th. August, 1942.

17

DISTRICT COMMISSIONER,
SAMARIA DISTRICT, NABLUS.

Subject :- Chlorination of Jenin Water Supply.

The S.M.O. Samaria has advised the Jenin Municipality to establish a chlorination plant for the public water supply. He stated that the Tulkarm Municipality have recently purchased a suitable chloniration plant for the sum of LP.150.-

2. The Mayor of Jenin has pointed out to me that water supplied to the Wilson Brown building and to the Military Camp by the Jenin Railway Station, is already chlorinated. Householders in the town can only obtain water at certain fixed times and it is necessary for them to store this in privately owned tanks. A supply chlorinated at the source would, therefore, be liable to suffer contamination before it was consumed in existing circumstances.

3. The Mayor does not consider that the Municipality would be justified in incurring expenditure on a chlorination plant at present and I am in agreement with his views. If, in the future, another camp (or community) wishes to draw a piped supply direct from the source, then the Mayor considers that the Municipality should establish a chlorination plant for this purpose and I am asking him to obtain detailed data for the purpose of estimating the cost.

4. I would not advise the installation of a chlorination plant unless it seemed probable that its total cost could be recouped within six months.

(Sgd.) L. T. STEVENSON

ASST. DISTRICT COMMISSIONER,
J E N I N .

LTS/TK.

Copy to:- A.D.C. Tulkarm
S.M.O. Samaria, Nablus
His Worship the Mayor, Jenin.

2/8

water Supply - Tulkarm

81/5. (Translation.) Tulkarm Municipality,
20.7.42.

A - D.C. Tulkarm

Subject :- Chlorination Plant.

The fixing up of the chlorination plant has now been completed. On 18.7.42 the Public Health Engineer reported to inspect the plant and submit[redacted] his report, but I understood from him verbally that he found the chlorination plant good, and he will inform us about his consent in order to take over the plant.

Therefore, the water become clean in Tulkarm, with the approval of the Public Health Department. With respects.

(Sgd). Hashem Jayyousi.
Chairman,
Municipal Commission,
Tulkarm.


F.M.
2/7.

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٥/٨١

٢٠/٧/١٩٤٢



سعادة مساعد حاكم اللواء في طولكرم المحترم

الموضوع: آلة تكرير الماء Chlorination Plant

لقد تم تركيب آلة التكرير مع مشروع الماء لبلدية طولكرم وحضر مهندس الصحة بتاريخ ١٨/٧/١٩٤٢ لفحص الآلة وتقديم تقريره عنها. وقد فهمنا منه شفهياً بانه وجد آلة التكرير جيدة وبانه سيبعث الينا بموافقة على تسلم الآلة. اذن فقد اصبح الماء في طولكرم نظيفاً بموافقة دائرة الصحة.

وتفضلوا بقبول فائق الاحترام

رئيس لجنة بلدية طولكرم

P.T.O

15

8/92/12

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
17 JUNE 42
156

OFFICE OF THE CONTROLLER OF
HEAVY INDUSTRIES &
DIRECTOR OF WAR PRODUCTION
P.O.B. 661
JERUSALEM

15 June, 1942

Asst. District Commissioner,
Tulkarm

P.9

Subject : Defence Regulations, 1939 - Application by Tulkarm Municipal Commission for the release of pipes

Reference: Your TUL.156/9 of 2.6.42

I am unable to give consideration to this application as it is not supported by a certificate of essentiality as laid down by the War Supply Board rules

D. H. Shaw

f. CONTROLLER OF HEAVY INDUSTRIES
COMPETENT AUTHORITY

Advise M.W. accordingly

[initials] 17/6.

N6


The formal [initials] 22/6/42

Tulkarm

T/4

Gen. 5

ON HIS MAJESTY'S SERVICE



14

H. 33/11.

Haifa, 15th. June, 1942.

Assistant District Commissioner,
Tulkarm.

P6

Subject :- Water Supply - Nur Esh Shems Quarry.

Reference :- Your TUL.165/6 of 18.3.42.

Delay in replying to your letter is regretted. Your proposal would mean leaving Rail water tanks at Tulkarm which does not work in with the Railways' traffic arrangements.

The situation is somewhat better now as regards travelling tanks. Work is still proceeding on the shallow well in the wadi but it is very doubtful if any water will be found.

The real solution is a pipe line from Tulkarm but it is at present out of the question to get piping.

R.2
on
17/6

J.A.R.

DISTRICT ENGINEER.

Form

92 . No. Code No.

ON HIS MAJESTY'S SERVICE

Gen. 5a.

R.at. District Commissioner

Lydda

16-6-42

HAIFA 8 PM 16 JU 42

DEDUCTIONS							Net amount payable			
Medical Fees	Losses & Damages	Arrested Wages				Total Deductions	Bank Transfer	Cash Payment	Signature or Thumb Print	Envelope Number
21	22	23	24	25	26	27	28	29	30	31
						3 420				AP58 D59a
						3 180				
						3 300				
						3 420				
						3 420				
						4 41				
						3 300				
						3 360				
						27 ~~419~~ 421				

Calculations checked

for Chief Accountant | Signature of Paying Officer | Witness

Date | Date | Date

No. TUL. 156/13.

Assistant District Commissioner's Office,
Tulkarm.

~~16~~ 16 June, 1942.

Sir,

I am directed to transmit for your information a copy of the letter received from the Superintendent of the Line concerning the Water Supply to Railway Station and Nur Esh Shams.

P 12

I have the honour to be,
Sir,

Your obedient servant.

(Sgd.) ... DEJANI

District Officer,
Tulkarm.

The Chairman,
Municipal Commission,
T u l k a r m.

		TOTAL المجموع ס״ה		

2. It is requested that the cheque be crossed

٢ وارجو ان تسطروا الشك

2. אתה מתבקש לשרטט את השיק

drawn to order

او ان تسحبوه لامر

או למשוך אותו לפקודת

Specimen signature of payee:

صورة توقيع المستلم דוגמת החתימה של מקבל התשלום

CLAIMANT.

المدعي התובע

Date

التاريخ

התאריך

RECEIPT BY PAYEE.

ايصال من المستلم קבלה מאת מקבל התשלום

Received by cheque the sum of

Pounds Palestine Mils in payment of the above claim.

استلمت شكا بقيمة جنيه فلسطيني و ملا وفاء لما هو مذكور اعلاه

קבלתי עפ״י שיק את הסכום פונטים פלשתינאיים (א״י) ו מיל בתורת תשלום התביעה דלעיל.

Date

التاريخ

תאריך

PAYEE

المستلم

מקבל התשלום

NOTE:— Payments on the authority of a Cheque Order Form may only be made by "crossed" cheque or cheques drawn "to order" Sub-Accountants may not issue "bearer" cheques.

تدفع الشكات بالاستناد الى اذن الصرف اذا كانت "مسطرة" او مسحوبة "للامر" ولا يجوز للمحاسبين ان يصدروا شكات مسحوبة "للحامل"

הערה:— מותר לשלם עפ״י טופס פקודת שיק רק שיק ״משורטט״ או שיק המשוך ״לפקודה״. אסור לסגנים למנהלי חשבונות להוציא שיקים למוכ״ז.

12

PALESTINE RAILWAYS

TELEGRAPHIC ADDRESS :
"TRAFFIC" - HAIFA.
CODE USED: "A.B.C." 6th. EDITION

Office of the Superintendent of the Line.

..........ENCLOSURES

HAIFA STATION 12th June, 1942.

IN REPLY PLEASE QUOTE

SL.2/102/21

Asst.District Commissioner,
Tulkarm.

15 JUNE 942
TULKARM

P6

SUBJECT :- Water Supply.
REFERENCE:- Your TUL.165/6 of 16.3.42.

The present arrangements for watering Tulkarm Station from the Khadouri School are satisfactory and it is not necessary to make a change.

2. We would give further consideration to the Municipality's offer in respect of Nur Esh Shams but the question of transport arises.

The laying of a pipe from Tulkarm Municipal supply to Nur Esh Shams at the expense of the Municipality is, it is presumed, out of question.

A.A.
15/6

JI.

SUPERINTENDENT OF THE LINE.

Copy to:- District Engineer, Haifa.

Copy to:- D.T.S., Haifa.

Pl. inform M.O. of this result
15/6

See P.13

11

حكـــومة فلســـطين

دائرة قائمقام طولكرم　　　　　　　　　　رقم ١٥٦ ٠

١٩٤٢/٦/٤


١٥٠م

سـعادة رئيس بلدية طولكرم المحـترم ٠

المبحث ـ الماء المستهلك في المدارس ٠

بالاشارة الى كتابكم رقم ٥/٨٦ تاريخ ١٩٤٢/٦/٣ بخصوص دفع ثمن الماء المستهلك في المدارس بطولكرم من مال هيئة المعارف المحلية اخبركم انه سيبحث في هذه المسألة لدى اجتماع لجنة المعارف المحلية ٠

وتفضلوا بقبول فائق الاحـترام ٠



رئيس لجنة المعارف المحلية بطولكرم

أنني بهذا أعين . . . . من قرية

قضاء طولكرم عضواً في لجنة القرية


مساعد حاكم اللواء

طولكرم

بلدية طولكرم

صندوق البريد رقم ٩

التلفون رقم ١٥



الرجاء ان تذكروا عند الاجابة
رقم ٨٦/٥

طولكرم في ٢/٦/٩٤٢

سعادة رئيس لجنة المعارف المحلية في طولكرم المحترم

البحث :- الماء المستهلك في المدارس

اخذت كتاباً من حضرة مفتش المعارف المحلي فيه بانه لا تمكنه من دفع ثمن الماء الذي يستهلك في مدارس طولكرم اعتباراً من اول نيسان سنة ١٩٤٢ وذلك بناء على منشور حضرة السكرتير العام رقم E/٤٤/٤٠ تاريخ ٢٦/٨/٩٤٢ وبما ان المنشور المذكور ينص على ان هيئة المعارف المحلية هي التي تقدم الماء للمدارس مجاناً فاني ارجوكم ان تعلموني عما اذا كنتم توافقون على دفع ثمن ماء المدارس اعتباراً من اول نيسان ١٩٤٢ حتى نباشر بتقديم الفواتير الشهرية الى لجنة المعارف، مع العلم بان ثمن الماء يبلغ نحو ستة جنيهات في الشهر.

وتفضلوا بقبول فائق الاحترام

رئيس لجنة بلدية طولكرم

[signature]

No.TUL.156/9.

Assistant District Commissioner's Office,
Tulkarm,

2nd June, 1942.

Deputy Controller of Heavy Industries,
Public Works Department,
Jerusalem.

Materials for Water Supply Scheme - Tulkarm.

I forward a copy of an application received from the Chairman, Municipal Commission, Tulkarm, concerning the issue of a permit to purchase pipes required for the maintenance and enlargement of the Tulkarm Water Supply.

2. I should be grateful if you would arrange for the necessary permit to be granted.

(SGD.) ROWAN REEVES

Assistant District Commissioner,
T u l k a r m.

F. 11

GOVERNMENT OF PALESTINE.

CASH ORDER FORM.

To the Sub-Accountant,

I have to request that you will pay to ....

whose specimen signature is appended, the sum of ....

Pounds Egyptian .... Milliemes which is required to defray the wages or incidental expenses set out in the accompanying vouchers and in the shedule below:—

759—12000—19/12/25—G. C. P.

Date of Voucher	Department	Wages or Incidental Expenses	Amount	
			L. E.	m/ms

No. TUL.156/8.8

Assistant District Commissioner's Office,
Tulkarm,

19 May, 1942.

R S H

Sir;

I transmit for necessary action, a copy of the letter No. E/24/40 of the 26th. of January,1942, from Chief Secretary concerning the water supply for public schools.

I have the honour to be,
Sir,
Your obedient servant.

(Sgd) R. [signature]

Assistant District Commissioner,
T u lkk a r m.

The Chairman,
Municipal Commission,
Tulkarm.

(Copy).

[illegible]24/40.

GOVERNMENT OF PALESTINE. 8A

CHIEF SECRETARY'S OFFICE
JERUSALEM.
26th. January, 1942.

District Commissioner,
Samaria District.

I am directed to refer to the correspondence ending with your letter No. 767 of the 26th. September, 1940, and to inform you that after consideration of the matter in Executive Council it has been agreed in principle that the local education authority is liable, under Rule 59(d) of the Education Rules made under the Education Ordinance, 1933, to provide water gratis for public schools within its area whether or not it possesses a municipal water supply.

2. It is understood that there will be no difficulty in applying this principle to your district and I am to request you to take the necessary steps for its application with effect from the 1st. April, 1942.

(sgd) Ruhi Abdul Hadi.
for Chief Secretary.

Copy to: Director of Education.

No. 84/5
District Officer,
Tulkarm.

Heading, date?

7

The Tulkarm Municipality.
26.4.42.

Materials for Water Supply Scheme.

The Tulkarm Municipality require the following pipes and articles for use in the water supply scheme:-

~~White~~ Galvanize Iron pipes:	$\frac{1}{2}$	inch	500 metres.
Elbows	$\frac{1}{2}$	inch	200 in number.
joints	$\frac{1}{2}$	inch	100 in number.

I shall be grateful if you will arrange to obtain the necessary permit to purchase these pipes and materials from Jaffa and transport them to Tulkarm.

With respects.

(sgd) Hashem Jayyousi,
Chairman.
Municipal Commission,
Tulkarm.

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥

الرجاء ان تذكروا عند الاجابة
رقم ٨٤/٥

٢٦/٤/١٩٤٢

2 7 APR 1942

سعادة قائمقام طولكرم المحترم

الموضوع :- لوازم مشروع الماء

تحتاج بلدية طولكرم الى الانابيب والادوات الاخرى المبينة فيما يلي لاصلاح مشروع الماء في طولكرم وهي :-

انابيب بيضاء	½	انش	متر	٥٠٠	G.I. Pipes ½" φ
زوايا	½	"	عدد	٢٠٠	Elbows ½" φ
نفات	½	"	"	١٠٠	Joints ½" φ

اكون ممتناً اذا تفضلتم وسمحتم لنا على اذن لشراء هذه الانابيب والادوات محلياً ونقلها الى طولكرم . وتفضلوا بقبول فائق الاحترام

رئيس لجنة بلدية طولكرم

[signature]

No. TUL. 56/6.

Assistant District Commissioner's Office,
Tulkarm,
March, 1942.

District Engineer,
Palestine Railways,
Haifa.

Water Supply.

P.5

(5690) ROWLAND HILL

Referring to Nur esh Shams letter No. G.13/42 of the 14th. of March, 1942, addressed to A.S.P. i/c Central Prison, copy to you and me, the Tulkarm Municipality could supply water at its usual rate of 30 mils per metre 3 which rate is I understand considerably cheaper than that at present paid for water obtained elsewhere for Nur esh Shams.

2. I understand also that under existing arrangements it is not always possible for the Tulkarm Railway Station to obtain all the water required.

3. I therefore suggest for your consideration that the Palestine Railways obtain all their needs at Tulkarm Railway Station (including supplies for Nur esh Shams) from the Municipality which could deliver regularly as much water as will be required.

Rly won't play
PA

P.T.O. /2........

P 14

/2.

4. Could you kindly inform me shold you wish arrangements on these lines to be made ?

(SGD.) ROWAN REEVES

Assistant District Commissioner,
T u l k a r m.

Copy to: Chairman, Municipal Council, Tulkarm.
A.S.P., Central Prison, Jerusalem.

G.13/42. NUR ESH SHAMS.
14.3.42.

5

A.S.P. i/c.,
Central Prison,
Jerusalem.

Subject :- Water Supply.

During the week I have had difficulty in getting the proper supply of water tanks from the Palestine Railway's, for this J.L.C.

2. This E.L.C. allottment is 18 tanks per week, during this week only 10 tanks have been received, and today 14.3.42, there was a great shortage of water.

3. The Raileway Headquarters, Haifa, were informed about this, and the reply was, it was impossible for them to send the Camp water, owing to so much Military work.

4. At 3 p.m. today 14.3.42, the water supply run out, and I had to collect water from the running stream nearby and have it boiled for consumption, this was certainly a risk, but it was the next b best thing I could do.

5. However the Medical Officer, Tulkarm, arrived at the Camp at about 3.45 p.m., and made arrangements with the Municipality Tulkarm, to supply water. Medical Officer's report is attached.

Inspector i/c
Jail Labour Company No. 1.

Copy to :- A.D.C., Tulkarm.
M.O.H., Tulkarm.
D.E.P.R's. Haifa.

1935	,,	Scholey J	do
1898	,,	Crawford W.B.	do
1882	,,	Amos G.	do
1920	,,	McCloughlan M.	do
1899	,,	Daley G.	do
1826	,,	Garcia L.	do
1859	,,	Preece H.	do
1912	,,	Jones J.P.	do
1929	,,	Peisley F.	do
1866	,,	Smith A.E.	do
1823	,,	Farley L.	do
1846	,,	Lynas T.	do
1858	,,	Potts T.	do
1851	,,	Mitchell T.	do
1819	,,	Donnelley R.M.	do
1811	,,	Connerneen M.	do
1888	,,	Bird W.	do
1842	,,	Lambert W.L.	do
1812	,,	Cowley T.H.	do
1889	,,	Budd E.J.	do
1831	,,	Hickey L.	do
1940	,,	Townsend E.	do
1890	,,	Burnell A.G.	do
1884	,,	Bacon L.R.	do
1848	,,	Marsh N.A.S.	do
1801	,,	Batt S.	do
1861	,,	Renwick J.	do
1834	,,	Hothersall J.	do
1829	,,	Harrison H.	do
1816	,,	DeLooze W.	do
1802	,,	Basley E.	do

From Central Prison Acre to Jerusalem Urban division.

104	B/Const.	Maughan-Taylor D.B.M.	do

COPY.

5A

MEDICAL OFFICERS ' REPORT.

Visited the Camp on 14.3.42 and found that not a drop of water is available in the tanks of the Camp at 3 p.m. Arrangements were made to collect the water from the running stream nearby and have it boiled and distributed for consumption. This proceedure is certainly arisk and might spread dysentery in the Camp, and I have arranged to supply the Camp with two water cars amounting to 8 cubic metres from the main of Tulkarm, and using the Municipal water vehicle.

(Sgd). A. Khartabeel M.O.H. Tulkarm.

Losing through negligence:
1 kalpack black, w/blue top
2 buttons medium

Fined 220 mils, forfeits 220 mils

8896 Const. Raphael Moore
Losing through negligence:
1 pair title shoulder.
1 badge headdress No. 3.

Fined 75 mils, forfeits 75 mils

8239 Const. George Yanovski.
Losing through negligence:
1 badge headdress No.2

Fined 80 mils, forfeits 80 mils
(P.11/194/11/SG).

British Police

Nablus division

1519 B/Const. Bell T.
Losing through negligence:-
1 pair socks worsted grey.

Forfeits 45 mils, fined 45 mils.

1446 B/Const. Kydd C.T.
Losing through negligence:-
1 badge headdress P.P.
1 pair socks worsted grey.

Forfeits 75 mils, fined 75 mils.

0/ ١٨٧

H

ENCLOSURES.

PALESTINE RAILWAYS

ENGINEERING BRANCH

District Engineer's office

In reply please quote :

H.48/11 3.

~~Haifa~~ Station 11th July, 1941.

The Mayor,
Tulkarm.

SUBJECT :- Water Supply - Tulkarm Station. P.3 A
REFERENCE :- Your No.86/5 of 30-6-41 received 7th instant.

Your Worship,

Thank you for your letter and for explaining the position as regards water supplies at Tulkarm.

The Railway also is grateful for your assistance in supplying water for an engine which was held up.

Your letter has been passed to Chief Engineer, Railways, who is taking up the matter.

Yours faithfully,

[signature]

DISTRICT ENGINEER.

I understand from H.W. that he has discussed with Akram Bey (who supplies at present) & that he agrees Municip. would supply. [initials] 12/3.

ا- رئيس الكتبة: للحفظ ١٢/٤/٤٢




13 IV
41

No. 86/5 Tulkarm Municipality

30th. June, 1941 3

District Engineer,
Palestine Railways,
Haifa.

Subject:- Water Supply -Tulkarm Station.
Reference:- My letter No. 86/5 of 14.6.1941.

The Kadoorie Agric. School Tulkarm could not supply the water regularly similar to the system of Tulkarm water supply scheme. The British Army stationed at Kadoorie School is taken the water from Tulkarm water scheme and is not relying on the water from the school because it is always out of order. It was happend that on the evening of the last Saturday the train arrived and was in need of water , and ~~it was~~ the school water was not working, so the train delayed about 4 hours, and if the Municipality has not arranged for the water which was sent by the street watering car the train will delay more than 4 hours. If your Department desire to secure the water for use by the trains and Railway station regularly, it should be obtained from the Tulkarm Water Scheme, and there are no obejection to keep the pipes installed from the Agric School as precaution measure.

I am awaiting your urgent reply in this respect and it may the Municiplity will agree with other places to supply the water in large quantities, thus, the Municipality will not be able to make an agreement with your Dept.

With respects.

Sgd. Hashem Jayyousi

Chairman,
Municipal Commission.

75 3A

الرجاء ان تذكروا عند الاجابة
رقم ٥/٨٦

بلدية طولكرم

صندوق البريد رقم ٩
التلفون رقم ١٥



طولكرم في ١٩٤١/٦/٣٠

حضرة مهندس سكك حديد فلسطين المحترم – حيفا

الموضوع – ايصال الماء من مشروع بلدية طولكرم الى محطة طولكرم
الاشارة – كتابنا رقم ٥/٨٦ تاريخ ١٩٤١/٦/١٤

لا تستطيع مدرسة خضورى الزراعية فى طولكرم توزيع الماء بالنظام والاستمرار الذى يوزع به الماء من مشروع بلدية طولكرم . والجيش البريطانى الذى يخيم فى مدرسة الزراعة ياخذ ماءه من بلدية طولكرم لكونه لا يعتمد على الماء الذى تعطيه المدرسة . ولا تستطيع ادارة السكة الحديدية ان تعتمد على ماء مدرسة الزراعة لانه كثيرا ما يتعطل عن العمل . وقد صادف مساء السبت الماضى ان وصل قطار الى محطة طولكرم فى حالة نفاذ الماء منه وكان ماء مدرسة الزراعة معطلا فتاخر القطار عن موعده اربع ساعات ولو لم تبعث بلدية طولكرم بسيارتى ماء للقطار اوصلتهما اليه سيارة رش الشوارع لتاخر اكثر من ذلك . فاذا كانت ادارتكم ترغب فى تأمين اخذ الماء اللازم للقطارات والمحطة فى طولكرم بانتظام فما عليها الا ان تشترك بالماء من بلدية طولكرم وان تجعل اشتراكها هذا الاشتراك الاساسى الذى تعتمد عليه . ولا بأس ان تبقى خط الانابيب الممتد من مدرسة الزراعة من قبيل الاحتياط .

انتظر جوابكم العاجل بهذا الصدد اذ لربما ارتبطت البلدية بتوريد كميات كبيرة من الماء لجهات اخرى فلا تعود بحالة تمكنها من ان ترتبط مع ادرتكم . وتفضلوا بقبول فائق الاحترام .

رئيس لجنة بلدية طولكرم

[signature]

نسخة الى سعادة قائمقام طولكرم المحترم

2

Enclosures

PALESTINE RAILWAYS

ENGINEERING BRANCH

District Engineer's Office

In reply please quote:
H.33/11.

Haifa Station 21st June, 1939.

His Worship the Mayor,
Tulkarm.

SUBJECT :- Water Supply - Nur Esh Shams.

Your Worship,

I am informed that it may be possible to provide piped water supply for the Jail Labour Camp at Nur Esh Shams from your wells at Tulkarm.

If this is so I should be glad to know under what conditions this could be provided, the cost per M3 and the quantity available.

I should also like to know if this would be supplied at rail level or to the level of the Inspector's house tanks.

Yours faithfully,

In the meantime I understand Rlys buy water at Lydda for 100 mils/m3 (+ cost of transport)

[illegible] 13/7/42

[illegible]

DISTRICT ENGINEER.

[illegible]

G.N..

E. 8

GOVERNMENT OF PALESTINE

CHIEF SECRETARY'S OFFICE
JERUSALEM

2 FEB 1942

26th January, 1942

District Commissioner,
Samaria District.

I am directed to refer to the correspondence ending with your letter No. 767 of the 26th September, 1946, and to inform you that after consideration of the matter in Executive Council it has been agreed in principle that the local education authority is liable, under Rule 59(d) of the Education Rules made under the Education Ordinance, 1933, to provide water gratis for public schools within its area whether or not it possesses a municipal water supply.

2. It is understood that there will be no difficulty in applying this principle to your district and I am to request you to take the necessary steps for its application with effect from the 1st April, 1942.

(sgd) Ruhi Abdul Hadi

for Chief Secretary

Copy to: Director of Education.

767 31.1.42